Block E and G Pre-Design Soil Sampling Investigation Work Plan Lockheed Martin Middle River Complex 2323 Eastern Boulevard Middle River, Maryland

Prepared for:
Lockheed Martin Corporation
Prepared by:
Tetra Tech, Inc.
June 2012
Milal Mart
Michael Martin, P.G.
Regional Manager
DAME O
Dev Murali, P.G.

TABLE OF CONTENTS

<u>Sect</u>	<u>ion</u>	<u>Page</u>
ACR	ONYMS	iii
1	INTRODUCTION	1-1
1.1	BACKGROUND	1-1
1.2	OBJECTIVE	1-4
2	INVESTIGATION APPROACH AND METHODOLOGY	2-1
2.1	SITE ACCESS AND UTILITY CLEARANCE	2-1
2.2	DRILLING AND SAMPLING PROCEDURES	2-2
2.3	SAMPLE NOMENCLATURE AND HANDLING	2-3
2.4	DATA ANALYSIS	2-4
2.5	SURVEYING	2-4
2.6	EQUIPMENT DECONTAMINATION	2-4
2.7	WASTE MANAGEMENT	2-5
2.8	DATA VALIDATION AND REPORTING	2-5
3	TAX BLOCKS	3-1
3.1	BLOCK E PRE-DESIGN SOIL SAMPLING	3-1
3.2	BLOCK G PRE-DESIGN SOIL SAMPLING	3-2
4	PROJECT DELIVERABLES	4-1
5	REFERENCES	5-1

APPENDICES

APPENDIX A— HEALTH AND SAFETY PLAN

APPENDIX B— WASTE MANAGEMENT PLAN

LIST OF FIGURES

		Page
Figure 1-1	Middle River Complex Location Map	1-5
Figure 1-2	Site Location Map and Site Tax Blocks	1-6
Figure 3-1	Block E Pre-Design Soil Boring Locations	3-12
Figure 3-2	Block G Pre-Design Soil Boring Locations	3-13
	LIST OF TABLES	
		Page
Table 2-1	Sample and Analytical Summary	2-7
Table 3-1	Rationale for Proposed Soil Sampling	3-3
Table 3-2	Sampling Requirements	3-4

ACRONYMS

μg/kg micrograms per kilogram
 AST aboveground storage tank
 BaPEq benzo(a)pyrene equivalent
 bgs below ground surface

COC chain of custody

DPT direct push technology
DRO diesel range organics

EESH energy, environment, safety, and health

EGIS environmental geographic information system

EPA United States Environmental Protection Agency

GPR ground penetrating radar
GPS global positioning system
GRO gasoline range organics
HASP health and safety plan

IDW investigation derived waste

Lockheed Martin Lockheed Martin Corporation

mg/kg milligrams per kilogram
MRC Middle River Complex

PAH polycyclic aromatic hydrocarbon

PCB polychlorinated biphenyl PID photoionization detector

PPE personal protective equipment

RAP response action plan

REC recognized environmental condition

SAP sampling and analysis plan STP sewage treatment plant

TCLP toxicity characteristic leaching procedure

Tetra Tech, Inc.

TPH total petroleum hydrocarbons
UST underground storage tanks

This page intentionally left blank.

Section 1 Introduction

On behalf of Lockheed Martin Corporation (Lockheed Martin), Tetra Tech Inc. (Tetra Tech) has prepared the following work plan for conducting pre-design soil sampling at Blocks E and G at the Lockheed Martin Middle River Complex (MRC) in Middle River, Maryland (Figure 1-1).

1.1 BACKGROUND

Soil characterization sampling to date has consisted of soil samples collected in borings advanced to varying depths (i.e., variable vertical limits) throughout the areas of concern. Impacted soils at Blocks E and G are characterized by one or more constituents exceeding cleanup goals, as defined in previous sampling and analysis plans and reports. Historical soil sampling results are summarized below. Impacted soils may be encountered when excavation related to the installation of the proposed groundwater remedial systems in Blocks E and G occurs; therefore, additional soil sampling is needed to further characterize soils and delineate the extent of impacted soil in these areas.

Block E, located in the southern portion of the Middle River Complex, is 15.97 acres in size, and is bounded on the north by the industrial portion of the Middle River Complex (Block I), to the east by Parking Lot No. 6 (Block D), to the south by Waterfront Lot (Block F), and to the west by the Tilley Chemical Company (Figure 1-2). Block E consists of the three recognized environmental conditions (RECs), Former Building D (Recognized Environmental Condition #1), Product Pipeline (Recognized Environmental Condition #2), and Former 500,000-gallon above-ground storage tank (AST) and associated tanks (Recognized Environmental Condition #3).

Former Building D (Recognized Environmental Condition #1) encompasses approximately half of Block E. Although Building D was demolished in the early 1970s, the building's foundation and areas of the ground floor's slab are still present. The floor slab consists of concrete; ceramic tiles overlay the concrete in several locations. The construction joints or expansion joints exhibit signs of weathering (e.g., cracking) between the slabs.

The Product Pipeline (Recognized Environmental Condition #2) is a 1,815-foot long, two-inch diameter pipe that runs underground from the former 500,000–gallon fuel oil aboveground storage tank (AST) (i.e., Recognized Environmental Condition #3) to the Middle River Complex's Power Plant (located in Block I). The pipeline supplied fuel oil to the Power House. The location of the pipeline coincides with the location of a drainage ditch that runs along the western and southern boundary of Block E. A small portion of the pipeline has been removed, but the majority of the run was abandoned in place.

The former 500,000–gallon aboveground storage tank and its associated tanks (Recognized Environmental Condition #3) were located near the Fire Pump Building, in a grass-covered shoulder in the southwestern portion of Block E. The 500,000–gallon aboveground storage tank was surrounded by a shallow, grass-covered earthen berm. A large water tower and the Fire Pump Building were located adjacent to the aboveground storage tank.

Block E is bounded on all four sides with a chain-link fence. Several locked exterior gates are present in the northeastern corner of the unit. These gates limit access from the active industrial portion of the Middle River Complex to Middle River Complex employees.

Block G consists of 13.46 acres, and is located in the southwestern portion of the Middle River Complex on the southern side of Chesapeake Park Plaza. Block G is bounded on the north by Parking Lot No. 2 (Block H), to the east by Chesapeake Park Plaza, to the south by North American Electric, Inc., and to the west by Cow Pen Creek (Figure 1-2). Two Recognized Environmental Conditions in Block G were identified during a historical research investigation: Recognized Environmental Condition #11, the former Sewage Treatment Plant (STP)/Wind Tunnel Test Building/Vibration Test Building, and Recognized Environmental Condition #12, located in the southern portion of Parking Lot No. 3 (Tetra Tech, 2005a). Recognized Environmental Condition #12 corresponds to an area of disturbed ground surface observed in a 1964 aerial photograph within the southern portion of the Block G Parking Lot No. 3. The remaining portion of Parking Lot No. 3 is also included in Block G.

In the past, the area defined as Recognized Environmental Condition #11 contained a former Sewage Treatment Plant that consisted of five structures; the Wind Tunnel Test Building; the Vibration Test Building; two fuel oil underground storage tanks (USTs) located immediately

west of the test buildings; an unidentified structure in the vicinity of the Sewage Treatment Plant; and the Hydraulic and Fuel Test Building. With the exception of storm drain outfall 5 and the foundations of the former test buildings, there are no structures currently present on Recognized Environmental Condition #11. The foundations of the former Sewage Treatment Plant have been mostly removed; however, some remnants of building slab foundations still exist. A chain-link fence present along the Recognized Environmental Condition #11's northern and eastern perimeter prohibits unauthorized access, but Recognized Environmental Condition #11 is unfenced along its southern perimeter, which is shared with North American Electric, Inc. A locked gate along Chesapeake Park Plaza provides vehicle access to the area.

Parking Lot No. 3 is a flat parcel of land currently leased for truck trailer storage. A chain-link fence surrounds the parking lot on all sides prohibiting unauthorized access. A locked gate off of Chesapeake Park Plaza allows access to the southern portion of the parking lot.

Polychlorinated biphenyls (PCBs) are considered the primary risk drivers in soils at Block E. Surface soil samples in the Recognized Environmental Condition #1 area (Former Building D) contained the following chemicals at concentrations exceeding residential reuse-based cleanup goals: 1,2,3-trichlorobenzene, 1,2,4-trichlorobenzene, 1,4-dichlorobenzene, polycyclic aromatic hydrocarbons (PAHs) (expressed as benzo[a]pyrene equivalents, or BaPEq), polychlorinated biphenyls (Aroclor-1254 and Aroclor-1260), several metals, diesel range organics (DRO), and gasoline range organics (GRO). These constituents, plus 1,3-dichlorobenzene and naphthalene, were also detected at concentrations exceeding respective cleanup goals in subsurface soils at Block E. In the area of the proposed Block E groundwater remedy, polychlorinated biphenyls and benzo(a)pyrene equivalents have been detected in surface and subsurface soils at concentrations greater than their residential reuse-based cleanup goals.

Polycyclic aromatic hydrocarbons (as benzo(a)pyrene equivalents) are considered the primary risk drivers in soils at Block G. Contaminated soils in Block G also contain arsenic, hexavalent chromium, cobalt, diesel range organics and gasoline range organics at concentrations that exceed residential reuse-based cleanup goals. In the area proposed for the groundwater remedy at Block G, arsenic, gasoline range organics, and benzo(a)pyrene equivalents were detected in surface and/or subsurface soils at concentrations greater than their residential re-use-based cleanup goals.

1.2 OBJECTIVE

This investigation is intended to be a final soil sampling event to provide subsurface

characterization data in the areas to be excavated during a planned groundwater remediation

system installation on portions of Blocks E and G. Planned remedial activities for groundwater

are described in the 30% design package to be finalized by the end of May 2012.

The objective of the pre-design soil sampling is to collect and analyze soil samples for

characterization purposes in the areas to be excavated. An excavation depth of up to three feet

may be needed for the installation of the groundwater remedy systems. The soil samples

collected for the pre-design are necessary to determine where excavation may be needed,

because the soils surrounding the groundwater remedy systems must meet applicable regulatory

criteria. This data will be used to evaluate the disposition of soils in the planned groundwater

remedial area, and to help refine the limits of soil areas slated for excavation and offsite disposal.

This pre-design soil sampling work plan is organized as follows:

Section 2—Investigation Approach and Methodology: Presents the technical approach to the

pre-design soil sampling and describes the field methodology to be employed

Section 3—Tax Block Methodology: Describes the sampling methodology to be used in each

block

Section 4—Project Deliverables: Describes the content of the final report summarizing the


findings of this pre-design soil sampling investigation program


Section 5—References: Cites references used to compile this work plan


7854 TETRA TECH • LOCKHEED MARTIN MIDDLE RIVER COMPLEX • BLOCK E AND G PRE-DESIGN SOIL SAMPLING INVESTIGATION WORK PLAN



Source: Google Earth Pro, 2008







Investigation Approach and Methodology

Before soil sampling begins, appropriate Tetra Tech, Inc. (Tetra Tech) personnel will become familiar with the site-specific health and safety plan (HASP) and respective Safe Work Permits and emergency response plan included in the HASP. Tetra Tech will conduct mandatory health and safety tailgate meetings before each day's field events. The Tetra Tech site health and safety officer will document the topics covered and personnel in attendance. Safety requirements are addressed in detail in the site-specific Tetra Tech HASP, included as Appendix A.

2.1 SITE ACCESS AND UTILITY CLEARANCE

Field activities planned for the locations identified in Blocks E and G during this investigation will be coordinated with Lockheed Martin. Utility clearance work and documentation will conform to the provisions of Lockheed Martin's *Remediation Contractor's ESH Handbook, Revision 1*, June 10, 2009 (Lockheed Martin, 2009b), or the latest update. Each boring location will be cleared for subsurface utilities before any intrusive field activities. In addition to calling in a Miss Utility ticket for each investigation area, a third-party utility–locating service (Enviroscan) will be used to mark any underground utilities and anomalies in accordance with Lockheed Martin's CS-28 protocol and other procedures for intrusive work.

A geophysical survey will be conducted to locate and mark (with paint) all underground utility lines within a 30-foot radius of each designated drilling location. Enviroscan will use typical utility-locating equipment representing the best available technology, including a Fisher TW-6 electromagnetic pipe and cable locator/tracer, a Radiodetection C.A.T. and genny pipe and cable locator/tracer, a Radiodetection model RD4000 multi-frequency pipe and cable tracer, and a GSSI SIR-2000 ground penetrating radar (GPR) system. Borings that require relocation due to subsurface obstructions will be positioned as close as possible to the original location identified.

2.2 DRILLING AND SAMPLING PROCEDURES

Soil borings will be advanced at a maximum of 35 locations (25 locations at Block E and 10 locations at Block G are proposed) in targeted areas as presented in Figures 3-1 and 3-2; respectively. Soil borings will be advanced by a Maryland state-licensed driller using direct push technology (DPT) downward to the groundwater table, or a maximum depth of ten feet, at each block. Soil samples will be collected from three depth intervals in each boring using a 1.5-inch-diameter, four-foot long, stainless steel, macrocore sampler fitted with a disposable acetate liner. At Block E, due to the shallow groundwater table, soil samples will likely be collected over the 0 to 6 feet below ground surface (bgs) total depth range, with soil samples spanning the continuous depth of the boring. For example, soil samples may be collected at 0 to 2, 2 to 4, and 4 to 6 feet bgs. At Block G, samples may be distributed similarly, with depth, downward to the groundwater table, or a maximum depth of 10 feet. Soil samples at Block G will likely be collected from the 0 to 2, 2 to 6, and 6 to 10-foot depth ranges. At Block E, approximately 25 borings will be installed and soil samples collected within the area designated for future groundwater remediation. At Block E, an estimated 12 borings will be installed through the former Building D concrete slab and nearby impervious surfaces; therefore, concrete coring will be required. Care will be taken to keep concrete dusts that result from coring activities to a minimum. These borings will target the same depths as those described above, but if insufficient soil volume is recovered in a given sample interval due to the presence of concrete, then the soil sample depth interval will be adjusted by up to one foot, as needed.

At Block G, approximately 10 borings will be installed and soil samples collected within the area designated for future groundwater remediation. It is estimated that only three borings at Block G will be installed through concrete surface materials associated with former structures at REC #11 (e.g., the former vibration test building); thus, concrete coring will be required in Block G as well. As described above for Block E, if insufficient soil volume is recovered due to the concrete, the sample depth interval will be adjusted accordingly.

Soil samples retrieved will be screened to characterize their lithology and to record visual observations. Samples will also be screened with a photoionization detector (PID) using the zip-top bag screening technique. Soil samples from each one-foot depth increment will be retained for laboratory analysis. All soil boring locations will be identified using global

positioning system (GPS) technology. All pertinent information, including boring location, soil/lithology description, sample designation and depth, PID readings, sample collection time, etc. will be recorded on a soil sample log sheet and boring log form. Section 3 contains details regarding the intervals and analysis requirements for each block.

After lithologic logging and field screening are complete, soil from the designated sampling intervals will be collected and immediately placed in the appropriate sample containers. Sample jars collected will be labeled and placed on ice pending delivery to the analytical laboratory. Sample labels will include a unique sample number, date and time the sample was collected, name of the person handling the sample, and the specific analyses requested from the laboratory. After soil sampling, completed borings will be backfilled with bentonite chips to within 0.5 feet of the surface and then completed to grade with like material (i.e., soil, gravel, asphalt, and concrete).

2.3 SAMPLE NOMENCLATURE AND HANDLING

Each soil sample collected during this study will be identified with a unique sample identification tag. The sample identification tag will consist of the block designation, followed by "SB," and the boring number. Surface soils (0 to 1 foot below grade) will be designated "SS" and samples from other depths will carry a two–digit label indicating the bottom depth of the sampled interval. For example, a sample collected from 5 to 6 feet below grade at soil boring location 918 at Block G would be labeled as G-SB-918-5-6.

Sample handling includes field related considerations concerning the selection of sample containers, preservatives, allowable holding times, and analyses requested. Proper custody procedures will be followed throughout all phases of sample collection and handling. Chain of custody (COC) protocols will be used throughout sample handling to establish the evidentiary integrity of sample containers. These protocols will be used to demonstrate that the samples were handled and transferred in a manner that would eliminate (or detect) possible tampering. Sample containers will be released under signature from the laboratory and will be accepted under signature by the sampler(s) or responsible individual that maintains custody until the sample containers are transferred to the sampler(s). Transport containers returning to the laboratory will be sealed with strapping tape and a tamper proof custody seal. The custody seal contains the signature of the individual releasing the transport container, along with the date and time.

2.4 DATA ANALYSIS

Task-specific analytical requirements are outlined in Table 2-1 and as follows. All soil samples from Block E and Block G soil borings will be analyzed for total petroleum hydrocarbons (TPH)–gasoline range organics (–GRO) and diesel range organics (–DRO) by SW846 Method 8015B, and for polycyclic aromatic hydrocarbons (PAHs) by SW846 Method 8270B. All the samples collected from Block E soil borings will be analyzed for polychlorinated biphenyls (PCBs) by SW846 Method 8082. Ten samples from each site (Block E and Block G) will be analyzed for total priority pollutant metals (PP13) by SW846 Method 6010, hexavalent chromium by SW846 Method 7199, and pesticides by SW846 Method 8081 for waste characterization. Section 3 describes the intervals and analytical requirements for each sampling location. All samples will be analyzed within a standard, 21-day turnaround time.

2.5 SURVEYING

Each boring location will be surveyed using GPS technology with submeter accuracy. Final survey locations will be used for data reporting at the end of field sampling.

2.6 EQUIPMENT DECONTAMINATION

A decontamination area and a clean zone will be established at the perimeter of the restricted work zone to prepare and break down sampling equipment. The decontamination area will be established to contain decontamination rinsate solution for subsequent disposal. Reusable equipment (e.g., DPT rods, augers, scoops) will be decontaminated before and after each use. The decontamination process for reusable small equipment will consist of the following steps:

- Alconox[®] and potable-water wash
- potable-water rinse
- thoroughly wetted with a reagent-grade isopropanol rinse
- analyte-free water rinse
- air drying

Decontamination solutions will be collected for disposal. All downhole drilling equipment, including the rear of the DPT rig, will be steam-cleaned before arriving on-site; before beginning work; between drilling locations; any time the rig leaves and returns to a hole before completing a boring; any time the drill rig leaves the site; and at the conclusion of the drilling program.

2.7 WASTE MANAGEMENT

Investigation—derived waste (IDW), consisting of soil cuttings, concrete and asphalt pavement fragments, decontamination rinsate water, and personal protective equipment (PPE), will be generated during sampling. PPE IDW will be placed in trash bags and placed in a facility trash receptacle to be disposed of as general refuse. Soil cuttings (including pavement fragments) and decontamination water will be collected and stored in U. S. Department of Transportation (DOT)-approved 55-gallon drums. All drums will be appropriately labeled and logged on a drum inventory form. Wastes will be characterized and disposed of in accordance with applicable state and federal regulations, and the *MRC Waste Management Plan* (Appendix B). After generation, the drums will be relocated to a drum staging area as identified by Lockheed Martin personnel.

Samples of IDW will be collected and analyzed for organic, inorganic, and PCB compounds using the toxicity characteristic leaching procedure (TCLP). Upon receipt of the IDW analytical data, the generated IDW will be removed from the facility and properly disposed of in accordance with federal, state, and local regulations. A waste management plan conforming to Lockheed Martin Energy, Environment, Safety, and Health (EESH) *Remediation Waste Management Procedure No: EROP-03, Revision 4,* effective April 17, 2009 (Lockheed Martin, 2009a) is included as Appendix B.

2.8 DATA VALIDATION AND REPORTING

Laboratory data will be entered upon receipt into a sampling database and evaluated against cleanup goals for preliminary review. Data will consist of soil samples intended to refine both the vertical and lateral limits of soil contamination. This will be conducted as sequential data are recorded and clean samples are identified, as per project protocols. A limited data review, assessing data completeness, holding time, calibrations, laboratory and field blank contamination, field—duplicate precision, and detection limits, will be completed concurrent with the data evaluation.

Both the laboratory results and their subsequent evaluation will be shared with CDM Smith and Lockheed Martin as soon as they are available. Once the analytical data have been obtained from the laboratory, the data will undergo 100% data validation for all of the analyses mentioned above. Validation will be conducted using the U.S. Environmental Protection Agency's (USEPA's) Contract Laboratory Program protocol, (US)EPA Region III Modifications to the Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analyses (USEPA, 1993), and (US)EPA Region III Modifications to National Functional Guidelines for Organic Data Review, Multi-Media, Multi-Concentration (USEPA, 1994), in conjunction with method-specific criteria. Results reported for the sampling event will be included in a report with data summary tables.

Table 2-1

Sample and Analytical Summary 2012 Blocks E and G Pre-Design Soil Sampling Investigation Lockheed Martin, Middle River Complex, Middle River, Maryland

Location	Number of Soil Boring Locations each Block ⁽¹⁾	Number of Samples Per Boring	Total Number of Soil Samples	Number of Field Days	РАН	TPH-DRO/GRO	Total Metals ³	Hexavalent Chromium	PCBs	Pesticides
Block E	25	3	$75 + 3^{(2)}$	3	78	78	11	11	78	11
Block G	10	3	$30 + 2^{(2)}$	2	32	32	10	10	1	10
Total	35		110	5	110	110	21	21	78	21

Notes:

- (1) Maximum number of soil borings for each tax block.
- (2) Quality assurance (QA) samples are listed in the table above and will include field duplicate samples representing 5% of the total quantity of samples collected. Three duplicate samples will be collected at Block E, and two will be collected at Block G.
- (3) The U.S. EPA Priority Pollutant 13 metals list.

This page intentionally left blank.

Section 3 Tax Blocks

This pre-design soil investigation is being conducted to further delineate contaminated soil distribution in areas proposed for installation of the groundwater remedy systems. Characterization activities completed during this investigation are intended to determine the extent of soil contamination in these areas, so a remedial design specifying the limits of excavation can be properly developed. Sampling will not replace post-excavation verification sampling, which will be completed as specified in the final soil response action plans (RAPs) for Blocks E and G.

3.1 BLOCK E PRE-DESIGN SOIL SAMPLING

The area of proposed soil sampling for Block E is located in the southeast corner of the block, and corresponds to the area of the proposed Block E groundwater remediation system (refer to Figure 3-1). Twenty five soil borings (E-SB-886 to E-SB-910) are proposed at Block E; three soil samples per boring location will be collected for laboratory analysis, as described below. Table 3-1 includes details regarding the sampling rationale for Block E.

A direct push technology (DPT) drill rig will be used to advance the 25 soil borings in Block E to a maximum depth of ten feet. The soil borings will be advanced using a 1.5-inch-diameter, four foot long, stainless steel macrocore sampler, fitted with a disposable acetate liner. Three soil samples will be collected from each soil boring, at depths of 0 to 2 feet, 2 to 4 feet, and 4 to 6 feet below ground surface (bgs). All samples (75 plus 3 duplicates) will be analyzed for polychlorinated biphenyls (PCBs) by SW846 Method 8082, polycyclic aromatic hydrocarbons (PAHs) by SW846 Method 8270B, and total petroleum hydrocarbons (TPH)-diesel range organics (DRO) and –gasoline range organics (GRO) by SW846 Method 8015B. Additionally, ten soil samples (plus one duplicate sample) from the Block E borings will be analyzed for total priority pollutant metals (PP13) by SW846 Method 6010, hexavalent chromium by SW846 Method 7199, and for pesticides by SW846 Method 8081 for waste characterization. The ten

boring locations and soil sample depths to be analyzed for metals, hexavalent chromium, and pesticides will be evenly distributed across the sample area to provide for adequate coverage of data. The Block E pre-design soil boring locations are shown in Figure 3-1. Table 3-2 lists the sample identifications and laboratory analyses to be performed for each boring location.

3.2 BLOCK G PRE-DESIGN SOIL SAMPLING

The area of proposed soil sampling for Block G is located in the southeast corner of the block, and corresponds to the area of the proposed Block G groundwater remediation system (refer to Figure 3-1). A total of ten soil borings (G-SB-911 to G-SB-920) are proposed at Block G, with three soil samples collected in each boring location for laboratory analysis as described below. The sampling rationale for Block G is included in Table 3-1.

A DPT drill rig will be used to advance the ten Block G soil borings to a maximum depth of ten feet. The soil borings will be advanced using a 1.5-inch-diameter, four foot long, stainless steel macrocore sampler fitted with a disposable acetate liner. Three soil samples (0 to 2 feet, 2 to 6, and 6 to 10 feet bgs) will be collected from each soil boring. All samples (30 plus 2 duplicates) will be analyzed for PAHs by SW846 Method 8270B, and TPH-DRO and –GRO by SW846 Method 8015B. Additionally, ten (10) soil samples from the Block G borings will be analyzed for total priority pollutant metals by SW846 Method 6010, hexavalent chromium by SW846 Method 7199, and for pesticides by SW846 Method 8081 for waste characterization. The ten soil samples to be analyzed for metals, hexavalent chromium, and pesticides will be evenly distributed across the sample area to provide for adequate coverage of data (e.g., one sample from each Block G boring). Figure 3–2 shows the Block G pre-design soil-boring locations, and the details regarding the sample identifications and laboratory analyses to be performed for each boring location are provided in Table 3-2.

Table 3-1

Rationale for Proposed Soil Sampling 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland

Soil sample ID	Rationale for sampling/analysis
Block E	
E-SB-886 through E-SB-899	Located in southeast portion of Block E; between former Building D parking area and 500,000-gallon water tank. Sample area coincides with the overall footprint of planned groundwater remedial system layout. Samples to provide shallow soil characterization data in general areas without previous soil analytical data and to further delineate the extent of contaminated soils near previous borings where constituent concentrations exceeded residential cleanup goals.
E-SB-900 through E-SB-910	Located within southeast portion of former Building D concrete foundation, in and around footprint of planned groundwater remedial system and near proposed groundwater injection equipment trailer. Samples to provide shallow soil characterization data in general areas without previous soil analytical data and to further delineate the extent of contaminated soils near previous borings where constituent concentrations exceeded residential cleanup goals.
Block G	
G-SB-911, G-SB-912, G-SB-915 through G-SB-920	Located in southeast portion of Block G and in the recognized environmental condition (REC) #11 area. Sample area coincides with the overall footprint of planned groundwater remedial system layout. Samples to provide shallow soil characterization data in general areas without previous soil analytical data and to further delineate the extent of contaminated soils near previous borings where constituent concentrations exceeded residential cleanup goals.
G-SB-913 through G-SB-914	Located within the footprint of re-located Block G swale.

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 1 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block E						
E-SB-886	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-887	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-888	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-889	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-890	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 2 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block E						
E-SB-891	Three continuous sample intervals downward to groundwater table (e.g., - 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-892	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-893	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-894	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-895	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-896	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 3 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block E						
E-SB-897	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-898	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-899	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-900	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-901	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 4 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block E						
E-SB-902	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-903	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-904	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-905	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-906	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
E-SB-907	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 5 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block E						
E-SB-908	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-909	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
E-SB-910	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-4, and 4-6 ft.)	PCBs, PAHs, TPH-DRO, TPH-GRO	SW-846 8082, SW-846 8270B, SW-846 8015	3-4 oz. glass jars	Cool to 4±2°C	3
Block G						
G-SB-911	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO,	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 6 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block G						
G-SB-912	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
G-SB-913	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
G-SB-914	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
G-SB-915	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1

Table 3-2

Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 7 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block G						
G-SB-916	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
G-SB-917	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
G-SB-918	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
G-SB-919	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1


Table 3-2


Sampling Requirements 2012 Pre-Design Soil Sampling—Blocks E and G Lockheed Martin Middle River Complex, Middle River, Maryland Page 8 of 8

Sample Identification	Depth Intervals (feet)	Analysis	Analytical Methods	Sample Containers	Preservation Requirements	Number of Samples Collected
Block G						
G-SB-920	Three continuous sample intervals downward to groundwater table (e.g., 0-2, 2-6, and 6-10 ft.)	PAHs, TPH-DRO, TPH-GRO	SW-846 8270B, SW-846 8015	2-4 oz. glass jars	Cool to 4±2°C	3
	One select depth interval	Total priority pollutant, hexavalent chromium, and pesticides	SW-846 6010, SW-846-7199, SW-846 8081	3-4 oz. glass jars	Cool to 4±2°C	1
°C - degrees Celsius		PAH -	polycyclic aromatic hydrocarbons			

DRO diesel-range organics PCBs polychlorinated biphenyls foot/feet TPH total petroleum hydrocarbons ft. -GRO ounce

gasoline-range organics oz. -





Section 4 Project Deliverables

A report summarizing the results will be prepared after the pre-design soil sampling investigation is complete. It will, at a minimum, describe all aspects of the investigation, including field procedures, and will contain the following:

- figures illustrating sampling locations,
- laboratory reports,
- summary tables of laboratory analytical results,
- discussion of laboratory analytical results with comparison to residential cleanup criteria,
- field documentation and screening results,
- documentation that an appropriate level of data validation and data usability assessment were employed,
- documentation of waste handling and disposal, and
- other relevant documentation, as appropriate.

The conclusion section of the summary report will make recommendations regarding further action. The report will be submitted to Lockheed Martin Corporation and its representatives for review and comment. Comments will be incorporated as appropriate to meet project needs. Tetra Tech, Inc. assumes that no more than one round of comments will be necessary and that any comments received will be minimal. Additional rounds of comments may require additional funding and may delay the schedule. Tetra Tech, Inc. will also update the environmental geographic information system (EGIS) system with the soil analytical data.

This page intentionally left blank.

Section 5 References

- 1. Lockheed Martin Corporation, 2009a. Department of Energy, Environment, Safety, and Health (EESH) *Remediation Waste Management Procedure No: EROP-03, Revision 4,* effective April 17, 2009.
- 2. Lockheed Martin Corporation, 2009. *Remediation Contractor's ESH Handbook, Revision 1*, effective June 10, 2009.
- 3. TAI Consulting Engineers, October 2002. Drawing titled "Site Plan, Chesapeake Park, LMC Properties, Inc." (Revision C, October 2, 2002).
- 4. Tetra Tech, January 2005. 2004 Phase II Environmental Site Assessment, Middle River Complex.
- 5. Tetra Tech, April 2005. Final Data Report, Site-Wide Phase II Investigation, Middle River Complex.
- 6. Tetra Tech, May 2006. Site Characterization Report, Revision 1.0, Lockheed Martin Middle River Complex.
- 7. Tetra Tech, Inc., October 2009. Sediment Characterization Report for Cow Pen Creek and Dark Head Cove, Lockheed Martin Middle River Complex.
- 8. Tetra Tech, Inc., November 2009. Block E Supplemental Soil and Storm Drain Sediment Characterization Report, Lockheed Martin Middle River Complex.
- 9. Tetra Tech, Inc. (Tetra Tech), 2010. *Blocks D, F, G, and H Data Gap Sampling Work Plan*. August.
- 10. Tetra Tech, Inc. (Tetra Tech), 2011a. Block G Data Summary Report. February.
- 11. Tetra Tech, Inc. (Tetra Tech), 2012a. Additional Block E Soil Characterization Report. January.
- 12. USEPA (United States Environmental Protection Agency), July 1990. *A Guide to Remedial Actions at Superfund Sites with PCB Contamination*, 9355.401FS. Office of Solid Waste and Emergency Response, Washington, D.C.
- 13. U.S. Environmental Protection Agency (USEPA), Region III, 1993. Region III Modifications to the Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analyses, April.

14. USEPA Region III, 1994. Region III Modifications to the National Functional Guidelines for Organic Data Review, September.						

APPENDIX A—HEALTH AND SAFETY PLAN

HEALTH AND SAFETY PLAN FOR MULTIMEDIA CHARACTERIZATION

AT

LOCKHEED MARTIN CORPORATION

LOCKHEED MARTIN MIDDLE RIVER COMPLEX

2323 EASTERN BOULEVARD MIDDLE RIVER, MARYLAND

Submitted to:
Lockheed Martin Corporation
Lockheed Martin Middle River Complex

Submitted by:
Tetra Tech
20251 Century Boulevard, Suite 200
Germantown, Maryland 20874

JUNE 2012

PREPARED UNDER THE SUPERVISION OF:

PREPARED AND APPROVED BY:

MICHAEL MARTIN, P.G. PROGRAM MANAGER

GERMANTOWN, MARYLAND

MATTHEW M. SOLTIS, CIH, CSP

CORPORATE HEALTH AND SAFETY MANAGER

PITTSBURGH, PENNSYLVANIA

TABLE OF CONTENTS

1.3 SITE INFORMATION AND PERSONNEL ASSIGNMENTS	SEC1	<u> ION</u>		<u>PAGE</u>
1.2 STOP WORK	1.0	INTRO		
1.3 SITE INFORMATION AND PERSONNEL ASSIGNMENTS. 1-4 2.0 EMERGENCY ACTION PLAN		1.1	KEY PROJECT PERSONNEL AND ORGANIZATION	1-1
2.0 EMERGENCY ACTION PLAN 2-1 2.1 INTRODUCTION 2-1 2.2 EMERGENCY PLANNING 2-1 2.3 EMERGENCY PLANNING 2-2 2.3.1 Recognition 2-2 2.3.2 Prevention 2-3 2.3.3 Fire Prevention / Flammable Liquids 2-3 2.3.2 Prevention / Flammable Liquids 2-3 2.3.2 Prevention / Flammable Liquids 2-3 2.3.2 EWERGENCY CONTACTS 2-4 2.6 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY COUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 2.11.1 TOTAL Incident Reporting System 2-9 2.11.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 3-2 3-2 3-2 3-2 3-3		1.2	STOP WORK	1-3
2.1 INTRODUCTION. 2-1 2.2 EMERGENCY PLANNING. 2-1 2.3 EMERGENCY RECOGNITION AND PREVENTION 2-2 2.3.1 Recognition 2-2 2.3.2 Prevention 2-3 2.3.3 Fire Prevention / Flammable Liquids 2-3 2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2-3 2.5 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-9 2.11 INJURYILLINESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 DIRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC)		1.3	SITE INFORMATION AND PERSONNEL ASSIGNMENTS	1-4
2.2 EMERGENCY PLANNING. 2-1 2.3.1 Recognition 2-2 2.3.2 Prevention 2-3 2.3.3 Fire Prevention / Flammable Liquids 2-3 2.3 2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2-3 2.5 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-1 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling <t< td=""><td>2.0</td><td>EMERG</td><td>ENCY ACTION PLAN</td><td> 2-1</td></t<>	2.0	EMERG	ENCY ACTION PLAN	2-1
2.3 EMERGENCY RECOGNITION AND PREVENTION 2-2 2.3.1 Recognition 2-2 2.3.2 Prevention 2-3 2.3.3 Fire Prevention / Flarmable Liquids 2-3 2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2-3 2.5 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 S.1 GENERAL SAFE WORK PRACTICES 5-1		2.1		
2.3.1 Recognition 2-2 2.3.2 Prevention 2-3 2.3 Fire Prevention / Flammable Liquids 2-3 2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2-3 2.5 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL		2.2		
2.3.2 Prevention 2-3 2.3.3 Fire Prevention / Flammable Liquids 2-3 2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2-3 2.5 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 <td></td> <td>2.3</td> <td></td> <td></td>		2.3		
2.3.3 Fire Prevention / Flammable Liquids 2.3 2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2.3 2.5 EMERGENCY CONTACTS 2.4 2.6 EMERGENCY ROUTE TO HOSPITAL 2.6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2.7 2.8 PPE AND EMERGENCY EQUIPMENT 2.7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2.8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2.8 2.11 INJURY/ILLNESS REPORTING 2.9 2.11.1 TOTAL Incident Reporting System 2.9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5.2.1 Before Drilling 5-3 5.2.2 During Drilling 5-3		2.3.1		
2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE 2-3 2.5 EMERGENCY CONTACTS 2-4 2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.2 During Drilling 5-4		-		
2.5 EMERGENCY CONTACTS. 2-4 2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES. 2-7 2.8 PPE AND EMERGENCY EQUIPMENT. 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT. 2-8 2.11 INJURY/ILLNESS REPORTING. 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND. 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK. 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES. 5-1 5.1 GENERAL SAFE WORK PRACTICES. 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES. 5-2 5.2.1 Before Drilling. 5-2 5.2.2 During Drilling. 5-2 5.2.3 After Drilling. 5-3 5.2.3 After Drilling. 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G. Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-13 5.5 EXCAVATION SAFE WORK PRACTICES 5-15			Fire Prevention / Flammable Liquids	2-3
2.6 EMERGENCY ROUTE TO HOSPITAL 2-6 2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-4 5.3.1 <				
2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES 2-7 2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-2 5.2.3 After Drilling 5-3 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-4 5.3.1 U.S.C.G. Flotat				
2.8 PPE AND EMERGENCY EQUIPMENT 2-7 2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE 2-8 2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT 2-8 2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Floation Device Types 5-6 5.3.2 U.S.C.G. Floation Device Types </td <td></td> <td></td> <td></td> <td></td>				
2.9				
2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT		_		
2.11 INJURY/ILLNESS REPORTING 2-9 2.11.1 TOTAL Incident Reporting System 2-9 3.0 SITE BACKGROUND 3-1 3.1 SITE HISTORY 3-1 3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5-2.1 Before Drilling 5-2 5-2.2 During Drilling 5-3 5-2.3 After Drilling 5-4 5-3 5-2 4 Concrete Coring Operations 5-4 5-3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5-3.2 U.S.C.G. Flotation Device Types 5-6 5-3.2 U.S.C.G. Boat Regulations 5-7 5-3.3 Uniform State Waterway Marking System (USWMS) 5-10 5-10 SAFE WORK PRACTICES 5-12 5-5 EXCAVATION SAFE WORK PRACTICES 5-13 5-6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15 5-6 5-6 5-15 5-6 5-15 5-6 5-15 5-15 5-15 5-6 5-15 5				_
2.11.1 TOTAL Incident Reporting System 2-9		_		
3.0 SITE BACKGROUND				
3.1 SITE HISTORY		2.11.1	TOTAL Incident Reporting System	2-9
3.2 BLOCK E BUILDING D RAD INVESTIGATION 3-2 4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-3 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-4 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15	3.0			
4.0 SCOPE OF WORK 4-1 5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		-		
5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		3.2	BLOCK E BUILDING D RAD INVESTIGATION	3-2
SAFE WORK PRACTICES 5-1 5.1 GENERAL SAFE WORK PRACTICES 5-1 5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15	4.0	SCOPE	OF WORK	4-1
5.1 GENERAL SAFE WORK PRACTICES	5.0	IDENTII	FYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND	
5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		SAFE V		
SAFE WORK PRACTICES 5-2 5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		5.1		5-1
5.2.1 Before Drilling 5-2 5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		5.2		
5.2.2 During Drilling 5-3 5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15				
5.2.3 After Drilling 5-4 5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		5.2.1		
5.2.4 Concrete Coring Operations 5-4 5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		-		
VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15				
VESSELS/BARGES) 5-6 5.3.1 U.S.C.G. Flotation Device Types 5-6 5.3.2 U.S.C.G Boat Regulations 5-7 5.3.3 Uniform State Waterway Marking System (USWMS) 5-10 5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES 5-12 5.5 EXCAVATION SAFE WORK PRACTICES 5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES 5-15		5.2.4	Concrete Coring Operations	5-4
5.3.1 U.S.C.G. Flotation Device Types		5.3	SAFE BOATING PRACTICES (I.E., WORKING FROM WATER	5-6
5.3.2 U.S.C.G Boat Regulations		531		
5.3.3 Uniform State Waterway Marking System (USWMS)				
5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES			Uniform State Waterway Marking System (USWMS)	5-10
BUILDINGS SAFE WORK PRACTICES			PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN	0
5.5 EXCAVATION SAFE WORK PRACTICES5-13 5.6 HAND AND POWER TOOL SAFE WORK PRACTICES5-15		J		5-12
5.6 HAND AND POWER TOOL SAFE WORK PRACTICES5-15		5.5		

TABLE OF CONTENTS (Continued)

SEC ₁	<u>ION</u>		PAGE
6.0		D ASSESSMENT AND CONTROLS	
	6.1	CHEMICAL HAZARDS	
	6.1.1	Volatile Organic Compounds (VOCs)	
	6.1.2	Metals	6-5
	6.2	EXHAUST GASES/FUMES CREATED DURING INDOOR ACTIVITIES	
	6.3	RADIOLOGICAL HAZARDS	6-6
	6.4	SUB SLAB AND IAQ SAMPLING BUILDINGS A,B,C	
	6.5	PHYSICAL HAZARDS	
	6.5.1	Slips, Trips, and Falls	
	6.5.2	Strain/Muscle Pulls from Heavy Lifting	
	6.5.3	Heat/Cold Stress	
	6.5.4	Pinch/Compression Points	
	6.5.5	Natural Hazards	
	6.5.6	Vehicular and Equipment Traffic	
	6.5.7	Inclement Weather	
	6.5.8	Contact with Underground or Overhead Utilities/Electrical Safety	
	6.5.9	Heavy Equipment Hazards	
	6.5.10	Compressed Gas Cylinders	6-11
7.0		D RADIATION MONITORING	
	7.1	INSTRUMENTS AND USE	
	7.1.1	Carbon Monoxide Detector and Colorimetric Tubes for Nitrogen Dioxide	
	7.1.2	Radiation Survey Instrument	7-4
	7.2	INSTRUMENT MAINTENANCE AND CALIBRATION	
	7.3	DOCUMENTING INSTRUMENT READINGS	7-5
8.0	TRAINII	NG/MEDICAL SURVEILLANCE REQUIREMENTS	
	8.1	INTRODUCTORY/REFRESHER/SUPERVISORY TRAINING	8-1
	8.2	SITE-SPECIFIC TRAINING	
	8.3	MEDICAL SURVEILLANCE	8-2
	8.4	SITE VISITORS	8-2
9.0	SITE CO	ONTROL	9-1
	9.1	EXCLUSION ZONE	
	9.1.1	Exclusion Zone Clearance	
	9.2	CONTAMINATION REDUCTION ZONE	
	9.3	SUPPORT ZONE	9-3
	9.4	SAFE WORK PERMITS	9-3
	9.5	SITE SECURITY	9-3
	9.6	SITE VISITORS	9-3
	9.7	SITE MAP	9-5
	9.8	BUDDY SYSTEM	9-5
	9.9	COMMUNICATION	9-5
	9.10	SELF-AUDITS	9-5
10.0	SPILL	CONTAINMENT PROGRAM AND WASTE MANAGEMENT PLAN	10-1
	10.1	SCOPE AND APPLICATION	
	10.1	POTENTIAL SPILL AREAS	
	10.2	LEAK AND SPILL DETECTION	
	10.4	PERSONNEL TRAINING AND SPILL PREVENTION	
	10.4	SPILL PREVENTION AND CONTAINMENT EQUIPMENT	
	10.6	SPILL CONTROL PLAN	
	10.7	WASTE MANAGEMENT PLAN	
11.0	CONEIN	IED-SPACE ENTRY	44.4
11.0		ILD OF AVE LITER I	1 - 1

TABLE OF CONTENTS (Continued)

SECTI	<u>ON</u>	PAGE	
12.0	HOT WORK	12-1	
13.0	USE OF LOCKHEED MARTIN MATERIALS AND EQUIPMENT		
14.0	ELEVATED LOCATIONS / LADDERS / SCAFFOLDS	14-1	
15.0	DANGEROUS OPERATIONS	15-1	
16.0	EXCAVATIONS, TRENCHES, AND EARTHWORK	16-1	
17.0	ASBESTOS	17-1	
18.0	NANOTECHNOLOGY	18-1	
19.0	WORK INVOLVING AIR EMISSIONS	19-1	
20.0	WORK INVOLVING WATER DISCHARGES	20-1	
21.0	MATERIALS AND DOCUMENTATION	21-1	
22.0	ACRONYMS / ABBREVIATIONS	22-1	
	LIST OF TABLES		
TABLE	<u>E</u>	PAGE	
2-1	Emergency Contacts	2-5	
6-1	Comparison of COPCs Available, Worst-Case Air Concentrations, and Current		
	Occupational Exposure Limits	6-1	
	LIST OF FIGURES		
FIGUR	E .	PAGE	
2-1	Route to Hospital	2-6	
3-1	Site Map	3-3	
7-1	Documentation of Field Calibration	7-6	
8-1	Site-Specific Training Documentation	8-4	
9-1	Example Safe Work Permit	9-7	

LIST OF ATTACHMENTS

ATTACHMENT I LOCKHEED MARTIN REMEDIATION CONTRACTOR'S ESH HANDBOOK

ATTACHMENT II INCIDENT REPORT FORM
ATTACHMENT III MEDICAL DATA SHEET
ATTACHMENT IV SAFE WORK PERMITS

ATTACHMENT V EQUIPMENT CHECKLIST FOR DPT RIGS

ATTACHMENT VI TETRA TECH SWP 5-6 SAFE WORKING PRACTICES FOR WORKING OVER

OR NEAR WATER

ATTACHMENT VII BOAT SAFETY CHECKLIST

ATTACHMENT VIII TETRA TECH SWP 5-15 HEAT STRESS AND 5-26 PREVENTION OF SUN

EXPOSURE

ATTACHMENT IX TETRA TECH DECONTAMINATION OF FIELD EQUIPMENT AND WASTE

HANDLING STANDARD OPERATING PROCEDURE

ATTACHMENT X OSHA POSTER

1.0 INTRODUCTION

This Health and Safety Plan (HASP) has been developed to provide the minimum practices and procedures for Tetra Tech, Inc. (Tetra Tech) and subcontractor personnel engaged in Multimedia Characterization activities at the Lockheed Martin Middle River Complex in Middle River, Maryland.

This HASP must be used in conjunction with the Tetra Tech Health and Safety Guidance Manual (HSGM). The HSGM contains Tetra Tech Health and Safety Standard Operating Procedures (SOPs), as well as detailed reference information on a variety of topics referenced in this HASP. This HASP and the contents of the Guidance Manual were developed to comply with the requirements stipulated in 29 CFR 1910.120 (OSHA's Hazardous Waste Operations and Emergency Response Standard) and applicable sections of 29 CFR 1926 (Safety and Health Regulations for Construction).

All contractor responsibilities stipulated in Section 1 of the Lockheed Martin Remediation Contractor's ESH Handbook (LM Handbook) will be adhered to. The LM Handbook can be found in Attachment I of this HASP.

Copies of all pertinent environmental, safety and health (ESH) records must be maintained at the job site. This includes, but is not limited to, this site-specific HASP, the Tetra Tech Health and Safety Guidance Manual, personnel training documentation, evidence of enrollment in a medical surveillance program, accident/injury reporting, work area inspections, periodic safety meetings, MSDS's, air monitoring data, waste container inspections, etc. These records must also be provided electronically to the Lockheed Martin Project Lead.

This HASP has been developed using the latest available information regarding known or suspected chemical contaminants and potential physical hazards associated with the proposed work and site. The HASP will be modified if the scope of work changes or if new information regarding site conditions, hazards, or contaminants of concern becomes available. If deviations are encountered from the field work plan, the contractor shall A) notify to the Lockheed Martin Project Lead and B) suspend work to assess changes to the work plan(s) and the HASP. Changes to the work plan(s) and the HASP shall be reviewed by the Project Lead. Procedures addressing changes to this HASP as described in Section 6 of the LM Handbook (Attachment I) will be followed.

1.1 KEY PROJECT PERSONNEL AND ORGANIZATION

This section defines responsibilities for site safety and health for Tetra Tech employees conducting field activities under this field effort. All personnel assigned to participate in the field work have the primary

responsibility for performing all of their work tasks in a manner that is consistent with the Tetra Tech Health and Safety Policy, the health and safety training that they have received, the contents of this HASP, and in an overall manner that protects their personal safety and health and that of their coworkers. The following persons are the primary point of contact and have the primary responsibility for observing and implementing this HASP and for overall on-site health and safety.

- The Tetra Tech Project Manager (PM) is responsible for the overall direction and implementation of this HASP.
- The Field Operations Manager (FOL) manages field activities, executes the work plan, and enforces safety procedures as applicable to the work plan.
- The Project Health and Safety Officer (PHSO) is responsible for developing this HASP in accordance with applicable OSHA regulations. Specific responsibilities include:
 - Providing information regarding site contaminants and physical hazards.
 - Establishing air monitoring and decontamination procedures.
 - Assigning personal protective equipment based on task and potential hazards.
 - Determining emergency action procedures.
 - Identifying appropriate emergency contacts.
 - Stipulating training and medical surveillance requirements.
 - Providing standard work practices to minimize potential injuries and exposures associated with hazardous waste site work.
 - Modify this HASP, where and when necessary.
- The Site Safety Officer (SSO) supports site activities by advising the PM on the aspects of health and safety on site. These duties may include the following:
 - Coordinate health and safety activities with the FOL.
 - Select, inspect, implement, and maintain personal protective equipment.
 - Establish work zones and control points.
 - Implements air-monitoring program for onsite activities.
 - Verify training and medical status of onsite personnel status in relation to site activities.
 - Implements hazard communication, respiratory protection, and other associated safety and health programs as necessary.
 - Coordinates emergency services.
 - Provides site specific training for onsite personnel.
 - Investigates accidents and injuries (see Attachment II Incident Report Form)

- Provides input to the PHSO regarding the need to modify, this HASP, or other applicable health and safety associated documents as per site-specific requirements.
- The Project Health Physicist (PHP) supports site activities by advising the PM on the aspects of health and safety on site. These duties may include the following:
 - Coordinate radiological activities with the FOL.
 - Select, implement, and survey personal protective equipment.
 - Establish radiological areas.
 - Provides site specific training for onsite personnel.
 - Provides input to the PHSO regarding the need to modify, this HASP, or other applicable health and safety associated documents as per site-specific requirements.
- Compliance with the requirements of this HASP are monitored by the SSO and coordinated through the Tetra Tech Health and Safety Manager (HSM).

Note: In some cases one person may be designated responsibilities for more than one position. For example, the FOL may also be responsible for the SSO duties. This action will be performed only as credentials, experience, and availability permits.

1.2 STOP WORK

All employees are empowered, authorized, and responsible to stop work at any time when an imminent and uncontrolled safety or health hazard is perceived. In a Stop Work event (immediately after the involved task has been shut down and the work area has been secured in a safe manner) the employee shall contact the Project Manager and the Corporate Health and Safety Manager. Through observations and communication, all parties involved shall then develop, communicate, and implement corrective actions necessary and appropriate to modify the task and to resume work. If worked was stopped for radiological reasons, Project Manager and Corporate Health and Safety Officer will consult with PHP prior to resuming work.

1.3 SITE INFORMATION AND PERSONNEL ASSIGNMENTS

Site Name:	Lockheed Martin Mi	ddle River Complex	Address:	Middle River, Maryland
LMC Contact: Tom Blackman Scott Lapp John Morgan			Phone Numbe	r: (301) 214-9958 (410) -682-0365 office (410) 967-8745 cell (410) 682-1382 office (410) 215-4530 cell
Purpose of Si	te Visit: Multimedia	Characterization activities	_	(110) 210 1000 00
Proposed Dat	es of Work: May 20	012 until completion	_	
Project Team:	<u>.</u>			
Tetra Tech Ma	anagement Personne	el: Discipline/Tasks Assi	gned:	Telephone
Mike Martin		Program Manager		(301) 528-3022 office (410) 707-5259 cell
Tony Apanava	ge	Project Manager (PM)		(301) 528-3021 (301) 233-8230 cell
TBD		Field Operations Leader (FOL)	
TBD		Site Safety Officer (SSO)		
Matthew M. So	oltis, CIH, CSP	Health and Safety Manager (412) 921-8912		(412) 921-8912
Clyde Snyder		Project Health and Safety Officer (PHSO)		(412) 921-8904
Amy Stanford		Project Health Physicist (PHP) (706) 832-73		(706) 832-7394
Non-Tetra Tec	ch Personnel	Affiliation/Discipline/	Гasks Assigned	Telephone
John Morgan		Facilities Manager		(410) 682-1328
Mike Musheno		Environment Safety & I	Health/Projects	(484) 875-2819
Tom Ambrose		Facilities Supervisor		(410) 682-1308
LMC Security Office (Chief Philip Johnston)		Site Security		(410) 682-1050
Jimmy Yeager		Lockheed Martin ESH	Manger	(301) 873-1444
Hazard Assess Prepared by: 9	, , ,	f 29 CFR 1910.132) for HAS	SP preparation ha	as been conducted by:

2.0 EMERGENCY ACTION PLAN

2.1 INTRODUCTION

This section has been developed as part of a planning effort to direct and guide field personnel in the event of an emergency. In the event of an emergency, the field team will primarily evacuate and assemble to an area unaffected by the emergency and notify the appropriate local emergency response personnel/agencies. Workers who are ill or who have suffered a non-serious injury may be transported by site personnel to nearby medical facilities, provided that such transport does not aggravate or further endanger the welfare of the injured/ill person. The emergency response agencies listed in this plan are capable of providing the most effective response, and as such, will be designated as the primary responders. These agencies are located within a reasonable distance from the area of site operations, which ensures adequate emergency response time.

Tetra Tech personnel may participate in minor event response and emergency prevention activities such as:

- Initial fire-fighting support and prevention
- Initial spill control and containment measures and prevention
- Removal of personnel from emergency situations
- Provision of initial medical support for injury/illness requiring only first-aid level support
- Provision of site control and security measures as necessary

2.2 EMERGENCY PLANNING

Through the initial hazard/risk assessment effort, emergencies resulting from chemical, physical, or fire hazards are the types of emergencies which could be encountered during site activities. To minimize or eliminate the potential for these emergency situations, pre-emergency planning activities will include the following (which are the responsibility of the SSO and/or the FOL):

- Coordinating with Lockheed Martin Middle River and/or local emergency response personnel to ensure that Tetra Tech emergency action activities are compatible with existing emergency response procedures.
- Establishing and maintaining information at the project staging area (support zone) for easy access in the event of an emergency. This information will include the following:
 - Chemical Inventory (of chemicals used onsite), with Material Safety Data Sheets.

- Onsite personnel medical records (Medical Data Sheets).
- A log book identifying personnel onsite each day.
- Hospital route maps with directions (these should also be placed in each site vehicle).
- Emergency Notification phone numbers.

The Tetra Tech FOL will be responsible for the following tasks:

- Identifying a chain of command for emergency action.
- Educating site workers to the hazards and control measures associated with planned activities at the site, and providing early recognition and prevention, where possible.
- Periodically performing practice drills to ensure site workers are familiar with incidental response measures.
- Providing the necessary equipment to safely accomplish identified tasks.

2.3 EMERGENCY RECOGNITION AND PREVENTION

2.3.1 Recognition

Emergency situations that may be encountered during site activities will generally be recognized by visual observation. Visual observation will also play a role in detecting potential exposure events to some chemical hazards. To adequately recognize chemical exposures, site personnel must have a clear knowledge of signs and symptoms of exposure associated with the principle site contaminants of concern as presented in this HASP. Tasks to be performed at the site, potential hazards associated with those tasks and the recommended control methods are discussed in detail in Sections 5.0 and 6.0. Additionally, early recognition of hazards will be supported by daily site surveys to eliminate any situation predisposed to an emergency. The FOL and/or the SSO will be responsible for performing surveys of work areas prior to initiating site operations and periodically while operations are being conducted. Survey findings are documented by the FOL and/or the SSO in the Site Health and Safety logbook; however, site personnel will be responsible for reporting hazardous situations. Where potential hazards exist, Tetra Tech will initiate control measures to prevent adverse effects to human health and the environment.

The above actions will provide early recognition for potential emergency situations, and allow Tetra Tech to instigate necessary control measures. However, if the FOL and the SSO determine that control measures are not sufficient to eliminate the hazard, Tetra Tech will withdraw from the site and notify the appropriate response agencies listed in Table 2-1.

2.3.2 <u>Prevention</u>

Tetra Tech and subcontractor personnel will minimize the potential for emergencies by following the Health and Safety Guidance Manual and ensuring compliance with the HASP and applicable OSHA regulations. Daily site surveys of work areas, prior to the commencement of that day's activities, by the FOL and/or the SSO will also assist in prevention of illness/injuries when hazards are recognized early and control measures initiated.

2.3.3 Fire Prevention / Flammable Liquids

Tetra Tech and subcontractor personnel are responsible for fire protection in all of their work areas at all times during the duration of this field effort (24 hours per day/seven days per week). Approved fire-fighting equipment and extinguishers, in adequate quantities for their work activates must be provided.

The Lockheed Martin Project Lead will be notified as soon as possible of any fire, if Tetra Tech or subcontractor personnel use a Lockheed Martin fire extinguisher, and of any and all fires that are extinguished. In case of fire, Tetra Tech and subcontractor personnel will call 9-1-1.

All flammable and combustible liquids must be stored, dispensed and used in accordance with OSHA regulations and the Uniform Fire Code. Bonding and grounding of containers containing flammable liquids will be required.

All fire prevention/flammable liquids safety procedures and requirements stipulated in Section 3.15 of the LM Handbook (Attachment I) will also be adhered to.

2.4 EVACUATION ROUTES, PROCEDURES, AND PLACES OF REFUGE

An evacuation will be initiated whenever recommended hazard controls are insufficient to protect the health, safety or welfare of site workers. Specific examples of conditions that may initiate an evacuation include, but are not limited to the following: severe weather conditions; fire or explosion; monitoring instrumentation readings which indicate levels of contamination are greater than instituted action levels; and evidence of personnel overexposure to potential site contaminants.

In the event of an emergency requiring evacuation, personnel will immediately stop activities and report to the designated safe place of refuge unless doing so would pose additional risks. When evacuation to the primary place of refuge is not possible, personnel will proceed to a designated alternate location and remain until further notification from the Tetra Tech FOL. Safe places of refuge will be identified prior to the commencement of site activities by the SSO and will be conveyed to personnel as part of the pre-

activities training session. This information will be reiterated during daily safety meetings. Whenever possible, the safe place of refuge will also serve as the telephone communications point for that area. During an evacuation, personnel will remain at the refuge location until directed otherwise by the Tetra Tech FOL or the on-site Incident Commander of the Emergency Response Team. The FOL or the SSO will perform a head count at this location to account for and to confirm the location of site personnel. Emergency response personnel will be immediately notified of any unaccounted personnel. The SSO will document the names of personnel onsite (on a daily basis) in the site Health and Safety Logbook. This information will be utilized to perform the head count in the event of an emergency.

Evacuation procedures will be discussed during the pre-activities training session, prior to the initiation of project tasks. Evacuation routes from the site and safe places of refuge are dependent upon the location at which work is being performed and the circumstances under which an evacuation is required. Additionally, site location and meteorological conditions (i.e., wind speed and direction) may dictate evacuation routes. As a result, assembly points will be selected and communicated to the workers relative to the site location where work is being performed. Evacuation should always take place in an upwind direction from the site.

2.5 EMERGENCY CONTACTS

Prior to initiating field activities, personnel will be thoroughly briefed on the emergency procedures to be followed in the event of an accident. Table 2-1 provides a list of emergency contacts and their associated telephone numbers. This table must be posted where it is readily available to site personnel. Facility maps should also be posted showing potential evacuation routes and designated meeting areas.

Any pertinent information regarding allergies to medications or other special conditions will be provided to medical services personnel. This information is listed on Medical Data Sheets filed onsite (see Attachment III). If an exposure to hazardous materials has occurred, provide hazard information from Table 6-1 to medical service personnel.

The Lockheed Martin Project Lead shall be contacted immediately in the event of a fatal or serious injury, and unpermitted environmental release, or any ESH incident that is likely to generate significant publicity or an adverse situation for Lockheed Martin. Detailed requirements are describe in Section 1.15 of the LM Handbook (Attachment I).

In the event of an emergency not requiring 9-1-1, LMC facility personnel should be contacted in the order presented on Table 2-1.

TABLE 2-1

EMERGENCY CONTACTS

LOCKHEED MARTIN MIDDLE RIVER COMPLEX, MARYLAND

AGENCY	TELEPHONE
EMERGENCY (Police, Fire, and Ambulance)	911
Franklin Square Hospital	(410) 682-7000
State of Maryland Emergency Response Center	(410) 974-3551
Local Emergency Planning Coordinator's office	(410) 887-2919
Chemtrec	(800) 424-9300
National Response Center	(800) 424-8802
Poison Control Center	(800) 222-1222
Mike Martin, Program Manager	(301) 528-3022 office (410) 707-5259 cell
PM, Tony Apanavage	(301) 528-3021 office (301) 233-8230 cell
HSM, Matthew M. Soltis, CIH, CSP	(412) 921-8912
PHSO, Clyde Snyder	(412) 921-8904 (724) 516-0907 cell
Amy Stanford (PHP)	(706) 832-7394
John Morgan, Facilities Manager	(410) 682-1328
Mike Musheno, ESH/ Projects	(410) 682-1315 office (610) 656-4012 cell
Scott Lapp	(410) 682-0365 office (410) 967-8745 cell
John Morgan	(410) 682-1382 office (410) 215-4530 cell
Tom Ambrose, Facilities Supervisor	(410) 682-1308 (856) 842-2590 cell
LMC Security (Chief Philip Johnston)	(410) 682-1050

2.6 EMERGENCY ROUTE TO HOSPITAL

FIGURE 2-1 ROUTE TO HOSPITAL



From: 2323 Eastern Boulevard, Middle River 21220, Maryland
To: Franklin Square Hospital Center(Baltimore), MD

Total Distance: 5.0 miles (8.0km)
Total Estimated Time: 0 hrs., 13mins.

Directions

2323 Eastern Boulevard, Middle River 21220, Maryland to Franklin Square Hospital Center(Baltimore), MD

Distance: 5.0 miles (8.0km) Time: 0 hrs., 13mins.

- Start out heading EAST on EASTERN BOULEVARD. Drive for 0.3 miles.
- 2. Make a U-turn at MD-150 E. Drive for 0.3 miles.
- Take exit on your RIGHT towards MD-700 / MARTIN BLVD / US-40. Drive for 0.2 miles.
- 4. Go STRAIGHT on MD-700 W. Drive for 1.6 miles.
- 5. Take US-40 W on your LEFT. Drive for 1 mile.
- 6. Turn RIGHT onto ROSSVILLE BOULEVARD. Drive for 1 mile.
- 7. Turn RIGHT onto FRANKLIN SQUARE DRIVE. Drive for 0.3 miles.
- 8. Turn LEFT onto HOSPITAL DRIVE. Drive for a short distance.
- 9. You have reached Franklin Square Hospital Center(Baltimore), MD

2.7 EMERGENCY ALERTING AND ACTION/RESPONSE PROCEDURES

Tetra Tech personnel will be working in close proximity to each other at Lockheed Martin Middle River Complex (LMC MRC). As a result, hand signals, voice commands, and line of site communication will be sufficient to alert site personnel of an emergency.

If an emergency warranting evacuation occurs, the following procedures are to be initiated:

- Initiate the evacuation via hand signals, voice commands, or line of site communication
- Report to the designated refuge point where the FOL will account for all personnel
- Once non-essential personnel are evacuated, appropriate response procedures will be enacted to control the situation.
- If personnel have been evacuated from a radiological area, contact the PHP.
- Describe to the FOL (FOL will serve as the Incident Coordinator) pertinent incident details.

In the event that site personnel cannot mitigate the hazardous situation, the FOL and SSO will enact emergency notification procedures to secure additional assistance in the following manner:

Dial 911 and call other pertinent emergency contacts listed in Table 2-1 and report the incident. Give the emergency operator the location of the emergency, the type of emergency, the number of injured, and a brief description of the incident. Stay on the phone and follow the instructions given by the operator. The operator will then notify and dispatch the proper emergency response agencies.

2.8 PPE AND EMERGENCY EQUIPMENT

A first-aid kit, eye wash units (or bottles of disposable eyewash solution) and fire extinguishers (strategically placed) will be maintained onsite and shall be immediately available for use in the event of an emergency. This equipment will be located in the field office as well as in each site vehicle. At least one first aid kit supplied with equipment to protect against bloodborne pathogens will also be available on site. Personnel identified within the field crew with bloodborne pathogen and first-aid training will be the only personnel permitted to offer first-aid assistance.

Safety eyewear meeting ANSI Z87.1 is required in areas designated as "Eye Projection Required" and is also required on all jobs where a potential injury to the eye is possible whether or not the area is posted.

Safety shoes and boots which meet the ANSI Z41 Standard shall be provided when impact and/or compression hazards exist.

Appropriate MSHA/NIOSH-approved respiratory protective devices must be worn when applicable state and/or federal action levels or OSHA permissible exposure levels are exceeded. Appropriate air monitoring and respiratory protection equipment will be supplied and maintained if inhalation hazards are anticipated and a respiratory protection adhering to all state and federal regulations implemented.

Hearing protection must be worn in all areas posted to indicate high noise level or where employees are exposed to noise levels in excess of the OSHA action level (85 dBA over an 8-hour time-weighted average or a dose of fifty percent).

Protective clothing such as suits, aprons, boots or gloves shall be worn where there is a hazard to the body through dermal contact with chemicals, dusts, heat or other harmful agents or conditions.

Hard hats meeting the ANSI Z89.1 Standard will be worn in all areas where there is danger of impact to the head or hazard from falling or moving objects.

All personal protective clothing and equipment will be used and approved as detailed in Section 3.1 of the LM Handbook (Attachment I).

Protective clothing for radiological work, if applicable, will be worn in accordance with Tetra Tech Radiologicial Protection Operating Procedures (Tt RPOP), found in the project work plan.

2.9 HAZARDOUS WASTE OPERATIONS AND EMERGENCY RESPONSE

Tetra Tech and subcontractor personnel conducting work at Lockheed Martin will adhere to Title 29, Code of Federal Regulations, Section 1910.120 – Hazardous Waste Operations and Emergency Response or the applicable state OSHA standards.

Tetra Tech and/or subcontractor personnel will to perform periodic work area inspections to determine the effectiveness of the site safety and health plan and to identify and correct unsafe conditions in the work area. These inspections shall be documented and available to Lockheed Martin upon request for review.

The requirements and regulations described in Section 3.20 of the LM Handbook (Attachment I) will be adhered to.

2.10 DECONTAMINATION PROCEDURES / EMERGENCY MEDICAL TREATMENT

During any site evacuation, decontamination procedures will be performed only if doing so does not further jeopardize the welfare of site workers. Decontamination will be postponed if the incident warrants

immediate evacuation. However, it is unlikely that an evacuation would occur which would require workers to evacuate the site without first performing the necessary decontamination procedures.

Tetra Tech personnel will perform rescue operations from emergency situations and may provide initial medical support for injury/illnesses requiring only "Basic First-Aid" level support, and only within the limits of training obtained by site personnel. Basic First-Aid is considered treatment that can be rendered by a trained first aid provider at the injury location and not requiring follow-up treatment or examination by a physician (for example; minor cuts, bruises, stings, scrapes, and burns). Personnel providing medical assistance are required to be trained in First-Aid and in the requirements of OSHA's Bloodborne Pathogen Standard (29 CFR 1910.1030). Medical attention above First-Aid level support will require assistance from the designated emergency response agencies. Attachment II provides the procedure to follow when reporting an injury/illness, and the form to be used for this purpose.

2.11 INJURY/ILLNESS REPORTING

Any pertinent information regarding allergies to medications or other special conditions will be provided to medical services personnel. This information is listed on Medical Data Sheets filed onsite (see Attachment III). If an exposure to hazardous materials has occurred, provide information on the chemical, physical, and toxicological properties of the subject chemical(s) to medical service personnel.

If any Tetra Tech personnel are injured or develop an illness as a result of working on site, the Tetra Tech "Injury/Illness Procedure" (Attachment II) must be followed. Following this procedure is necessary for documenting of the information obtained at the time of the incident.

Tetra Tech personnel will contact the LMC personnel in the order presented in Table 2-1 in the event of a fatality injury, environmental release (spill), near-miss incident, or an ESH incident that is likely to generate significant publicity. A written report of the incident/injury/spill and corrective action(s) must be submitted to LMC personnel within one (1) day of the incident.

Section 8.1 of the LM Handbook (Attachment I) describing the requirements of accident, injury, illness and incident reporting will be addressed.

2.11.1 TOTAL Incident Reporting System

TOTAL is Tetra Tech's new online incident reporting system. Use TOTAL to directly report health and safety incidents, notify key personnel, and initiate the process for properly investigating and addressing the causes of incidents, including near-miss events. An incident is considered any unplanned event. It may include several types of near misses, events where no loss was incurred, or incidents that resulted in injuries or illness, property or equipment damage, chemical spills, fires, or damage to motor vehicles.

TOTAL looks like the incident reporting form in Attachment II. TOTAL is an intuitive system that will guide you through the necessary steps to report an incident within 24 hours of its occurrence. Behind the scenes, TOTAL is a powerful tool for H&S professionals, and will help Tetra Tech to better track incidents, analyze root causes, implement corrective action plans, and share lessons learned. The ultimate result is a more safe and healthy working environment.

TOTAL is maintained on the Tetra Tech Intranet site at https://my.tetratech.com/

Once on the "My Tetratech" site, TOTAL can be found under the Health and Safety tab, Incident Reporting section, select "Report an Incident (TOTAL)". This will connect you directly to TOTAL. TOTAL can also be accessed directly from the internet using the following web address: http://totalhs.tetratech.com/

Note: When using the system outside the Tetra Tech intranet system or when operating in a wireless mode, a VPN connection will be required. The speed of the application may be affected dependent upon outside factors such as connection, signal strength, etc. Enter the system using your network user name and password. The user name should be in the following format - TT\nickname.lastname.

3.0 SITE BACKGROUND

3.1 SITE HISTORY

The LMC MRC is located at 2323 Eastern Boulevard in Middle River, Maryland. The site consists of approximately 180 acres of land and twelve main buildings. The subject property also includes perimeter parking lots, an athletic field, Lot D (presently a vacant lot with a concrete foundation for former Building D), a trailer and parts storage lot, and a vacant waterfront lot. The site is bounded by Eastern Boulevard (Route 150) to the north, Dark Head Creek to the south, Cow Pen Creek to the west, and Martin State Airport to the east.

Currently, LMC activities at the site are limited to facility and building management and maintenance. There are two main tenants at the site, Middle River Aircraft Systems (MRAS) and Naval Electronics & Surveillance Systems (NE&SS), also referred to as Vertical Launch Systems. MRAS conducts design, manufacturing, fabrication, testing, overhaul, and repair and maintenance of aeronautical structures, parts, and components for military and commercial applications. NE&SS conducts fabrication, assembly, testing and support of vertical launch systems. Historically, the property has been used for aircraft and missile launching systems design, development, and sales.

The purpose of these investigations are to characterize soil (surface/subsurface), surface water, groundwater, sediment, and indoor air quality in areas of the facility. Based on review of available facility information during the Phase I Environmental Site Assessment, no indication of current or historical site activities, within these areas, potentially resulting in a release of any hazardous substances or petroleum products was identified.

The facility is divided into blocks for the purpose of site investigations. The blocks included for investigation in this HASP are the following:

- Block D
- Block E
- Block F
- Block G
- Block H
- Block I*

*Work in Block I will not be conducted at this time information in this HASP is placed only for reference purposes at this time.

3.2 BLOCK E BUILDING D RAD INVESTIGATION

Recognized environmental condition (REC) #1 (Former Building D) is the only one of the three RECs located in Block E that were identified in the Phase I environmental site assessment that has a radiological concern. This investigation takes place in Tax Block E in former Building D. Former Building D, which was built in the early 1940s for final assembly of aircraft frames, was demolished in 1972. The building had an assembly floor (first floor), and a basement (current concrete slab), and occupied approximately 400,000 square feet.

The former basement areas were used for welding, extrusion milling, engine preparation, and assembly. The northwestern and southwestern portions of the basement housed several offices and laboratories used for radiological operations. Cleaning, plating, and finishing work areas were located along the southern interior wall near the building's center.


Since the building was demolished it had been used for storage, including the storage of airplane carcasses from the Martin State Airport air museum.

A radiological survey of REC #1 (Former Building D) was performed in March 2004 (Tetra Tech, 2004b) to determine if radiological activities possibly conducted in Building D had affected the underlying environmental media. The survey focused on the remaining Former Building D foundation slab where suspected radiological activities may have occurred. A cobalt-60 source was also located in the wet lab. The radiological survey covered two areas where isotopes were known to have been used, based on information obtained from MRC personnel who had been present when such operations occurred during the late 1950s–1960s. The primary area was in the southwestern portion of the building, along the southern exterior wall; the secondary area was immediately north of the first area, along the western exterior wall of Former Building D.

The radiological survey uses alpha and beta monitors and a gamma radiation survey instrument; see the Work Plan for more detailed explanation. See Figure 3-1 for the specific location of each block.

FIGURE 3-1

SITE MAP



K:\GProject\middle_river\Maps\draft\response\action\plan\Block\B\Tax\Blocks.mad

4.0 SCOPE OF WORK

This section discusses the specific tasks that are to be conducted as part of this scope of work. These tasks are the only ones addressed by this HASP. Any tasks to be conducted outside of the elements listed here will be considered a change in scope requiring modification of this document. The PM or a designated representative will submit the requested modifications to this document to the HSM.

Specific tasks to be conducted include the following:

- Mobilization/demobilization activities
- Indoor Air Quality Sampling using Summa Canisters
- Soil borings via Direct Push Technology (DPT)
- · Test Pits, Excavations
- Membrane Interface Probe via DPT
- Concrete Coring
 - Installation of permanent soil gas vapor monitoring points
- Monitoring well installation
 - Installation and development using DPT
 - Soil Vapor Points Installation
- Multimedia sampling including
 - Surface water and sediment sampling from a barge
 - Groundwater
 - Soil vapor points sampling
 - Surface and Subsurface soil
 - Storm Water Sampling
 - Sediment Sampling
- Decontamination
- Geophysical Survey
- Geographical Survey
- IDW Management
- Building D Rad Investigation
- Block E additional media characterization:
 - Work area exposure surveys
 - Collection of background samples
 - Collection of soil, concrete, and perch water samples
 - Perform surface scans and removable contamination surveys for personnel protection during sampling and imaging operations.

For more detailed description of the planned tasks associated with LMC MRC, refer to the Work Plan (WP). Any tasks to be conducted outside of the elements listed here will be considered a change in scope requiring modification of this document. All requested modifications to this document will be submitted to the HSM by the PM or a designated representative.

No other activities are anticipated to be necessary. If it becomes apparent that additional or modified tasks must be performed beyond those listed above, the work is not to proceed until the FOL or SSO notifies the Project Manager and the HSM, so that any appropriate modifications to this HASP can first be developed and communicated to the intended task participants.

5.0 IDENTIFYING AND COMMUNICATING TASK-SPECIFIC HAZARDS AND SAFE WORK PRACTICES

The purpose of this section is to identify the anticipated hazards and appropriate hazard prevention/hazard control measures that are to be observed for each planned task or operation. These topics have been summarized for each planned task through the use of task-specific Safe Work Permits (SWPs), which are to be reviewed in the field by the SSO with all task participants prior to initiating any task. Additionally, potential hazard and hazard control matters that are relevant but are not necessarily task-specific are addressed it the following portions of this section.

Section 6.0 presents additional information on hazard anticipation, recognition, and control relevant to the planned field activities.

In the event of an emergency, not requiring 911, LMC facility personnel should be contacted in the order presented on Table 2-1.

5.1 GENERAL SAFE WORK PRACTICES

In addition to the task-specific work practices and restrictions identified in the SWPs (Attachment IV) the following general safe work practices are to be followed when conducting work on-site.

- Eating, drinking, chewing gum or tobacco, taking medication, or smoking in contaminated or
 potentially contaminated areas or where the possibility for the transfer of contamination exists is
 prohibited.
- Wash hands and face thoroughly upon leaving a contaminated or suspected contaminated area. If a
 source of potable water is not available at the work site that can be used for hands-washing, the use
 of waterless hands cleaning products will be used, followed by actual hands-washing as soon as
 practicable upon exiting the site.
- Avoid contact with potentially contaminated substances including puddles, pools, mud, or other such
 areas. Avoid, kneeling on the ground or leaning or sitting on equipment. Keep monitoring equipment
 away from potentially contaminated surfaces.
- Plan and mark entrance, exit, and emergency evacuation routes.
- Rehearse unfamiliar operations prior to implementation.

- Buddies should maintain visual contact with each other and with other on-site team members by remaining in close proximity to assist each other in case of emergency.
- Establish appropriate safety zones including support, contamination reduction, and exclusion zones.
- Minimize the number of personnel and equipment in contaminated areas (such as the exclusion zone). Non-essential vehicles and equipment should remain within the support zone.
- Establish appropriate decontamination procedures for leaving the site.
- Immediately report all injuries, illnesses, and unsafe conditions, practices, and equipment to the SSO.
- Observe co-workers for signs of toxic exposure and heat or cold stress.
- Inform co-workers of potential symptoms of illness, such as headaches, dizziness, nausea, or blurred vision.

5.2 DRILLING (HSA/DPT/HANDCART MOUNTED DPT UNIT/ROTOSONIC) SAFE WORK PRACTICES

The following Safe Work Practices are to be followed when working near operating drilling equipment.

5.2.1 Before Drilling

- Identify underground utilities, buried structures, and aboveground utility lines before drilling. Tetra
 Tech personnel will use the Utility Locating and Excavation Clearance Standard Operating Procedure
 provided in the Tetra Tech Health and Safety Guidance Manual.
- Drill rigs will be inspected by the SSO or designee, prior to the acceptance of the equipment at the site and prior to the use of the equipment. Needed repairs or identified deficiencies will be corrected prior to use. The inspection will be accomplished using the Equipment Inspection Checklist provided in Attachment V. Additional inspections will be performed at least once every 10-day shift or following repairs.
- Check operation of the Emergency Stop/Kill Switch and/or the "Dead Man's" operational controls.
 These operational checks are required initially as part of the equipment pre-use inspection, and then

<u>periodically</u> thereafter. Periodic checks are required at least weekly, or more frequently if recommended by the rig manufacturer.

- Ensure that machine guarding is in place and properly adjusted.
- Block drill rig and use out riggers/levelers to prevent movement of the rig during operations.
- The work area around the point of operation will be graded to the extent possible to remove any trip
 hazards near or surrounding operating equipment.
- The driller's helper will establish an equipment staging and lay down plan. The purpose of this is to keep the work area clear of clutter and slips, trips, and fall hazards. Mechanisms to secure heavy objects such as drill flights will be provided to avoid the collapse of stacked equipment.
- Potentially contaminated tooling will be wrapped in polyethylene sheeting for storage and transport to the centrally located equipment decontamination unit.
- Prior to each instance of engaging the HSA drill rig, the Driller will look to ensure that the drilling area
 is clear of personnel and obstructions, and verbally alert everyone in the area that the rig is about to
 be engaged.
- Prior to the start of boring operations, one individual will be designated at the person responsible for immediate activation of the emergency stop device (if applicable) in the event of an emergency. This individual will be made known to the field crew and will be responsible for visually checking the work area and verbally alerting everyone of boring operations prior to engaging the equipment.

5.2.2 <u>During Drilling</u>

- The Driller will ensure that an individual is constantly stationed at a location were the drill rig emergency stop switch can be immediately engaged.
- Minimize contact to the extent possible with contaminated tooling and environmental media.
- Support functions (sampling and screening stations) will be maintained a minimum distance from the
 drill rig of the height of the mast plus five feet or 35-feet for Rotosonic/HSA, 25-feet for DPT
 operations whichever is greater to remove these activities from within physical hazard boundaries.

- Only qualified operators and knowledgeable ground crew personnel will participate in the operation of the drill rig.
- During maintenance, use only manufacturer provided/approved equipment (i.e. auger flight connectors, etc.)
- In order to minimize contact with potentially contaminated tooling and media and to minimize lifting hazards, multiple personnel should move auger flights and other heavy tooling.
- Only personnel absolutely essential to the work activity will be allowed in the exclusion zone.

5.2.3 After Drilling

- Equipment used within the exclusion zone will undergo a complete decontamination and evaluation by the SSO to determine cleanliness prior to moving to the next location, exiting the site, or prior to down time for maintenance.
- Motorized equipment will be fueled prior to the commencement of the day's activities. During fueling
 operations equipment will be shutdown and bonded to the fuel source.
- When not in use drill rigs will be shutdown, and emergency brakes set and wheels will be chocked to prevent movement.
- The mast will be completely lowered and outrigger completely retracted during movement to decontamination or the next location.
- Areas subjected to subsurface investigative methods will be restored to equal or better than original condition. Any contamination that was brought to the surface by drilling or DPT operations will be removed and containerized. Physical hazards (debris, uneven surfaces, ruts, etc.) will be removed, repaired or otherwise corrected. In situations where these hazards cannot be removed these areas will be barricaded to minimize the impact on field crews working in the area.

5.2.4 Concrete Coring Operations

The following safe work practices will be employed during concrete coring operations:

Identify underground utilities before commencing any concrete operations.

- Use wetting techniques to minimize dust and friction.
- When applying water to the core bit the operator should apply water until the slurry begins to look like heavily creamed coffee.
- Wear the well-fitting nitrile gloves (rather than cotton or leather gloves) when in coring.
- Wash and dry hands before putting on gloves and every time that you remove your gloves.
- Replace grossly contaminated or worn-out gloves.
- Make sure the coring machine is properly anchored.
- Standing on the machine may cause the bit to bind up in the hole
- Use the manufacturers recommended speed (revolutions per minute) for the diameter of the bit used.
- The coring machine will be inspected to ensure housings; plugs; guards are intact, and the coring machine is in good operating order.
- If the power source to be employed is not through a Ground Fault Circuit Interrupter (GFCI) then a temporary GFCI plug extension shall be put in place.
- A shop vac or similar device also connected to the GFCI will be used to collect the water employed during the coring process. All water in the coring area will be cleaned to reduce the potential for slip, trip and falls. Place floor wet signs as necessary from all approach venues.
- The preferred method is to bolt the coring machine to the floor during coring operations. It is however
 acceptable to utilize sand bags or similar weighted devices to control movement during this activity.
- No open core holes will be permitted after the termination of the shift. All cores will be placed back in the holes or the holes will be fitted for their permanent casings for the sub-slab soil gas vapor monitoring points.
- All core holes finished with protective casings or finished using concrete will be finished to grade again to prevent slip, trips, and/or falls.

5.3 SAFE BOATING PRACTICES (I.E., WORKING FROM WATER VESSELS/BARGES)

Offshore soil boring activities will require site personnel to work from barges in tidal bodies of water. To avoid potential hazards associated with working on water (drowning), the field team shall employ lifelines (tie-off procedure), safety harnesses, when on the barge. U.S. Coast Guard (USCG) approved personal flotation devices (PFD) will be on hand for all participants and will be used. Due to the obvious hazards associated with working on water during inclement weather, field activities may be temporarily suspended or terminated at the discretion and direction of the FOL or SSO. Tetra Tech personnel will also follow the Tetra Tech procedures for working over water outlined in Standard Opering Procedure SWP 5-6 found in Attachment VI

Refer to the Tetra Tech Boat Safety Checklist in Attachment VII of this HASP.

5.3.1 <u>U.S.C.G. Flotation Device Types</u>

Use the following information to determine the proper type of U.S.C.G. PFD.

Off Shore Life Jacket (Type I, 22lbs buoyancy)

Type I life jacket is the best choice for rough or open waters. This type will float you the best and is favorable if rescue may be long in coming. This type will turn an unconscious person upright in the water. Though is bulky it does have a highly visible color for easier detection.

Near Shore Buoyant Vest (Type II, 15.5lbs buoyancy)

Type II is a good choice for calmer waters. It will turn most unconscious persons face-up in the water. Though it is less bulky than Type I, it is not intended for long hours in calm or rough water.

Flotation Aid (Type III, 15.5lbs buoyancy)

Type III is probably the most comfortable device offering more freedom of movement, such as water skiing or fishing, but is not intended for rough water. Also, an unconscious person may end up face-down in the water.

Throwable Devices (Type IV)

Throwable devices are intended for calm waters with heavy boat traffic where help is always close. It is not intended for unconscious persons or non-swimmers or long hours in the water. They are good backups for the other devices.

Site personnel shall wear Type III personal flotation devices in the event someone falls overboard, boats sinks or capsizes. Type IIIs were selected as they offer the most flexibility for working while still meeting minimum requirements for buoyancy. In situations where personal flotation devices cannot be worn due to the task to be conducted, the flotation devices shall be immediately available/accessible. It is recommended that personal flotation devices be continually worn during colder months due to the potential for hypothermia to restrict muscle movement and therefore, self rescue and maintaining buoyancy. In addition, a single Type IV Throwable Flotation Device shall be maintained on board the boat with at least 90 feet of 3/8 polypropylene line.

When work activities take personnel within four feet of navigable waters edge personnel will have immediately accessible a lifeline with a throwing bag or Type IV flotation device facilitate extraction from the water. Personnel working on water's edge will do so using the buddy system to assist in rescue efforts, if needed.

Device	Туре	Description
Off Shore Life Jacket	Type I 22lbs buoyancy	Best in rough or open waters. Floats best especially in long time rescue. Will turn unconscious upright. Bulky but highly visible.
Near Shore Buoyant Vest	Type II, 15.5lbs buoyancy	Good in calmer waters. Will turn most unconscious face-up. Less bulky. Not for long time rescue.
Flotation Aid	Type III 15.5lbs buoyancy	Most comfortable device offering more freedom of movement. Not intended for rough water. Unconscious may end up face-down
Throwable Devices	Type IV	Throwable devices for calm waters with heavy boat traffic where help is always close. Not for unconscious, non-swimmers or long hours. Good backups for the other devices.

5.3.2 U.S.C.G Boat Regulations

No person born on or after January 1, 1986 shall operate a vessel that is fitted with propulsion machinery of more than ten (10) horsepower on waterways unless the person has successfully completed a boating safety education program as approved by the director of the Department of Environmental Management. Certain bodies of water in some states may also have local restrictions as to type and size of watercraft or motor horsepower, restricted use areas, boat speed, and times for use. The FOL is responsible for authorities checking with appropriate local to identify and address any additional requirements/restrictions.

The U.S.C.G. requires boats to have the following equipment on board:

- One personal flotation device per person
- A sound producing device such as an air horn or whistle which can be heard one half mile.

Speed Limits

Any motorboat or vessel operated within a harbor or inlet or any pond of other confined body of water shall not exceed 45 mph from sunrise to sunset and 25 mph during periods of darkness or restricted visibility. Lower speed limits may be regulated in certain areas.

Reckless and Negligent Operation

Negligent or grossly negligent operation of a vessel which endangers lives and/or property is prohibited by law. A civil penalty may be imposed by the Coast Guard for this offense under federal laws. An operator may be subjected to a fine of up to \$5,000 and or imprisonment for up to one year, or both. The Maryland penalty is a fine of up to \$500 for the first offense.

Some examples of actions that may constitute negligent or grossly negligent operation include but are not limited to:

- Operating in a swimming area
- Operating under the influence of alcohol or drugs.
- Excessive speed in the vicinity of other boats or in dangerous waters.
- Hazardous water skiing practices
- Bow riding, also riding on seatback, gunwale or transom.

Termination of Use

A Maryland Natural Resources Police Officer who observes a boat being operated in an unsafe condition and who determines that an especially hazardous condition exists may direct the operator to take immediate steps to correct the condition, including returning to port. Termination for unsafe use may be imposed for, but is not limited to:

- Insufficient number of USCG approved Personal Flotation Devices.
- Insufficient fire extinguishers.
- Overloading beyond manufacturer's recommended safe loading capacity.
- Improper navigation light display.

- Ventilation requirements for tank and engine spaces not met.
- Fuel leakage.
- Fuel in bilges.
- Improper backfire flame control.

Boating Accident Reports

The operator of any boat involved in an accident must stop, render assistance, and offer identification. An accident report must be made to the Department within 48 hours if:

- A person dies within 24 hours;
- A person loses consciousness or receives medical treatment beyond first aid or is disabled more than 24 hours;
- A person disappears from the vessel under circumstances that indicate death or injury.

Accidents must be reported within 10 days if damage to all vessels and other property totals more than \$500.00 or an earlier report is not required. Running aground or hitting a fixed or floating object is considered a boating accident. Boating accident report forms (DNR-149) are obtainable from the Natural Resources Police. They must be submitted to the Natural Resources Police by the operator of the vessel or vessels involved. Accident reports are required by federal law and furnish information for use in accident prevention. Information from individual reports will not be publicly disclosed nor may the information be used in court.

Rendering Assistance


Federal law requires the operator of a vessel to provide assistance that can be safely provided to any individual in danger on the water. Persons who fail to provide assistance may be subject to fine or imprisonment.

Vessels Required to be Registered in Maryland


All vessels, whether commercial or recreational, must be registered in Maryland if it is equipped with any kind of primary or auxiliary mechanical propulsion; if it is not currently documented with the U. S. Coast Guard; and if it is being used principally in Maryland. An owner of a federally documented vessel, though exempt from state numbering requirements, shall apply to the Maryland Department of Natural Resources for documented use decals, and is subject to the state excise tax requirements.

5.3.3 <u>Uniform State Waterway Marking System (USWMS)</u>

Lateral System (As Seen Entering From Seaward)




Preferred Channel No Numbers-May Be Lettered Preferred Channel To Starboard Topmost Band Green



Preferred Channel No Numbers-May Be Lettered


Preferred Channel To Port Topmost Band Red

Red Light Only



Lateral Aids to Navigation generally indicates which side of an aid to navigation a vessel should pass when channels are entered from seaward. In the absence of a route leading from seaward, the conventional direction of buoyage, generally follows a clockwise direction around landmasses. The most important characteristic of an aid is its color. The "3R" rule "Red Right Returning" is the essential rule of thumb for using the lateral system. This means that when entering one body of water from a larger body of water (i.e. returning to a harbor from a bay or sound), keep the red aids to starboard (right) side and green aids to port (left) side. In addition, each aid is numbered, and these numbers increase as entering from seaward.

Preferred Channel Marks are found at junctions of navigable channels and often mark wrecks or obstructions. A vessel may normally pass this aid on either side, but the top color band indicates the preferred channel. If the top band of the aid is red, it is treated as a red mark and kept to starboard as the vessel passes it while returning from sea. Caution: It may not always be possible to pass on either side of preferred channel aids to navigation. The appropriate nautical chart should always be consulted.



Cardinal System

May show white reflector or light



white buoy

Do not pass between buoy and nearest shore



Black topped white buoy

Pass to north or east of buoy



Red topped white buoy

Pass to south or west of buoy

5.4 PERMANENT SOIL GAS VAPOR MONITORING POINTS WITHIN BUILDINGS SAFE WORK PRACTICES

Installation of permanent soil gas vapor monitoring points will be conducted within buildings on site. Soil gas monitoring points will be installed at various locations using electric powered concrete coring machine will be used to push through the concrete floor.

Prior to installation of the VMPs, appropriate procedures will be followed to address the potential presence of asbestos-containing materials (ACM) at all proposed VMP locations. An outside contractor licensed by the State of Maryland to manage all aspects of asbestos will perform inspections and

sampling if necessary to determine the absence or presence of ACM prior to any work being performed. If necessary, ACM such as floor tile will be removed to facilitate installation of the new VMPs. All removed materials will be replaced to prevent any potential tripping hazards. After final locations have been established, Tetra Tech will initiate subsurface utility clearance. Tetra Tech will place a call to Miss Utility and, in addition, will use a private utility locating service (Enviroscan) to identify and mark subsurface utilities and anomalies. All utilities within a 15-foot radius of each designated drilling location will be located using the appropriate technology and marked with paint. Standard utility locating methods may not be effective based on the presence of subsurface metal (rebar) or the presence of metal-stored materials. In the case that standard methods are not effective, alternative methods such as line tracing will be utilized to effectively identify and mark any utilities. Proposed VMP boring locations may be offset based on the results of the asbestos or subsurface utility survey.

Operation of electric powered equipment within enclosed areas such as buildings presents the hazard of dusts generated during concrete coring. Additional hazards that may be present during these operations include, increased noise levels, contact with utilities, electrocution hazards (particularly if water is present). Use wetting methods to suppress airborne dusts generated during concrete coring within a building.

5.5 EXCAVATION SAFE WORK PRACTICES

Soil excavation activities will be performed through the use of a track or wheel mounted excavator that is outfitted with a boom and excavator bucket that is adequate to complete the entire excavation task in a manner that will not involve or require any entry into the open excavation by any person or by any part of the excavator except for the boom/bucket. The process for performing the excavation and the visual inspections will involve the following:

- 1. First, any surface encumbrances within the intended work area of the excavation will be removed or supported, as necessary, in accordance with OSHA 1926.651(a).
- 2. The FOL will assure that the intended excavation area is cleared of any utility installations that may reasonably be expected to be encountered during excavation work (in accordance with the Tetra Tech Utility Locating SOP and with OSHA 1926.651 [b]).
- 3. Prior to being put into service at the site, the excavator will be inspected by the SSO, and this inspection will be documented.
- 4. The excavator will be positioned and operated so that it never approaches closer than 4 feet from the edge of an open excavation (other than the boom and bucket portion of the excavator).
- 5. At no time during the active operation of the excavator will any person (other than the operator) be permitted to approach the vehicle closer than a distance of the length of the excavator boom and bucket (fully-extended) plus 5 feet, but not less than 25 feet, whichever is greater.

6. After a test pit has been created, and after the excavator has been either removed or completely neutralized or shut down, Tetra Tech personnel may approach to perform the visual inspection activities. Tetra Tech personnel will not be permitted to enter any open excavation or approach closer than 2 feet from the edge of an open excavation.

Hazards associated with these activities may include:

- Being struck by the excavator or being trapped between an immovable object and the excavator.
- Being struck by truck traffic being loaded out.
- Slips, trips, and falls associated with movement over uneven terrain or over the sidewall of the excavation
- Contact with contaminants of concern.

Control measures will include:

- The Tetra Tech Site Safety Officer will serve as the Excavation Competent Person (as defined in OSHA 1926.651 [b], as "one who is capable of identifying existing and predictable hazards in the surroundings, or working conditions which are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them".
- Assuring that all personnel remain clear of the operating excavator at all times during its operation (a minimum "no approach" zone of 25 feet from the excavator or the length of the fully extended excavator boom/bucket length plus 5 feet, whichever is greater).
- All work tasks will be performed in a manner that does not require any entry into an open excavation. In fact all persons are to be restricted form approaching within 2 feet of the edge of any open excavation.
- The FOL and the Excavator Operator will establish and maintain clear communications at all times.
 Also, the FOL is responsible for assuring that all persons are aware that it is their responsibility to remain outside of the "No Approach" Zone and out of the operator's blind spots.
- Hard hat, hearing protection and a high visibility vest will be required by all persons working near the
 excavation work area. Also, all personnel will be required to wear steel toe safety footwear,
 preferably with sole designs that include an aggressive lug to enhance traction
- Personnel will be made aware that they are to never place him/herself between the excavator and an immovable object.
- The assignment of an Excavation Competent Person is also an important part of hazard recognition, evaluation, and control to protect personnel during excavation activities.

Excavation Competent Person (ECP)

The ECP is responsible for addressing responsibilities as defined in OSHA 29 CFR 1926 Subpart P. For this project, the SSO will serve as the ECP. Specific ECP responsibilities include the following:

- Assuring that surface encumbrances are avoided, removed, or supported in accordance with (IAW)
 OSHA 1926.651 (a)
- Assuring that the FOL has accomplished the utility locating/avoidance processes prior to beginning any excavation (IAW 1926.651 [b])
- Assuring that no load (e.g., excavator boom or bucket) passes over the head of any person (IAW 1926.651[e])
- Assuring that adjacent structures, sidewalks, etc. are not undermined by excavation activities.
- Assuring that stockpiled material is placed in a location, at a height, and in a manner that does not represent the hazard of employees being struck by loose or falling materials.
- Because it is anticipated that excavations will be backfilled to grade the same day that they are created, the need to perform visual inspections (such as daily and after rain events, as specified in OSHA 1926.651[k][1]) should not be necessary. However, if such a need is encountered due to inclement weather or other reason, the ECP will be responsible for performing and documenting these excavation inspections. The inspection checklists in Attachment V are provided for this purpose.
- Assuring that stockpiled material will be placed no closer than 4 feet from the edge of an open excavation.

5.6 HAND AND POWER TOOL SAFE WORK PRACTICES

The following safe work practices will be employed during hand and power tool usage:

- All hand and power tools will be maintained in a safe condition.
- Electrical power tools shall be grounded or double insulated with proper assured equipment grounding inspections or Ground Fault Interrupter (GFI) circuit protection provided.
- Pneumatic power tools shall be secured to the hose or whip by some positive means.
- Only properly trained Contractor employees shall operate power-actuated tools.
- All grinding machines shall conform to OSHA and ANSI requirements.

Hand and power tool use procedures are detailed in Section 3.16 of the LM handbook and will be followed.

5.7 HOUSEKEEPING / CLEANUP SAFE WORK PRACTICES

Housekeeping procedures described in Section 5 of the LM Handbook (Attachment I) will be addressed and the following housekeeping practices will be employed during this field effort:

- Ensure discharge permits and/or Stormwater Pollution Prevention Plans (if applicable) are available at the project job site.
- Tetra Tech and/or subcontractor personnel will clean up its respective work area(s) and maintain work areas free from all slip, trip, and fall hazards at all times.
- Debris shall be kept cleared from work areas, passageways, stairs, and in and around buildings or other structures. The work area must be left free from accumulation of waste and rubbish at the end of each work shift.
- Combustible scrap and debris shall be removed at regular intervals during the course of work. Safe means shall be provided to facilitate such removal.
- At the end of each working day and/or the conclusion of work being performed, the work area will be
 restored to the same degree of neatness as when work commenced.
- Tetra Tech and/or subcontractor will furnish necessary equipment and/or receptacles to remove waste and rubbish from the job site unless otherwise specified by Lockheed Martin.

6.0 HAZARD ASSESSMENT AND CONTROLS

This section provides reference information regarding the chemical and physical hazards which may be associated with activities that are to be conducted as part of the scope of work.

6.1 CHEMICAL HAZARDS

The areas in this investigation have been characterized. Based on historical data from past use and previous sampling events the following contaminants were found to exist at the site:

- VOCs
- SVOCs
- Metals
- PCBs

Although the above chemicals are identified as site contaminants, the latest sampling data indicates that the chemicals in Table 6-1 are the primary contaminants of concern to site personnel performing intrusive work. Although all the chemical contaminants listed above may be present, not all are approaching levels of concern from a human health aspect. The chemicals of concern (COCs) listed below could approach airborne concentrations reaching current occupational exposure limits (OEL). Table 6-1 below shows these and/or common types of these constituents, and a comparison of potential worst case air concentrations (when available) with current Occupational Exposure Limits (OELs).

TABLE 6-1
COMPARISON OF COPCs, AVAILABLE WORST-CASE AIR CONCENTRATIONS,
AND CURRENT OCCUPATIONAL EXPOSURE LIMITS

Contaminant of Concern (in soil)	Maximum Concentration In Soil	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV		
		Block D			
Benzene	0.02 mg/kg in soil	1.25 ppm	ACGIH: 0.5 ppm TWA ₈ 1 ppm STEL		
Carbon Disulfide	0.035 mg/kg in soil	5.85 ppm	OSHA: 4 ppm		
Methylene Chloride	0.12 mg/kg in soil	31.49 ppm	OSHA: 25 ppm		

TABLE 6-1 COMPARISON OF COPCs, AVAILABLE WORST-CASE AIR CONCENTRATIONS, AND CURRENT OCCUPATIONAL EXPOSURE LIMITS

Block E							
Contaminant of Concern (in soil)	Maximum Concentration In Groundwater	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV				
Acetone	16 mg/kg in soil	2,317.77 ppm	OSHA: 1000 ppm ACGIH: 500 ppm, TWA ₈				
Chlorobenzene	4 mg/kg in soil	23.62 ppm	OSHA: 75 ppm ACGIH: 10 ppm, TWA ₈				
1,2 Dichlorobenzene	1,20 mg/kg in soil	70.28 ppm	OSHA: NA ACGIH: 25 ppm, TWA ₈				
1,4 Dichlorobenzene	130 mg/kg in soil	93.28 ppm	OSHA: 75 ppm ACGIH: 10 ppm, TWA ₈				
Methylene Chloride	4.8 mg/kg in soil	1,259.65 ppm	OSHA: 25 ppm ACGIH: 50 ppm, TWA ₈				
PCBs	24,000 mg/kg	0.10 ppm	OSHA: 0.37 ppm				
Trichlorobenzene	9600 mg/kg	381.50 ppm	OSHA: 5ppm				
Vinyl Chloride	0.004 mg/kg in soil	4.55 ppm	OSHA: 1 ppm, TWA ₈ 5 ppm Ceiling				
Contaminant of Concern (in water)	Maximum Concentration In Water	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV				
Carbon Tetrachloride	13 ug/l in water	2.33 ppm	OSHA: 10 ppm ACGIH: 5 ppm TWA ₈				
Trichlorobenzene	11,000 ug/l in water	86.1 ppm	OSHA: NA ACGIH: 5 ppm, Ceiling ₈				
TCE (VOC)	19,000 ug/l in water	1,424.39 ppm	OSHA: 300 ppm Ceiling ACGIH: 50 ppm TWA ₈ 100 ppm STEL				
	Block F						
Contaminant of Concern (in soil)	Maximum Concentration In Soil	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV				
Napthalene	159 mg/kg in soil	36.62 ppm	OSHA: 10 ppm ACGIH: 10 ppm TWA ₈				

TABLE 6-1 COMPARISON OF COPCS, AVAILABLE WORST-CASE AIR CONCENTRATIONS, AND CURRENT OCCUPATIONAL EXPOSURE LIMITS

Block G					
Contaminant of Concern (in soil)	Maximum Concentration In Soil	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV		
1,1-Dichloroethene	0.007 mg/kg in soil	1.8 ppm	OSHA: NA ACGIH: 5 ppm, TWA ₈		
Contaminant of Concern (in water)	Maximum Concentration In Water	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV		
1,1-Dichloroethene	780 ug/l in water	210.01 ppm	OSHA: NA ACGIH: 5 ppm, TWA ₈		
Trichloroethylene	2,800 ug/l in water	209.91 ppm	OSHA: 100 ppm ACGIH: 10 ppm, TWA ₈		
Vinyl Chloride (VOC)	7.2 ug/l in water	3.2 ppm	OSHA: 1 ppm, TWA ₈ 5 ppm Ceiling		

Block H

Various VOC's - none found to be above threshold limits in soil or water

Block I Note: At this time work will not be conducted in Block I but this info is placed here for future investigations.

Contaminant of Concern (in soil)	Maximum Concentration In Soil	Worst-Case Air Concentration That Could Be Encountered	Current OSHA PEL or ACGIH TLV
Benzene	0.45 mg/kg	28.19 ppm	ACGIH: 0.5 ppm TWA ₈ 1 ppm STEL
1,2,3, Trimethylbenezene	11 mg/kg	10.6 ppm	OSHA: NA ACGIH: 25 ppm, TWA ₈
1,2,4- Trimethylbenezene	46 mg/kg	47.7 ppm	OSHA: NA ACGIH: 25 ppm, TWA ₈
1,1-Dichloroethane	4.3 mg/kg	482.98 ppm	OSHA: 100 ppm TWA ₈ ACGIH: 100 ppm, TWA ₈
1,1-Dichloroethene	0.74 mg/kg	180.12 ppm	OSHA: NA ACGIH: 5 ppm, TWA ₈
1,1,1-Trichloroethane	22 mg/kg	1,119.31 ppm	OSHA: 350 ppm TWA ₈ ACGIH: 350 ppm, TWA ₈
Vinyl Chloride	0.031 mg/kg	40.34 ppm	OSHA: 1 ppm, TWA ₈ 5 ppm Ceiling
Xylene	36 mg/kg	181.66 ppm	OSHA: 350 ppm TWA ₈ ACGIH: 350 ppm, TWA ₈
Lead	2,600 mg/kg	4.81 mg/m3	OSHA: 0.05 mg/m3 TWA ₈ ACGIH: 0.05 mg/m3, TWA ₈

Table Notes:

TWA₈: Average air concentration over an 8-hour work period that is not to be exceeded OSHA Ceiling: Concentration in air that is not to be exceed

Note: All sites contain various metals, however none above occupational exposure limits if visible dust is observed. Area wetting methods will be used to suppress dust at all locations.

As indicated in Table 6-1, are from a worst-case scenario, COC concentrations immediately above a captured air phase above contaminated soil or water (such as in the head space during soil drilling or excavation activities) could potentially reach concentrations that exceed the OELs. However, in regarding the results of this data evaluation, it is important to recognize the following:

- The planned work area is outdoors with ample natural ventilation that will reduce any airborne VOCs through dilution and dispersion
- The soil value used in this evaluation was the <u>highest</u> concentration detected during the most recent soil sampling events

As a result of these factors, it is possible that workers participating in site activities may encounter airborne concentrations of COCs that could represent an occupational exposure concern, however it is unlikely. To monitor this route, real-time direct reading monitoring instruments will be used (as described in Section 7.0). This will be performed during the intrusive tasks in soil and IDW management activities, as these tasks are the most likely to involve encountering/releasing any VOCs into the airphase.

Potential exposure concerns to the COCs may also occur through ingestion, or coming into direct skin contact with contaminated groundwater. The likelihood of worker exposure concerns through these two routes are considered unlikely, provided that workers follow good personal hygiene and standard good sample collection/sample handling practices, and wear appropriate PPE as specified in this HASP. Examples of onsite practices that are to be observed that will protect workers from exposure via ingestion or skin contact include the following:

- No hand-to-mouth activities on site (eating, drinking, smoking, etc.)
- Washing hands upon leaving the work area and prior to performing any hand to mouth activities
- Wearing surgeon's-style gloves whenever handling potentially-contaminated media, including groundwater and any potential free product, sampling equipment, and sample containers.

6.1.1 <u>Volatile Organic Compounds (VOCs)</u>

The majority of VOCs are often related to chlorinated solvents and associated degradation products, paint thinners, dry cleaning solvents, constituents of petroleum fuels (e.g. gasoline and natural gas), and crude oil tanking. Symptoms of exposure to VOCs can include abdominal pain, irritation of the skin, eyes, nose, and throat, dizziness, tremors, vomiting, GI bleeding, enlarged liver, pallor of the extremities, and frostbite like-symptoms.

Short-term exposure to VOCs, such as TCE and VC, can cause irritation of the nose and throat and central nervous system (CNS) depression, with symptoms such as drowsiness, dizziness, giddiness, headache, loss of coordination. High concentrations have caused numbness and facial pain, reduced eyesight, unconsciousness, irregular heartbeat and death. Very high concentrations have produced death due to CNS effects, and, in rare cases, irregular heart beat. Permanent nervous system damage and/or liver injury have resulted from severe overexposure.

6.1.2 Metals

The physical effects of poisoning from the heavy metals tend to be a very slow process and occur over a long period of continued exposure to the source of the toxic metal. The physical symptoms which are typically induced by the presence of toxic metals in the body tend to be very vague and can include

symptoms such as persistent fatigue, the appearance of splitting and blinding headaches, the presence of an upset stomach, disorders such as colic and even anemia in some cases. The central nervous system is the main part of the human body likely to be affected by the presence of toxic metals. Symptoms of a disrupted central nervous system include the appearance of muscular tremors, the development of spells of dizziness, the presence of insomnia, the poor concentration abilities in the person and a sudden lack of muscular coordination in the body.

6.2 EXHAUST GASES/FUMES CREATED DURING INDOOR ACTIVITIES

Short-term (acute) effects of workers exposed to high concentrations of exhaust gasses/fumes may include irritation of the eyes, nose, and throat; lightheadedness; heartburn; headache; weakness, numbness and tingling in the extremities; chest tightness; wheezing; and vomiting. Some studies have suggested that workers exposed to diesel/gasoline exhaust are more likely to have chronic respiratory symptoms such as persistent cough and mucous, bronchitis, and reduced lung capacity than unexposed workers. Of particular concern is the potential for exposure to carbon monoxide which is present in diesel and more predominately, in gasoline engine exhaust. Upon entering the bloodstream, carbon monoxide combines with hemoglobin over 200 times more tightly than oxygen. Hemoglobin, then, is unable to carry oxygen in the blood. Carbon monoxide may also combine with myoglobin which may cause muscle metabolism disturbances, especially in the heart. The degree of toxicity depends primarily on carbon monoxide concentrations, exposure time, individual susceptibility, and exertion level.

To prevent or minimize potential exposures to carbon monoxide and other exhaust gas constituents, safe work practices identified in Section 5.4 and air monitoring measures listed Section 7.1.2 will be used.

6.3 RADIOLOGICAL HAZARDS

Based on historical information, and the results of previous screening and sampling events, alpha, beta and gamma radiation may exist at Former Building D. Unstable radioactive elements can be found in a wide range of concentrations in all rocks, soil, and water. The most common radioactive elements, uranium and thorium, decay slowly and produce other radioactive elements, such as radium, which in turn undergo still further radioactive decay. These radioactive product elements have different chemical properties, decay at different rates, and emit different levels of radiation energy than either uranium or thorium. The two most common isotopes of radium (Ra) are Ra-226 and Ra-228. Ra-226 has a long half-life (1,600 years) compared to that of Ra-228 (5.75 years). A half-life is the time required for half of the initial amount of a radionuclide to decay. Ra-226 decays by emitting the nucleus of a helium atom (alpha particle), whereas Ra-228 emits an electron (beta particle). Radiological survey and soil sampling activities will be performed to determine if remedial actions have removed radiological contamination to acceptable levels.

Of particular concern are exposures that occur as a result of inhalation of radium dusts or radium contaminated particles. However, site activities are unlikely to generate airborne dusts that can be inhaled. Rather the greatest potential for exposure is anticipated to be via ingestion of contaminated soils as a result of hand to mouth activities (eating, drinking, smoking, etc.). As a result, minimizing contact with potentially contaminated soils through the use of avoidance and ppe use as well as the implementation of sound decontamination procedures and personal hygiene practices will be used to prevent exposures to radium. Safe work permits contained in Attachment IV provide specific control methods that will be used to minimize potential exposures to site personnel.

6.4 SUB SLAB AND IAQ SAMPLING BUILDINGS A,B,C

Previous sampling data indicates the presence of VOC'S, within Block I (see Table 6-1) for concentrations.

6.5 PHYSICAL HAZARDS

The following is a list of physical hazards that may be encountered at the site or may be present during the performance of site activities.

- Slips, trips, and falls
- Cuts (or other injuries associated with hand tool use)
- Lifting (strain/muscle pulls)
- Ambient temperature extremes (heat stress)
- · Pinches and compressions
- Vehicular and foot traffic
- Noise in excess of 85 dBA
- Flying projectiles
- Contact with underground or overhead utilities/electrical safety
- Heavy equipment hazards (rotating equipment, hydraulic lines, etc.)
- Compressed gas cylinders

Specific hazards are discussed further below, and are presented relative to each task in the task-specific Safe Work Permits.

6.5.1 Slips, Trips, and Falls

During various site activities there is a potential for slip, trip, and fall hazards associated with wet, steep, or unstable work surfaces. To minimize hazards of this nature, personnel required to work in and along areas prone to these types of hazards will be required to exercise caution, and use appropriate precautions (restrict access, guardrails, life lines and/or safety harnesses) and other means suitable for the task at hand. Site activities will be performed using the buddy system.

6.5.2 Strain/Muscle Pulls from Heavy Lifting

During execution of planned activities there is some potential for strains, sprains, and/or muscle pulls due to the physical demands and nature of this site work. To avoid injury during lifting tasks personnel are to lift with the force of the load carried by their legs and not their backs. When lifting or handling heavy material or equipment use an appropriate number of personnel. Keep the work area free from ground clutter to avoid unnecessary twisting or sudden movements while handling loads.

6.5.3 <u>Heat/Cold Stress</u>

Because of the length of planned project activities, the likely seasonal weather conditions that will exist during the planned schedule, and the physical exertion that can be anticipated with some of the planned tasks, it will be necessary for the field team to be aware of the signs and symptoms and the measures appropriate to prevent cold stress. This is addressed in detail in Section 4.0 of the Tetra Tech Health and Safety Guidance Manual, which the SSO is responsible for reviewing and implementing as appropriate on this project. Tetra Tech personnel will also follow the guidance for Heat Stress and prevention of Sun Exposure found in Tetra Tech Safe Work Procedures SWP 5-15 and 5-26 found in Attachment VIII.

6.5.4 Pinch/Compression Points

Handling of tools, machinery, and other equipment on site may expose personnel to pinch/compression point hazards during normal work activities. Where applicable, equipment will have intact and functional guarding to prevent personnel contact with hazards. Personnel will exercise caution when working around pinch/compression points, using additional tools or devices (e.g., pinch bars) to assist in completing activities.

6.5.5 Natural Hazards

Natural hazards such as poisonous plants, bites from poisonous or disease carrying animals or insects (e.g., snakes, ticks, mosquitoes) are often prevalent at sites that are being investigated as part of

hazardous waste site operations. To minimize the potential for site personnel to encounter these hazards, nesting areas in and about work areas will be avoided to the greatest extent possible. Work areas will be inspected to look for any evidence that dangerous animals may be present. Based on the planned location for the work covered by this HASP, encountering wild animals is not a likely probability.

During warm months (spring through early fall), tick-borne Lyme disease may pose a potential health hazard. The longer a disease carrying tick remains attached to the body, the greater the potential for contracting the disease. Wearing long sleeved shirts and long pants (tucked into boots and taped) will prevent initial tick attachment, while performing frequent body checks will help prevent long term attachment. Site first aid kits should be equipped with medical forceps and rubbing alcohol to assist in tick removal. For information regarding tick removal procedures and symptoms of exposure, consult Section 4.0 of the Health and Safety Guidance Manual.

Contact with poisonous plants and bites or stings from poisonous insects are other potential natural hazards. Long sleeved shirts and long pants (tucked into boots), and avoiding potential nesting areas, will minimize the potential for exposure. Additionally, insect repellents may be used by site personnel. Personnel who are allergic to stinging insects (such as bees, wasps and hornets) must be particularly careful since severe illness and death may result from allergic reactions. As with any medical condition or allergy, information regarding the condition must be listed on the Medical Data Sheet (see Attachment III of this HASP), and the FOL or SSO notified.

6.5.6 Vehicular and Equipment Traffic

Vehicle and equipment traffic hazards are present for both indoor and outdoor work. While conducting work inside Buildings A, B and C workers should be aware of various vehicles and equipment including but not limited to forklifts, golf carts, maintenance carts and bicycles. All indoor means of vehicular transport are either manual or propane powered as to avoid producing toxic fumes in an indoor environment. Caution should be taken while walking, riding or conducting work in these buildings. Pedestrian traffic should walk in painted aisles marked on the ground whenever possible and should take caution when approaching intersections in the buildings. Mirrors and motion alarms notify of pedestrian and vehicular traffic as they approach major intersections throughout the buildings, however, every intersection does not possess these same warning methods. Each worker must receive cart training provided by either the onsite maintenance contractor or a qualified person who has already received the training. Cart traffic shall always yield to pedestrian traffic. Each cart is also equipped with a horn that can be used when approaching an intersection or a blind corner to notify any oncoming traffic.

If working in or near streets or roadways, hazards associated with vehicular and equipment traffic are likely to exist during various site activities and whenever site personnel performed work on or near

roadways. Site personnel will be instructed to maintain awareness of traffic and moving equipment when performing site activities. When working near roadways, site personnel will wear high visibility vests. Also, when conducting work other methods of traffic safety will be utilized such as strategically positioning the worker's truck, the use of traffic cones, traffic signs and caution tape to quarantine off each work site. Workers shall also be aware of the potential for train traffic through the site. The train runs in a northern direction from Tilley Chemical (neighboring chemical packaging and distribution company) along the western side of Building A out to a railway located north of Eastern Boulevard. All personnel should be cautious of the train running thru work areas. At this time all work areas are not within the railroad right of way but site personnel should be cautious when working in the vicinity of the train tracks.

6.5.7 <u>Inclement Weather</u>

Project tasks under this Scope of Work will be performed outdoors. As a result, inclement weather may be encountered. In the event that adverse weather (electrical storms, snow, ice, tornadoes, etc.) conditions arise, the FOL and/or the SSO will be responsible for temporarily suspending or terminating activities until hazardous conditions no longer exist.

6.5.8 Contact with Underground or Overhead Utilities/Electrical Safety

Contact with energized sources can result in severe injury and even death. There are two areas of concern with this potential hazard: contact with energized processing equipment and contact with energized utilities including underground utilities (i.e., electrical transmission lines, gas lines, water lines, etc.) and overhead utilities (i.e., power lines, etc.).

- Use and application of the Tetra Tech Standard Operating Procedure (SOP) for Utility Locating and Excavation Clearance found in the Tetra Tech Health and Safety Guidance Manual will be employed. This procedure provides step-by-step instructions for clearance of underground utilities, as well as avoidance techniques, and required documentation.
- Establishment of a suitable clearance distance (20-feet) from overhead utilities will be the primary method to control hazards conveyed through contact with these power sources.
- Identify underground utilities and buried structures before commencing any DPT operations. Follow the Tetra Tech Utility Locating and Excavation Clearance Standard Operating Procedure.

In addition, the electrical safety procedures stipulated in Section 3.9 of the LM Handbook and the overhead power line safety procedures in Section 3.14 of the LM Handbook will also be followed.

No hazardous energy work is being conducted as part of this field effort. However, should activities associated with lockout/tagout be required, the requirements stipulated in Section 3.5 of the LM Handbook (Attachment I) will also be adhered to.

6.5.9 <u>Heavy Equipment Hazards</u>

Ensure that workers are thoroughly trained and competent to perform their assigned task with the equipment used in investigation. Ensure that back-up alarms are functional on equipment. Heavy equipment will be subjected to an equipment inspection, upon arrival on-site and prior to leaving. This inspection will be recorded on the Equipment Inspection Checklist provided in Attachment V of this HASP. The equipment operators and on-site Supervisors responsible for the equipment are to ensure that the Equipment Inspection Checklist has been reviewed and completed, and that all moving parts are guarded if such parts are exposed. Check/test all emergency stop controls. Use escort vehicles with flashing lights to ward and control local traffic when moving large equipment to support area.

Only trained and authorized workers may operate heavy equipment, industrial vehicles and/or cranes. All manufacturer's specifications and limitations will be adhered to.

In addition, the heavy equipment, industrial vehicle, and crane operation safety procedures stipulated in Section 3.13 of the LM Handbook and will be followed.

6.5.10 Compressed Gas Cylinders

Work utilizing compressed gas cylinders is not anticipated as part of this field effort. However, if work utilizing compressed gas cylinders is required, this HASP will be updated/amended as necessary and the procedures in Section 3.17 of the LM Handbook (Attachment I) will be followed.

7.0 AIR AND RADIATION MONITORING

The COCs outlined in Section 6 have the potential to be present in concentrations that could present an inhalation hazard during planned site activities at the individual blocks. To assure that such exposures are avoided and documented, a direct reading instrument will be used to monitor worker exposures to chemical hazards present at the various blocks. A Photoionization Detector (PID) using a lamp energy of 11.7 eV will be used to monitor the air when conducting site activities. For Block I only a Flame Ionization Detector (FID) will be used to detect the presence of 1,1 Dichloroethane which is not detected by the PID. A Draeger Tube 0.5/a will be used when the presence of VOCs is confirmed. The PID will be used for most onsite activities to screen source areas (sample locations, monitoring wells, etc.) and worker breathing zones for volatile and detectable site contaminants. The presence of elevated airborne concentrations of volatile organic compounds will suggest an increased exposure threat to site personnel and will require site activities to be suspended until readings return to background levels. The use of personal protective equipment and the observance of the other control requirements presented in this HASP have been selected to minimize potential for personnel exposures to hazardous concentrations (known or unknown) of site contaminants.

Some COCs (PAHs, PCB, metals) are not volatile and are unable to be detected with traditional field instrumentation (photoionization detectors). For metals visible dust will require area wetting to control the dust since the level of the contaminants are above the visible spectrum. Generation of dusts should be minimized. If airborne dusts are observed, use area wetting methods. Site contaminants may adhere to or be part of airborne dusts or particulates. Although unlikely to be present, the generation of dusts should be minimized to avoid inhalation of contaminated dusts or particulates.

Instruments will be used primarily to monitor source points and worker breathing zone (BZ) areas, while observing instrument action levels. The SSO shall obtain and document the daily background reading at an upwind, unaffected area and observe for readings above that background level. The SSO shall monitor source areas (e.g., above collected samples and confined areas, etc.) for the presence of any reading above the daily-established background level. If elevated readings are observed above the PEL, the SSO shall monitor the workers' BZ areas. If elevated readings are observed, the following process will be followed:

- The SSO shall order site personnel to stop work and retreat upwind to a safe, unaffected area, where they will remain until further directed by the SSO.
- The SSO shall begin wetting procedures to control dust and then re-approach the work area while continuously monitoring the BZ areas.

- Only when levels are below the PEL standard in BZ areas will work be permitted to resume.
- If background levels are not regained, the SSO will contact the HSM for additional direction.

There is a sampling task where the use of DRIs will not be required that is for the marine operations (surface water and sediment sampling tasks from a small water vessel/boat and drilling soil borings from a barge). An evaluation of available data from previous investigations at the intended sampling areas did not identify any volatile substances (only low concentrations of metals, PCBs, and PAHs. Furthermore, these types of substances only represent an inhalation concern if they are either present in inhalable air as suspended solid particulates in sizes that can be inspired into to the body, or if they are heated to very high temperatures and are present as fumes. Neither of these types of situations is plausible for the marine operations. Therefore, DRI usage will not be required for those tasks only.

Tetra Tech will issue or cause to be issue all necessary personal protective equipment and air monitoring equipment prior to commencing the job to all its agents and personnel, including full instructions and training on the use of the equipment. The requirements included in Section 3.1 of the LM Handbook (Attachment I) addressing monitor equipment will be followed.

Radiological contaminants of concern are alpha, beta and possibly gamma sources. Past actions have likely removed much of the site contamination; however this effort is to determine if contamination exists and to determine background levels. For this reason, a radiological field survey and sampling will be performed to identify any areas of elevated radioactivity. Radiological work will be monitored by the PHP in accordance with Tt RPOP. Action levels are established in the project work plan.

7.1 INSTRUMENTS AND USE

Instruments will be used primarily to monitor source points and worker breathing zone areas, while observing instrument action levels. The SSO shall obtain and document the daily background (BG) reading at an upwind, unaffected area and observe for readings above that BG level. The SSO shall monitor source areas (e.g., monitoring wells) for the presence of any reading above the daily-established BG level. If elevated readings are observed, the SSO shall monitor the workers breathing zone (BZ) areas with the PID. If the appropriate instrument Action Level is exceeded (see below), the following process will be followed:

• The SSO shall order all personnel to stop work and retreat upwind to a safe, unaffected area, where they will remain until further directed by the SSO.

- The SSO shall allow at least 5 minutes to pass so that the work area can ventilate, and will then reapproach the work area while continuously monitoring the BZ areas.
- Only when BG levels are regained in BZ areas will work be permitted to resume.
- If BG levels are not regained, the SSO will contact the HSM for additional direction.

Instrument Action Levels: Monitoring instruments use will follow the action levels specified below:

- A Draeger Tube 0.5/a will be used when the presence of VOCs is confirmed:
 - If the readings are Benzene, the action level is 5 ppm/sustained 10 minutes/4 times/day
 - If readings are not Benzene, the action levels are as follows:

Instrument Action Levels:

The use of either a PID will be acceptable at all sites, provided that the following action levels are observed:

ACTION LEVELS					
Location	Instrument	Action Level	Exposure Time		
Block D	PID with 11.7 eV lamp	1 ppm	4 exposures of 5 minutes one day		
Block E	PID with 11.7 eV lamp	7 ppm	4 exposures of 5 minutes one day		
Block F	PID with 11.7 eV lamp	1000 ppm	4 exposures of 5 minutes one day		
Block G	PID with 11.7 eV lamp 7 ppm		4 exposures of 5 minutes one day		
Block H	PID with 11.7 eV lamp Precautionary use	10 ppm	4 exposures of 5 minutes one day		
Block I*	PID with 11.7 eV lamp	1 ppm	4 exposures of 5 minutes one day		
Block I* (1,1 Dichloroethane only)	FID	1,900 ppm	4 exposures of 5 minutes one day		

^{*}Reference only at this time

7.1.1 <u>Carbon Monoxide Detector and Colorimetric Tubes for Nitrogen Dioxide</u>

A direct-read carbon monoxide detector such as a Draeger PAC III Single Gas Monitor, an Industrial Scientific T82 Single Gas Monitor (or equivalent) will be used during all soil boring and concrete coring operations performed in Building B146 to evaluate airborne concentrations of carbon monoxide. Although other exhaust gases may be present, carbon monoxide has been selected as the primary indicator

compound to determine potential exposure concerns. Conservative action levels for carbon monoxide have been established to prevent potential exposures to other exhaust gas compounds including oxides nitrogen and sulfur.

As a precautionary measure, colorimetric tubes for nitrogen dioxide (NO₂) will also be available for use and will be required whenever elevated CO readings are observed. To evaluate NO2 concentrations a Nitrogen Dioxide Draeger tube (0.5/c) will be used. These tubes detected NO2 at concentrations ranging from 0.5 to 10 ppm or 5 to 25 ppm depending on the number of pump strokes that are used. For the purpose of determining exposure concerns, the lower range will be used which will require 5 strokes of the hand pump. A color change from pale grey to blue grey indicates the presence of NO₂.

7.1.2 Radiation Survey Instrument

Radiological instruments will be used for field survey and sampling as described below. Radiological surveys will be performed in accordance with the guidance provided in the Tt RPOP.

Instrument	Detector	Type of Activity Detected	Survey Type
Ludlum Model 2350 Digital Data Logger	Phoswhich Probe	Alpha/Beta	Contamination Surveys (counts per minute [cpm])
Ludlum Model 2241 Scaler/Ratemeter	2" x 2" Ludlum Model 44-10 Nal Scintillation Probe	Gamma	Dose Rate Surveys (cpm)
Ludlum Model 19 Survey Meter	1" x 1" Sodium lodide (Nal)Tl scintillator	Low-Level Gamma	Dose Rate (micro Röntgen per hour [µR/hr])

7.2 INSTRUMENT MAINTENANCE AND CALIBRATION

Hazard monitoring instruments will be maintained and pre-field calibrated by the equipment provider (i.e., rental agency used). Operational checks and field calibration will be performed on site instruments each day prior to their use. Field calibration will be performed on instruments according to manufacturer's recommendations. These operational checks and calibration efforts will be performed in a manner that complies with the employees health and safety training, the manufacturer's recommendations, and with the applicable manufacturer standard operating procedure (which the SSO must assure are included with the instrument upon its receipt onsite). Field calibration efforts must be documented. Figure 7-1 is provided for documenting these calibration efforts. This information may instead be recorded in a field operations logbook, provided that the information specified in Figure 7-1 is recorded. This required information includes the following:

- Date calibration was performed
- Individual calibrating the instrument
- Instrument name, model, and serial number
- Any relevant instrument settings and resultant readings (before and after) calibration
- Identification of the calibration standard (lot no., source concentration, supplier)
- Any relevant comments or remarks

Radiological instruments will be calibrated with known source before field use. Pre-operational checks will be performed on the instruments each day before use in accordance with the guidance provided in the Tt RPOP.

7.3 DOCUMENTING INSTRUMENT READINGS

The SHSO is responsible for ensuring that air monitoring instruments are used in accordance with the specifications of this HASP and with manufacturer's specifications/recommendations. In addition, the SHSO is also responsible for ensuring that all instrument use is documented. This requirement can be satisfied either by recording instrument readings on pre-printed sampling log sheets or in a field log book. This includes the requirement for documenting instrument readings that indicate no elevated readings above noted daily background levels (i.e., no-exposure readings). At a minimum, the SHSO must document the following information for each use of an air monitoring device:

- Date, time, and duration of the reading
- Site location where the reading was obtained
- Instrument used (e.g., PID, etc.)
- Personnel present at the area where the reading was noted
- Other conditions that are considered relevant to the SHSO (such as weather conditions, possible instrument interferences, etc.)

Radiological surveys and instrument pre-operational checks will be documented in accordance with the Tt RPOP.

FIGURE 7-1

DOCUMENTATION OF FIELD CALIBRATION

SITE NAME:	PROJECT NO.:
•	

D. (Instrument Instrument Person		Person	Instrumer	Instrument Settings		Instrument Readings		D /
Date of Calibration	Name and Model	I.D. Number	Performing Calibration	Pre- Calibration	Post- Calibration	Pre- Calibration	Post- Calibration	Standard	Remarks/ Comments

8.0 TRAINING/MEDICAL SURVEILLANCE REQUIREMENTS

8.1 INTRODUCTORY/REFRESHER/SUPERVISORY TRAINING

This section is included to specify health and safety training and medical surveillance requirements for Tetra Tech personnel participating in on site activities. Tetra Tech personnel must complete 40 hours of introductory hazardous waste site training prior to performing work at the LMC MRC. Tetra Tech personnel who have had introductory training more than 12 months prior to site work must have completed 8 hours of refresher training within the past 12 months before being cleared for site work. In addition, 8-hour supervisory training in accordance with 29 CFR 1910.120(e)(4) will be required for site supervisory personnel. Tetra Tech and subcontractor personnel working on site who are potentially exposed to hazardous substances shall receive initial and annual refresher training in accordance with 29 CFR 1910.120(e) – Hazardous Waste Operations and Emergency Response or the applicable state OSHA standard. Lockheed Martin shall be provided with electronic copies of the training certificates.

Documentation of Tetra Tech introductory, supervisory, and refresher training as well as site-specific training will be maintained at the site. Copies of certificates or other official documentation will be used to fulfill this requirement.

The requirements described in Section 3.20.3 of the LM Handbook (Attachment I) addressing training will be followed.

8.2 SITE-SPECIFIC TRAINING

Tetra Tech SSO will provide site-specific training to Tetra Tech employees who will perform work on this project. Figure 8-1 will be used to document the provision and content of the project-specific and associated training. Site personnel will be required to sign this form prior to commencement of site activities. This training documentation will be employed to identify personnel who through record review and attendance of the site-specific training are cleared for participation in site activities. This document shall be maintained at the site to identify and maintain an active list of trained and cleared site personnel.

The Tetra Tech SSO will also conduct a pre-activities training session prior to initiating site work. This will consist of a brief meeting at the beginning of each day to discuss operations planned for that day, and a review of the appropriate Safe Work Permits with the planned task participants. A short meeting may also be held at the end of the day to discuss the operations completed and any problems encountered.

8.3 MEDICAL SURVEILLANCE

Tetra Tech personnel participating in project field activities will have had a physical examination meeting the requirements of Tetra Tech's medical surveillance program. Documentation for medical clearances will be maintained in the Tetra Tech Pittsburgh office and made available, as necessary, and will be documented using Figure 8-1 for every employee participating in onsite work activities at this site. Tetra Tech shall provide evidence of employee enrollment in a medical surveillance program. Lockheed Martin does not provide medical surveillance examinations to contractor employees.

The medical surveillance requirements described in Section 3.20.4 of the LM Handbook (Attachment I) will be followed.

Each field team member, including visitors, entering the exclusion zone(s) shall be required to complete and submit a copy of the Medical Data Sheet (see Attachment III of this HASP). This shall be provided to the SSO, prior to participating in site activities. The purpose of this document is to provide site personnel and emergency responders with additional information that may be necessary in order to administer medical attention.

8.4 SITE VISITORS

Site visitors for the purpose of this document are identified as representing the following groups of individuals:

- Personnel invited to observe or participate in operations by Tetra Tech
- Regulatory personnel (i.e. EPA, MDEP, OSHA)
- Property Owners
- Authorized Personnel
- Other authorized visitors

Non Tetra Tech personnel working on this project are required to gain initial access to the facility by coordinating with the Tetra Tech FOL or designee and following established facility access procedures.

Once access to the base is obtained, personnel who require site access into areas of ongoing operations will be required to obtain permission from the PM. In addition, site visitors wishing to observe operations in progress will be escorted by a Tetra Tech representative and shall be required to meet the minimum requirements discussed below:

- Site visitors will be directed to the FOL/SSO, who will sign them into the field logbook. Information to be recorded in the logbook will include the individual's name (proper identification required), the entity which they represent, and the purpose of the visit.
- Site visitors must be escorted and restricted from approaching any work areas where they could be exposed to hazards from Tetra Tech operations. If a visitor has authorization from the client and from the Tetra Tech Project Manager to approach our work areas, the FOL must assure that the visitor first provides documentation indicating that he/she/they have successfully completed the necessary OSHA introductory training, receive site-specific training from the SSO, and that they have been physically cleared to work on hazardous waste sites. Site visitors wishing to enter the exclusion zone will be required to produce the necessary information supporting clearance to the site. This shall include information attesting to applicable training and medical surveillance as stipulated in Section 8.0 of this document. In addition, to enter the site operational zones during planned activities, visitors will be required to first go through site-specific training covering the topics stipulated in Section 8.2 of this HASP. All jobsite visitors must have a safety orientation prior to commencing work or touring the site. A visitor log will be kept to document the orientation.
- Once the site visitors have completed the above items, they will be permitted to enter the operational zone. Visitors are required to observe the protective equipment and site restrictions in effect at the site at the time of their visit. Visitors entering the exclusion zones during ongoing operations will be accompanied by a Tetra Tech representative. Visitors not meeting the requirements, as stipulated in this plan, for site clearance will not be permitted to enter the site operational zones during planned activities. Any incidence of unauthorized site visitation will cause the termination of on site activities until the unauthorized visitor is removed from the premises. Removal of unauthorized visitors will be accomplished with support from local law enforcement personnel.

FIGURE 8-1

SITE-SPECIFIC TRAINING DOCUMENTATION

My signature below indicates that I am aware of the potential hazardous nature of performing field activities at LCM MRC and that I have received site-specific training which included the elements presented below:

- Names of designated personnel and alternates responsible for site safety and health
- Safety, health, and other hazards present on site
- Use of personal protective equipment
- Safe use of engineering controls and equipment
- Medical surveillance requirements
- Signs and symptoms of overexposure
- Emergency response procedures (evacuation and assembly points)
- Incipient response procedures
- Review of the contents of relevant Material Safety Data Sheets
- Review of the use of Safe Work Permits
- Stop Work Procedures

I have been given the opportunity to ask questions and all of my questions have been answered to my satisfaction. The dates of my training and medical surveillance requirements indicated below are accurate.

Site- Specific Training Date	40-Hour Training (Date)	8-Hour Refresher Training (Date)	8-Hour Supervisory Training (Date)	Medical Exam
	Specific Training	Specific Training (Date)	Specific Training Refresher Training Training	Specific Training Refresher Supervisory Training Training Training Training Training Training (Date)

9.0 SITE CONTROL

This section outlines the means by which Tetra Tech will delineate work zones and use these work zones in conjunction with decontamination procedures to prevent the spread of contaminants into previously unaffected areas of the site. It is anticipated that a three-zone approach will be used during work at this site. This approach will be comprised of an exclusion zone, a contamination reduction zone, and a support zone. It is also anticipated that this approach will control access to site work areas, restricting access by the general public, minimizing the potential for the spread of contaminants, and protecting individuals who are not cleared to enter work areas.

Radiological areas, if applicable, will be posted independently of work zones in accordance with the Tt RPOP.

9.1 EXCLUSION ZONE

The exclusion zone will be considered the areas of the site of known or suspected contamination. It is anticipated that the areas around active/intrusive activates will have the potential for contaminants brought to the surface. These areas will be marked and personnel will maintain safe distances. Once active/intrusive activities have been completed and any surface contamination has been removed, the potential for exposure is again diminished and the area can then be reclassified as part of the contamination reduction zone. The exclusion zones for this project are those areas of the site where active work (DPT work areas, drilling, installation, and sample collection, etc.) is being performed plus a designated area of at least 25 feet surrounding the work area. Exclusion zones will be delineated as deemed appropriate by the FOL, through means such as erecting visibility fencing, barrier tape, cones, and/or postings to inform and direct personnel.

9.1.1 <u>Exclusion Zone Clearance</u>

An Exclusion Zone (EZ) will be established at each well installation/sampling location. The purpose of establishing and maintaining these localized exclusion zones is to define areas where more rigorous safety and health protection measures will be required and to designate areas restricted to non-essential and unauthorized personnel. The size and dimensions of these EZs will vary based on the nature of the planned activities, and may be subject to change at the SSO's discretion based on factors such as visual observations, nearby concurrent operations, and other factors. However, the following dimensions represent basic considerations for establishing EZs:

- <u>DPT and associated concurrent sampling activities</u>. The EZ for this activity will be set at the height of the mast, plus five feet surrounding the point of operation, with a minimum of 25-feet. This distance will also apply when surface and subsurface soil sampling from behind these type rigs.
- Monitoring well development, purging, construction and use, and collecting groundwater soil, sediment samples, water level readings and indoor air sampling. The EZ for these activities will be set to encompass an area of at least 10-feet surrounding the well head.
- <u>Decontamination operations</u>. The EZ for this activity will be set at 25 feet surrounding the gross contamination wash and rinse as well as 25-feet surrounding the heavy equipment decontamination area. Sample equipment decontamination boundaries will be set at 10-feet surrounding hand wash and rinse areas.
- <u>Investigative Derived Waste (IDW)</u> area will be constructed and barricaded. Only authorized personnel will be allowed access.

EZs will be marked using barrier tape, traffic cones and/or drive pole, or other readily-visible devices. Signs may also be posted at the SSO's discretion to inform and direct site personnel and site visitors. EZs shall remain marked until the SSO has evaluated the restoration effort and has authorized changing the zone status.

A pre-startup site visit will be conducted by members of the identified field team in an effort to identify proposed subsurface investigation locations, conduct utility clearances, and provide upfront notices concerning scheduled activities within the facility.

Subsurface activities will proceed only when utility clearance has been obtained. In the event that a utility is struck during a subsurface investigative activity, the emergency numbers provided in Section 2.0, Table 2-1, will be notified.

9.2 CONTAMINATION REDUCTION ZONE

The contamination reduction zone (CRZ) will be a buffer area between the exclusion zone and any area of the site where contamination is not suspected. This area will also serve as a focal point in supporting exclusion zone activities. This area will be delineated using barrier tape, cones, and postings to inform and direct facility personnel. Decontamination will be conducted at a central location. Equipment potentially contaminated will be bagged and taken to that location for decontamination.

9.3 SUPPORT ZONE

The support zone for this project will include a staging area where site vehicles will be parked, equipment will be unloaded, and where food and drink containers will be maintained. The support zones will be established at areas of the site where away from potential exposure to site contaminants during normal working conditions or foreseeable emergencies.

9.4 SAFE WORK PERMITS

Exclusion Zone work conducted in support of this project will be performed using Safe Work Permits (SWPs) to guide and direct field crews on a task by task basis. An example of the SWP to be used is provided in Figure 9-1. Partially completed SWPs for the work to be performed are attached (Attachment IV) to this HASP. These permits were completed to the extent possible as part of the development of this HASP. It is the SSO's responsibility to finalize and complete all blank portions of the SWPs based on current, existing conditions the day the task is to be performed, and then review that completed permit with all task participants as part of a pre-task tail gate briefing session. This will ensure that site-specific considerations and changing conditions are appropriately incorporated into the SWP, provide the SSO with a structured format for conducting the tail gate sessions, as well will also give personnel an opportunity to ask questions and make suggestions. All SWPs require the signature of the FOL or SSO.

9.5 SITE SECURITY

As this activity will take place at an active facility, the first line of security will be provided by the facility entrance/gate restricting the general public. The second line of security will take place at the work site referring interested parties to the FOL and LMC Contact.

Security at the work areas will be accomplished using field personnel. This is a multiple person operation, involving multiple operational zones. Tetra Tech personnel will retain complete control over active operational zones.

The site contact will serve as the focal point for facility personnel and interested parties and will serve as the primary enforcement contact.

9.6 SITE VISITORS

Site visitors for the purpose of this document are identified as representing the following groups of individuals:

- Personnel invited to observe or participate in operations by Tetra Tech
- Regulatory personnel (i.e. EPA, MDEP, OSHA)
- Property Owners
- Authorized Personnel
- Other authorized visitors

Non Tetra Tech personnel working on this project are required to gain initial access to the facility by coordinating with the Tetra Tech FOL or designee and following established facility access procedures.

Once access to the base is obtained, personnel who require site access into areas of ongoing operations will be required to obtain permission from the PM. In addition, site visitors wishing to observe operations in progress will be escorted by a Tetra Tech representative and shall be required to meet the minimum requirements discussed below:

- Site visitors will be directed to the FOL/SSO, who will sign them into the field logbook. Information to
 be recorded in the logbook will include the individual's name (proper identification required), the entity
 which they represent, and the purpose of the visit.
- Site visitors must be escorted and restricted from approaching any work areas where they could be exposed to hazards from Tetra Tech operations. If a visitor has authorization from the client and from the Tetra Tech Project Manager to approach our work areas, the FOL must assure that the visitor first provides documentation indicating that he/she/they have successfully completed the necessary OSHA introductory training, receive site-specific training from the SSO, and that they have been physically cleared to work on hazardous waste sites. Site visitors wishing to enter the exclusion zone will be required to produce the necessary information supporting clearance to the site. This shall include information attesting to applicable training and medical surveillance as stipulated in Section 8.0 of this document. In addition, to enter the site operational zones during planned activities, visitors will be required to first go through site-specific training covering the topics stipulated in Section 8.2 of this HASP. All jobsite visitors must have a safety orientation prior to commencing work or touring the site. A visitor log will be kept to document the orientation.
- Once the site visitors have completed the above items, they will be permitted to enter the operational zone. Visitors are required to observe the protective equipment and site restrictions in effect at the site at the time of their visit. Visitors entering the exclusion zones during ongoing operations will be accompanied by a Tetra Tech representative. Visitors not meeting the requirements, as stipulated in this plan, for site clearance will not be permitted to enter the site operational zones during planned activities. Any incidence of unauthorized site visitation will cause the termination of on site activities

until the unauthorized visitor is removed from the premises. Removal of unauthorized visitors will be accomplished with support from local law enforcement personnel.

9.7 SITE MAP

Once the areas of contamination, access routes, topography, and dispersion routes are determined, a site map will be generated and adjusted as site conditions change. These maps will be posted to illustrate up-to-date collection of contaminants and adjustment of zones and access points.

9.8 BUDDY SYSTEM

Personnel engaged in on site activities will practice the "buddy system" to ensure the safety of personnel involved in this operation.

9.9 COMMUNICATION

As personnel will be working in proximity to one another during field activities, a supported means of communication between field crew members will not be necessary.

External communication will be accomplished by using the cell phones/telephones at predetermined and approved locations. External communication will primarily be used for the purpose of resource and emergency resource communications. Prior to the commencement of activities at the LCM MRC, the FOL will determine and arrange for telephone communications.

9.10 SELF-AUDITS

The procedures outlined in Section 7 of the LM Handbook (Attachment I) addressing self-audits will be adhered to.

Tetra Tech and/or subcontractor personnel will perform periodic work area/project field inspections to monitor compliance with project environmental, safety and health requirements. The name of Tetra Tech's jobsite health and safety (H&S) representative will be provided to Lockheed Martin prior to starting work at the jobsite.

For jobs that are ongoing, an annual H&S audit shall be conducted and for jobs with a duration of less than one year at least one audit shall occur. A competent H&S representative designated by the Tetra Tech shall perform the audit. Unsafe acts and/or non-compliance conditions noted during inspections shall be corrected immediately.

The documentation related to the audits and inspections shall be submitted electronically to the Lockheed Martin Project Lead.

FIGURE 9-1 SAFE WORK PERMIT

Permit N	No Date:	_ Time: From	to
l.	Work limited to the following (description, area, o	equipment used):	
II.	Primary Hazards: Potential hazards associated with	n this task:	
III.	Field Crew:		
IV.	On-site Inspection conducted Yes No Equipment Inspection required Yes No	Initials of Inspector Initials of Inspector	Tetra Tech Tetra Tech
٧.	Protective equipment required R	Respiratory equipment requir	ed
	Level D	Yes ☐ Specify on the r No ☐	everse
VI.	Chemicals of Concern Hazard Monitoring	Action Level(s)	Response Measures
	Primary Route(s) of Exposure/Hazard:		-
	Timary Route(3) of Exposure/Hazard.		
VII.	(Note to FOL and/or SHSO: Each item in Sections Additional Safety Equipment/Procedures	s VII, VIII, and IX must be che	ecked Yes, No, or NA)
	Hard-hat ☐ Yes ☐ No Safety Glasses ☐ Yes ☐ No	Hearing Protection (Plugs/M Safety belt/harness	
	Chemical/splash goggles Yes No	Radio/Cellular Phone	
	Splash Shield	Barricades	
	Splash suits/coveralls Yes No Impermeable apron Yes No	Gloves (Type – Work/rest regimen	☐ Yes ☐ No
	Steel toe Work shoes or boots Yes No	Chemical Resistant Boot Co	
	High Visibility vest ☐Yes ☐ No	Tape up/use insect repellent	t 🔲 Yes 🔲 No
	First Aid Kit	Fire Extinguisher	
	Safety Shower/Eyewash	Other	Yes No
VIII.	Site Preparation	4	Yes No NA
	Utility Locating and Excavation Clearance completed Vehicle and Foot Traffic Routes Established/Traffic C		
	Physical Hazards Identified and Isolated (Splash and		
	Emergency Equipment Staged (Spill control, fire exti	inguishers, first aid kits, etc)	
IX.	Additional Permits required (Hot work, confined sp If yes, SHSO to complete or contact Health Science.		
Χ.	Special instructions, precautions:	. , ,	
Permit I	ssued by:	Permit Accepted by:	

10.0 SPILL CONTAINMENT PROGRAM AND WASTE MANAGEMENT PLAN

10.1 SCOPE AND APPLICATION

It is not anticipated that bulk hazardous materials (over 55-gallons) will be generated or handled at any given time as part of this scope of work. It is also not anticipated that such spillage would constitute a danger to human health or the environment. However, as the job progresses, some potential may exist for accumulating Investigative Derived Wastes (IDW) such as decontamination fluids, soil cuttings, disposable sampling equipment and PPE.

10.2 POTENTIAL SPILL AREAS

Potential spill areas will be periodically monitored in an ongoing attempt to prevent and control further potential contamination of the environment. Currently, limited areas are vulnerable to this hazard including:

- · Resource deployment
- Waste transfer
- Central staging

It is anticipated that the IDW generated as a result of this scope of work will be containerized, labeled, and staged to await further analyses. The results of these analyses will determine the method of disposal.

10.3 LEAK AND SPILL DETECTION

To establish an early detection of potential spills or leaks, a periodic walk-around by the personnel staging or disposing of drums area will be conducted during working hours to visually determine that storage vessels are not leaking. If a leak is detected, the contents will be transferred, using a hand pump, into a new vessel. The leak will be collected and contained using absorbents such as Oil-Dry, vermiculite, or sand, which are stored at the vulnerable areas in a conspicuously marked drum. This used material, too, will be containerized for disposal pending analysis. Inspections will be documented in the project logbook.

In case of a spill or release of hazardous chemicals, Tetra Tech shall immediately notify the Lockheed Martin Project Lead, and/or if the severity of the spill warrants, the local fire department by calling 9-1-1. Tetra Tech shall take all necessary steps to control the spread of the release and to provide site control to prevent unauthorized personnel from entering the affected area.

Section 8.2 of the LM Handbook (Attachment I) pertaining to spill reporting will be addresses.

10.4 PERSONNEL TRAINING AND SPILL PREVENTION

Personnel will be instructed in the procedures for incipient spill prevention, containment, and collection of hazardous materials in the site-specific training. The FOL and the SSO will serve as the Spill Response Coordinators for this operation, should the need arise.

10.5 SPILL PREVENTION AND CONTAINMENT EQUIPMENT

The following represents the types of equipment that should be maintained at the staging areas for the purpose of supporting this Spill Prevention/Containment Program.

- Absorbent materials such as: Sand, clean fill, vermiculite, or other non combustible absorbent (Oildry)
- Drums (55-gallon U.S. DOT 1A1 or 1A2)
- Shovels, rakes, and brooms
- Hand pump
- Container labels

Hazardous materials shall be stored in designated areas and all containers effectively closed. Spill equipment/supplied shall be readily available to contain and/or mitigate accidental spills of hazardous materials.

10.6 SPILL CONTROL PLAN

This section describes the procedures the Tetra Tech field crew members will employ upon the detection of a spill or leak.

- Notify the SSO or FOL immediately upon detection of a leak or spill. Activate emergency alerting
 procedures for that area to remove non-essential personnel.
- Employ the personal protective equipment stored at the staging area. Take immediate actions to stop
 the leak or spill by plugging or patching the container or raising the leak to the highest point in the
 vessel. Spread the absorbent material in the area of the spill, covering it completely.
- Transfer the material to a new vessel; collect and containerize the absorbent material. Label the new container appropriately. Await analyses for treatment and disposal options.

• Re-containerize spills, including 2-inch of top cover impacted by the spill. Await test results for treatment or disposal options.

It is not anticipated that a spill will occur that the field crew cannot handle. Should this occur, notification of the appropriate Emergency Response agencies will be carried out by the FOL or SSO in accordance with the procedures discussed in Section 2.0 of this HASP.

As mentioned above, in the event of a spill or release of hazardous chemicals, Tetra Tech will immediately notify the LMC personnel in the order presented in Table 2-1, and/or if the severity of the spill warrants, the local fire department by calling 9-1-1.

10.7 WASTE MANAGEMENT PLAN

Tetra Tech personnel will adhere to the decontamination and waste management procedures laid out the Tetra Tech HSGM and the Tetra Tech Decontamination of Field Equipment and Waste Handling Standard Operating Procedure (Attachment IX).

In addition, all requirements described in Sections 4.1 and 4.2 of the LM Handbook (Attachment I) will be addressed.

11.0 CONFINED-SPACE ENTRY

It is not anticipated, under the proposed scope of work, that confined space and permit-required confined space activities will be conducted. **Therefore, personnel under the provisions of this HASP are not allowed, under any circumstances, to enter confined spaces**. A confined space is defined as an area which has one or more of the following characteristics:

- Is large enough and so configured that an employee can bodily enter and perform assigned work.
- Has limited or restricted means for entry or exit (for example, tanks, manholes, sewers, vessels, silos, storage bins, hoppers, vaults, and pits are spaces that may have limited means of entry).
- Is not designed for continuous employee occupancy.

Additionally, a Permit-Required Confined Space must also have one or more of the following characteristics:

- Contains or has a potential to contain a hazardous atmosphere.
- Has an internal configuration such that an entrant could be trapped or asphyxiated by inwardly caving
 walls or by a floor that slopes downward and tapers to a smaller cross-section.
- Contains any other recognized, serious, safety or health hazard.

For further information on confined space, consult the Health and Safety Guidance Manual or call the PHSO. If confined space operations are to be performed as part of the scope of work, detailed procedures and training requirements will have to be addressed and this HASP will be updated/amended as necessary to address the confined space entry requirements detailed in Section 3.3 of the LM Handbook (Attachment I).

12.0 HOT WORK

No hot work activities are being conducted as part of this field effort. Should hot work be required, this HASP will be amended/updated as necessary to include the requirements stipulated in Section 3.4 of the LM Handbook (Attachment I).

13.0 USE OF LOCKHEED MARTIN MATERIALS AND EQUIPMENT

No Lockheed Martin materials, tools, equipment, PPE shall be used until authorized by Lockheed Martin.

No Tetra Tech personnel will start, stop, relocate, or adjust any Lockheed Martin process or production equipment without approval of the Lockheed Martin Project Lead. Details of these requirements are described in Section 3.6 of the LM Handbook.

14.0 ELEVATED LOCATIONS / LADDERS / SCAFFOLDS

No elevated location work, ladder work, or scaffolding activities are being conducted as part of this field effort. Should any of these activities be required, this HASP will be amended/updated as necessary to include the requirements stipulated in Sections 3.10, 3.11, and 3.12 of the LM Handbook (Attachment I).

15.0 DANGEROUS OPERATIONS

Tetra Tech and subcontractor personnel will isolate their work areas from Lockheed Martin operations, employees, and the public. Barricades, signs, and signals will be employed as necessary and will be visible at all times where hazards exist.

Tetra Tech and subcontractors will effectively barricade excavations, floor openings, etc. as required by OSHA regulations.

Prior to beginning work, Tetra Tech and subcontractors must inform the Lockheed Martin Project Lead of any potentially dangerous operations.

All requirements addressing dangerous operations are detailed in Section 3.7 of the LM Handbook and will be adhered to.

16.0 EXCAVATIONS, TRENCHES, AND EARTHWORK

Excavation, trench work, or earthwork is being conducted as part of this field effort. The excavation, test pit work, required, in this HASP will include the requirements stipulated in Section 3.8 of the LM Handbook (Attachment I) and a trained, competent person will be designated to oversee the activities. Excavation safe work practices are outlined in Section 5.5 of this HASP

17.0 ASBESTOS

Asbestos abatement work may be conducted as part of this field effort. This HASP includes the requirements stipulated in Section 3.19 of the LM Handbook (Attachment I) and can be found in Section 5.4 of this HASP.

Asbestos containing material (ACM) or presumed asbestos containing material (PACM) if it is to be disrupted, Tetra Tech and/or subcontractor personnel shall <u>immediately</u> report to the Lockheed Martin Project Lead and to other employers of employees working at the job site any anticipated work that could lead to the discovery, disturbance, and/or spill of ACM and/or PACM. All operations will cease and the Asbestos contractor called in to remove or investigate the suspected ACM. The approval of the Lockheed Martin Project Lead is required before resuming operations.

Tetra Tech and/or subcontractor personnel shall not disturb any pipe insulation, boiler insulation, or any other material reasonably suspected of containing asbestos until the Lockheed Martin is notified and approval is obtained.

Abatement of asbestos can be performed only by persons properly trained and licensed to perform such activities.

All requirements addressed in Section 3.18 of the LM Handbook pertaining to incidental asbestos exposure will be followed.

18.0 NANOTECHNOLOGY

No nanotechnology work is being conducted as part of this field effort. Should it be required, this HASP will be amended/updated as necessary to include the requirements stipulated in Section 3.21 of the LM Handbook (Attachment I).

19.0 WORK INVOLVING AIR EMISSIONS

No work involving air emissions is being conducted as part of this field effort. Should it be required, this HASP will be amended/updated as necessary to include the requirements stipulated in Section 4.3 of the LM Handbook (Attachment I).

20.0 WORK INVOLVING WATER DISCHARGES

No work involving water discharges is being conducted as part of this field effort. Should it be required, this HASP will be amended/updated as necessary to include the requirements stipulated in Section 4.4 of the LM Handbook (Attachment I).

21.0 MATERIALS AND DOCUMENTATION

The Tetra Tech Field Operations Leader (FOL) shall ensure the following materials/documents are taken to the project site and used when required.

- A complete copy of this HASP
- Health and Safety Guidance Manual
- Incident Reports
- Medical Data Sheets
- Material Safety Data Sheets for chemicals brought on site, including decontamination solutions, fuels, sample preservatives, calibration gases, etc.
- A full-size OSHA Job Safety and Health Poster (posted in the site trailer)
- Training/Medical Surveillance Documentation Form (Blank)
- First-Aid Supply Usage Form
- Emergency Reference Form (Section 2.0, extra copy for posting)
- Directions to the Hospital

21.1 MATERIALS TO BE POSTED AT THE SITE

The following documentation is to be posted or maintained at the site for quick reference purposes. In situations where posting these documents is not feasible (such as no office trailer), these documents should be separated and be immediately accessible.

- Chemical Inventory Listing (posted) This list represents all chemicals brought on-site, including decontamination solutions, sample preservations, fuel, etc. This list should be posted in a central area.
- MSDSs (maintained) The MSDSs should also be in a central area accessible to all site personnel. These documents should match all the listings on the chemical inventory list for all substances employed on-site. It is acceptable to have these documents within a central folder and the chemical inventory as the table of contents.
- The OSHA Job Safety & Health Protection Poster (posted Attachment X) This poster should be conspicuously posted in places where notices to employees are normally posted, as directed by 29 CFR 1903.2 (a)(1). Each FOL shall ensure that this poster is not defaced, altered, or covered by other material. The law also states that reproductions or facsimiles of the poster shall be at least 8 1/2 by 14 inches with 10 point type.

- **Site Clearance (maintained)** This list is found within the training section of the HASP (Figure 8-1). This list identifies all site personnel, dates of training (including site-specific training), and medical surveillance. The list indicates not only clearance, but also status. If personnel do not meet these requirements, they do not enter the site while site personnel are engaged in activities.
- Emergency Phone Numbers and Directions to the Hospital(s) (posted) This list of numbers and directions will be maintained at all phone communications points and in each site vehicle.
- Medical Data Sheets/Cards (maintained) Medical Data Sheets will be filled out by on-site
 personnel and filed in a central location. The Medical Data Sheet will accompany any injury or illness
 requiring medical attention to the medical facility. A copy of this sheet or a wallet card will be given to
 all personnel to be carried on their person.
- **Personnel Monitoring (maintained)** All results generated through personnel sampling (levels of airborne toxins, noise levels, etc.) will be posted to inform individuals of the results of that effort.
- Placards and Labels (maintained) Where chemical inventories have been separated because of
 quantities and incompatibilities, these areas will be conspicuously marked using DOT placards and
 acceptable [Hazard Communication 29 CFR 1910.1200(f)] labels.

The purpose of maintaining or posting this information, as stated above, is to allow site personnel quick access. Variations concerning location and methods of presentation are acceptable providing the objective is accomplished.

21.2 HAZARD COMMUNICATION – USE OF HAZARDOUS MATERIALS

All hazardous substance (as defined by OSHA) brought onto Lockheed Martin remediation sites must be accompanied by a MSDS and the containers labeled in accordance with the Red OSHA Hazard Communication Standard, 29 CFR 1910.1200 or applicable state OSHA standard. Tetra Tech and subcontractor personnel will provide MSDSs for chemicals brought on site. The contents of these documents will be reviewed by the SSO with the user(s) of the chemical substances prior to any actual use or application of the substances on site. A chemical inventory of the chemicals used on site will be developed using the Health and Safety Guidance Manual. The MSDSs will then be maintained in a central location (i.e., temporary office) and will be available for anyone to review upon request.

The Lockheed Martin Project Lead shall be notified prior to bringing any quantity of hazardous materials onto Lockheed Martin remediation sites. Hazardous materials shall be stored in designated areas and all

containers effectively closed. Spill equipment/supplied shall be readily available to contain and/or mitigate accidental spills of hazardous materials.

All other hazard communication requirements are detailed in Section 3.2 and Section 4.1 of the LM Handbook (Attachment I) and will be adhered to.

22.0 ACRONYMS / ABBREVIATIONS

CFR Code of Federal Regulations
CIH Certified Industrial Hygienist
CSP Certified Safety Professional
DRI Direct Reading Instrument
FOL Field Operations Leader
HASP Health and Safety Plan

HAZWOPER Hazardous Waste Operations and Emergency Response

HSM Health and Safety Manager
IDW Investigation Derived Waste

MDEP Maryland Department of Environmental Protection

N/A Not Available

NIOSH National Institute for Occupational Safety and Health

OSHA Occupational Safety and Health Administration (U.S. Department of Labor)

PHP Project Health Physicist

PHSO Project Health and Safety Officer

PID Photoionization Detector

PM Project Manager

PPE Personal Protective Equipment

SSO Site Safety Officer
TBD To be determined
TCE Trichloroethene
Tetra Tech Tetra Tech, Inc.

Tt RPOP Tetra Tech Radiological Protection Operating Procedures

VC Vinyl Chloride

VOCs Volatile Organic Compounds

ATTACHMENT I LOCKHEED MARTIN'S REMEDIATION CONTRACTOR'S ESH HANDBOOK

LOCKHEED MARTIN

REMEDIATION CONTRACTOR'S ESH HANDBOOK

June 10, 2009

Revision 1

Lockheed Martin Corporation Energy, Environment, Safety & Health

A COPY OF THE JOB SPECIFIC HASP SHALL BE AVAILABE AT THE JOB SITE FOR THE DURATION OF THE PROJECT

REVISION STATUS

REVISION	DATE	COMMENTS
1	06/10/2009	

CONTRACTOR'S ESH HANDBOOK

TABLE OF CONTENTS

Table of Contents

I CONTRACT RESPONSIBILITIES			
2 DEFINITION	e		
SAFETY & HEALTH			
3.1 PERSONAL PROTECTIVE CLOTHING AND EQUIPMENT	7		
3.2 HAZARD COMMUNICATION - USE OF HAZARDOUS MATERIALS			
3.3 CONFINED SPACE ENTRY	9		
3.4 HOT WORK REQUIREMENTS (i.e., welding, torch cutting, brazing, etc.)	10		
3.5 LOCKOUT / TAGOUT - Control of Hazardous Energy	10		
3.6 USE OF LOCKHEED MARTIN MATERIALS AND EQUIPMENT	11		
3.7 DANGEROUS OPERATIONS - WARNINGS AND BARRICADES	11		
3.8 EXCAVATIONS, TRENCHES, EARTHWORK	11		
3.9 ELECTRICAL SAFETY	12		
3.10 ELEVATED LOCATIONS / FALL PROTECT	13		
3.11 LADDERS	13		
3.12 SCAFFOLDS	14		
3.13 HEAVY EQUIPMENT, INDUSTRIAL VEHICLES, AND CRANES	14		
3.14 OVERHEAD POWER LINES			
3.15 FIRE PREVENTION / FLAMMABLE LIQUIDS	15		
3.16 HAND AND POWER TOOLS			
3.17 COMPRESSED GAS CYLINDERS			
3.18 INCIDENTAL CONTACT WITH ASBESTOS			
3.19 ASBESTOS ABATEMENT CONTRACTORS			
3.20 HAZARDOUS WASTE OPERATIONS and EMERGENCY RESPONSE			
3.21 MANAGEMENT OF NANOTECHNOLOGY	22		
4 ENVIRONMENTAL			
4.1 HAZARD COMMUNICATION - USE OF HAZARDOUS MATERIALS			
4.2 NON-HAZARDOUS WASTE DISPOSAL			
4.3 WORK INVOLVING AIR EMISSIONS			
4.4 WORK INVOLVING WATER DISCHARGES			
5 HOUSEKEEPING / CLEANUP			
5 CHANGE MANAGEMENT			
7 REQUIREMENT TO PERFORM & DOCUMENT SELF-AUDITS			
ACCIDENT, INJURY, ILLNESS, INCIDENT and SPILL REPORTING			
FINES, PENALTIES AND COSTS			
10 LOCKHEED MARTIN ESH MANAGER			
ppendix A – LMC Requirements for Invasive Fieldwork			
ppendix B – LMC Waste Management Procedure			

CONTRACTOR'S ESH HANDBOOK

GENERAL

Lockheed Martin Corporation management at all levels is committed to conducting operations and activities in a manner that provides and maintains safe and healthful working conditions, protects the environment, and conserves natural resources.

This *Contractor's ESH Handbook* has been prepared to assist each project jobsite employer/contractor in satisfying its' contractual and legal accident prevention responsibilities, in such a manner that a safe, efficient operation is assured. All applicable requirements outlined in this handbook shall be incorporated into the contractor's site specific Safety and Health Plan The site specific Safety and Health plan shall be submitted to the Lockheed Martin Project Lead at least two weeks prior to starting work on any Lockheed Martin remediation projects.

This material must not be considered to be all inclusive as to the hazards that might be encountered, safe practices that should be performed, or safe conditions that should be maintained during the course of any project. Moreover, this handbook does not replace the contractor's legal obligation to its employees under all relevant environmental, safety and health requirements and laws. All legal standards not specifically referenced in this handbook shall apply when applicable.

1 CONTRACT RESPONSIBILITIES

The Contractor agrees to comply with all rules and procedures contained in this document, known as the *Remediation Contractor's ESH Handbook*, unless Lockheed Martin specifically agrees, in writing, to a modification or exemption. In addition, the Contractor and subcontractors, at any tier, shall:

- 1.1 Lockheed Martin is a drug free-work workplace. This requirement extends to contractors working on Lockheed Martin remediation projects. Additionally, the use of tobacco is not permitted on Lockheed Martin owned property.
- 1.2 Take all prudent and proper environmental, safety and health (ESH) precautions to protect Lockheed Martin employees, all other workers, and the public from ESH hazards associated with contractor activities.
- 1.3 Comply with all applicable Federal, State, municipal, local, and any other applicable occupational safety and health statutes, rules, ordinances, regulations, and requirements issued or imposed by any governmental authority (including, but not limited to *Title 29*, *Code of Federal Regulations Parts 1903, 1904, 1910* and *1926*).
- 1.4 Comply with all applicable Federal, State, municipal, local, and any other applicable air pollution statutes, rules, ordinances, regulations, and requirements issued or imposed by any governmental authority.

- 1.5 Comply with all Federal, State, municipal, local and Lockheed Martin hazardous materials, hazardous waste, and non-hazardous waste statutes, rules, ordinances, regulations, and requirements (including, but not limited to *Title 40*, *Code of Federal Regulations*).
- 1.6 Obtain the applicable ESH permits to conduct the work in compliance with local, state, federal ESH regulations and site requirements (including, but not limiting to *Title 29*, *Code of Federal Regulations, 1910 and 1926*).
- 1.7 Ensure that all employees and subcontractors have received the appropriate level of ESH training in accordance with applicable ESH regulations necessary for the performance of the work requested by Lockheed Martin.
- 1.8 To instruct, prior to commencement of operations, all employees on the jobsite about relevant governmental laws and regulations, specific hazards expected to be encountered and proper safety precautions to be observed. In addition, jobsite employees shall read and certify that they have read and understand the job specific health and safety plan (HASP). The certification forms provided by the contractor within the HASP shall be electronically sent to the Lockheed Martin Project Lead.
- 1.9 Provide all jobsite visitors with a safety orientation prior to commencing work or touring the site. A visitor log shall be kept to document the orientation.
- 1.10 To ensure Contractor's job specific health and safety plan (HASP) encompasses Federal, State, municipal, local and the Lockheed Martin requirements found within this document the HASP should contain a section on crisis management / emergency response. A copy of the job specific HASP shall be maintained at the job site where jobsite employees have access to a copy. All Contractor Project Managers shall be provided a copy of the *Contractor's ESH Handbook* found within the Lockheed Martin Request for Proposal or as an appendix of the Key National Contractor Agreement. Contractors shall flow these requirements down to their subcontractors.
- 1.11 Contractor understands that Lockheed Martin may immediately stop Contractor's work if Contractor violates any applicable Federal, State, municipal, local, or any other rules, regulations, and requirements, *Remediation Contractor's ESH Handbook* provisions, or other contract terms and conditions regarding environmental, safety and health compliance. Lockheed Martin shall not incur work stoppage charges unless the contractor demonstrates that the work stoppage was unwarranted for any of the reasons stated above. Any dispute regarding work stoppage charges must be resolved through binding arbitration.
- 1.12 Contractor is advised that the Project may be inspected from time to time by Lockheed Martin or a representative of Lockheed Martin. Periodic Lockheed Martin inspections in no way relieve the Contractor of their obligation to maintain its own inspection program to identify unsafe conditions or acts. ESH violations will be considered in evaluation of Contractor's performance.

- 1.13 Lockheed Martin is not responsible for training or supervising Contractor employees or abating workplace hazards created by the Contractor or to which the Contractor's employees are exposed.
- 1.14 Contractor agrees to maintain copies of all pertinent ESH records at the job site. Pertinent records include, but is not limited to, personnel training documentation, evidence of enrollment in a medical surveillance program, accident/injury reporting, work area inspections, periodic safety meetings, MSDS's, air monitoring data, waste container inspections, etc. These records shall also be provided electronically to the Lockheed Martin Project Lead.
- 1.15 Contractor shall contact the Lockheed Martin Project Lead immediately in the event of a fatal or serious injury, an unpermitted environmental release, or any ESH incident that is likely to generate significant publicity or an adverse situation for Lockheed Martin (e.g., alleged releases of contaminants beyond property boundaries, purported fish or wildlife impacts, allegations of adverse community health or property impacts, etc.)

2 DEFINITION

- 2.1 <u>Contractor</u>: any agent/agency engaged by Lockheed Martin through written contract (or other written agreement) to perform work on Lockheed Martin Remediation Sites. For the purposes of this *Remediation Contractor's ESH Handbook*, "Contractor" shall also include Contractor's subcontractors at any tier.
- 2.2 <u>EPA</u>: the Environmental Protection Agency.
- 2.3 Fed/OSHA: the Federal Occupational Safety and Health Administration
- 2.4 <u>Hazard Communication Program</u>: a written program meeting the requirements of Title 29, Code of Federal Regulations, Section 1910.1200 Hazard Communication.
- 2.5 <u>Lockheed Martin</u>: Lockheed Martin Corporation, Corporate Energy, Environment, Safety & Health
- 2.6 <u>Lockheed Martin Project Lead</u>: the Lockheed Martin Corporate Environment, Safety & Health individual that has been designated to manage a specific project.
- 2.7 <u>Lockheed Martin Contract Representative</u>: the Lockheed Martin Corporate Environment, Safety & Health contract representative (Contract Administrator/Buyer) for the project.
- 2.8 <u>RCRA</u>: the Federal Resource Conservation and Recovery Act and all amendments or revisions.

3 SAFETY & HEALTH

Contractor shall comply with applicable provisions of Federal, State, municipal, local, and any other applicable occupational safety and health statutes, rules, ordinances, regulations and requirements. Contractor shall take all precautions for the protection of the safety and health of Contractor employees, subcontractor employees, and Lockheed Martin employees to prevent accidents or injury to them or to other persons on, about, or adjacent to site of work performance. Notwithstanding this handbook, Contractor will hold harmless Lockheed Martin for any incident, violation, regulatory agency inspection resulting in a finding, or any other ESH issue that occurs to a Contractor employee.

Within Section 3.0, Lockheed Martin is identifying specific requirements within the Federal regulations that need extra attention. These are not all encompassing and adherence to the all rules and regulations must be followed.

3.1 PERSONAL PROTECTIVE CLOTHING AND EQUIPMENT

1926 Subpart E or 1910 Subpart I 1910.139 / 1926.103 ANSI Z87.1 ANSI Z41 Standard ANSI Z89.1 Standard

- 3.1.1 Protective equipment, including personal protective equipment for eyes, face, head, and extremities, protective clothing, respiratory devices, and protective shields and barriers, shall be provided, used, and maintained in a sanitary and reliable condition wherever it is necessary by reason of hazards of processes or environment, chemical hazards, radiological hazards, or mechanical irritants encountered in a manner capable of causing injury or impairment in the function of any part of the body through absorption, inhalation or physical contact.
 - <u>Eye Protection</u>. Safety eyewear meeting ANSI Z87.1 shall be worn in areas designated as "Eye Protection Required" and on all jobs where a potential injury to the eyes is possible whether or not the area is posted.
 - Foot Protection. Affected employee(s) shall wear protective footwear when working in areas where there is a danger of foot injuries due to falling or rolling objects, or objects piercing the sole, and where such employee's feet are exposed to electrical hazards. Safety shoes and boots which meet the ANSI Z41 Standard shall be provided when impact and/or compression hazards exist. Soft-shoes, including but not limited to, tennis shoes, athletic shoes, moccasins, sandals, and open-toed or open-heeled shoes shall not be worn.
 - Respiratory Protection Devices. Appropriate, MSHA/NIOSH-approved respiratory protective devices must be worn when applicable state and/or federal action levels or OSHA permissible exposure levels (PELs) are exceeded. Contractor must have fully implemented a respiratory protection program meeting the requirements of *Title 29*, *Code of Federal Regulations*, Section 1910.139 / 1926.103 or applicable state OSHA regulations prior to issuing and using respiratory equipment. Contractor shall supply and maintain

- appropriate air monitoring and respiratory protection equipment if inhalation hazards are anticipated.
- <u>Protective Clothing</u> such as suits, aprons, boots, or gloves shall be worn where there is a hazard to the body through dermal contact with chemicals, dusts, heat or other harmful agents or conditions.
- <u>Hearing Protection</u> (muffs and/or plugs) must be worn in all areas posted to indicate high noise level or where Contractor employees are exposed to noise levels in excess of the OSHA action level (85 dBA over a 8-hour time-weighted average or a dose of fifty percent).
- <u>Hard Hats</u> will be worn in all areas where there is a danger of impact to the head or hazard from falling or moving objects. Hard hats must meet the ANSI Z89.1 Standard.
- 3.1.2 Contractor will issue or cause to be issued prior to commencing the job all necessary personal protective equipment and air monitoring equipment to all its agents and employees, together with full instructions and training on the use of said equipment.
- 3.1.3 Contractor will meet all applicable Federal, Sate, municipal, local, and Lockheed Martin requirements for protective clothing and equipment. Contractor will properly supervise all its agents and employees to ensure protective clothing and equipment are used in conformance with applicable rules and regulations.

3.2 <u>HAZARD COMMUNICATION - USE OF HAZARDOUS MATERIALS</u>

Title 29, Code of Federal Regulations, Section 1926.59 Hazard Communication Title 29, Code of Federal Regulations, Section 1910.1200 Hazard Communication

- 3.2.1 Contractor personnel shall not bring any hazardous substances (as defined by OSHA) onto Lockheed Martin remediation sites unless accompanied by a Material Safety Data Sheet (MSDS) and the containers are appropriately labeled. MSDS's must be maintained at the job site.
- 3.2.2 Contractor shall notify the Lockheed Martin Project Lead <u>prior</u> to bringing onto Lockheed Martin remediation sites any quantity of hazardous materials.
- 3.2.3 Contractor shall ensure all containers of hazardous materials are labeled in accordance with the Fed OSHA Hazard Communication Standard, 29 CFR 1910.1200 or applicable state OSHA standard.
- 3.2.4 Do not handle or use any hazardous material that does not have adequate safety warning labels.
- 3.2.5 Do not dump, drain or discharge any hazardous materials or wastes into any sink, drain or sewer.
- 3.2.6 The Lockheed Martin Project Lead shall inform the Contractor(s) of the identity of hazardous chemicals to which Contractor's employees may be exposed from

Lockheed Martin operations, if applicable. The Lockheed Martin Project Lead shall provide the following information:

- Where to obtain information concerning any hazardous substances used in Lockheed Martin operations that the Contractor's employees may come in contact with while performing their work;
- If Lockheed Martin owns or uses chemicals on a remediation site for any
 process where contractors could be exposed, Lockheed Martin shall make
 available to the Contractor Material Safety Data Sheets (MSDS) and sufficient
 information to permit the Contractor to train its employees on the hazards of the
 chemical Appropriate protective measure Contractor employees may take to
 protect themselves from exposure to known hazards from Lockheed Martin
 operations; and
- Appropriate work practice procedures (safety rules) for the location where work is to be performed.
- 3.2.7 Contractor shall ensure its employees are trained in the safe handling and use of hazardous materials in accordance with 29 CFR 1910.1200 Hazard Communication or the applicable state-OSHA hazard communication standard.
- 3.2.8 Contractor shall ensure that all applicable employees are medically qualified (as defined by OSHA) to perform the work assigned.
- 3.2.9 Hazardous materials shall be stored in designated areas and all containers effectively closed. Spill equipment/supplies shall be readily available to contain and/or mitigate accidental spills of hazardous materials.

3.3 <u>CONFINED SPACE ENTRY</u>

Title 29, Code of Federal Regulations, Section 1910.146 Permit-Required Confined Spaces

- 3.3.1 If Contractor or any other employee must enter a confined space (tank, vat, pit, sewer, etc.), the entry must be performed in accordance with the applicable state OSHA or federal OSHA regulations.
- 3.3.2 Before Contractor's employees are permitted entry into any confined space, the internal atmosphere shall be tested with a calibrated direct-reading instrument for the following conditions in the order given: 1) Oxygen content, 2) Flammable gases & vapors, and 3) Potential toxic air contaminants. Contractor shall furnish the air testing equipment and a person competent in the use of the testing equipment.
- 3.3.3 When possible, the Contractor shall notify the Lockheed Martin Project Lead prior to entering a permit required confined space. A permit shall be issued by the contractor prior to entry and electronically submit a copy to the Lockheed Martin Project Lead.

- 3.3.4 To ensure the safety of Contractor personnel during entry into confined spaces, the Contractor shall have a written confined space entry program.
- 3.4 HOT WORK REQUIREMENTS (i.e., welding, torch cutting, brazing, etc.)
 - Title 29, Code of Federal Regulations, Section 1910 Subpart Q Title 29, Code of Federal Regulations, Section 1926 Subpart J
 - 3.4.1 All hot work activities shall be conducted in accordance with the hot work permit requirements outlined in the site specific HASP (i.e., fire suppression equipment availability, removal of combustibles, fire watch, etc.).
 - 3.4.2 Contractor personnel must secure all oxygen and acetylene cylinders in a manner that will prevent them from falling or tipping over. Oxygen and acetylene cylinders must be stored separately. Oxygen cylinders in storage must be separated from fuel gas cylinders a distance of 20 feet or by a noncombustible barrier 5 feet high. Acetylene cylinders shall not be stored horizontally, lying on their side.
 - 3.4.3 When welding, Contractor personnel shall use welding curtains and/or suitable protective devices to protect persons from indirect exposure to welding flashes.
- 3.5 LOCKOUT / TAGOUT Control of Hazardous Energy
 - Title 29, Code of Federal Regulations, Section 1910.147
 - 3.5.1 Contractors are required to establish a written program and utilize procedures for affixing appropriate lockout devices or tagout devices to energy isolating devices, and to otherwise disable machines or equipment to prevent unexpected energization, start-up or release of stored energy in order to prevent injury to employee.
 - 3.5.2 Contractor shall not service and/or maintain machines and equipment in which the unexpected energization or start up of the machines or equipment, or release of stored energy could cause injury to employees. Servicing and/or maintaining such equipment shall not be conducted until appropriate energy control methods have been initiated.
 - The Contractor shall provide training to ensure that the purpose and function of the energy control program are understood by their employees and that the knowledge and skills required for the safe application, usage, and removal of the energy controls are acquired by the employees.
 - 3.5.3 If Contractor needs to service or maintain Lockheed Martin equipment, Contractor(s) shall notify the Lockheed Martin Project Lead and/or on-site facility operator (if applicable) of the intended equipment service for any unscheduled maintenance.
 - 3.5.4 Upon completion of the job, Contractor is to notify the Lockheed Martin Project

Lead and/or on-site facility operator (if applicable) so power can be resumed to the equipment after the lock-outs and tags have been removed.

3.6 <u>USE OF LOCKHEED MARTIN MATERIALS AND EQUIPMENT</u>

- 3.6.1 Contractor's employees shall not use Lockheed Martin tools, equipment, materials, or personal protective equipment unless otherwise authorized by Lockheed Martin.
- 3.6.2 Contractor shall not start or stop any production equipment without the approval of the Lockheed Martin Project Lead.
- 3.6.3 Contractor shall not adjust or relocate any Lockheed Martin process equipment without the approval of the Lockheed Martin Project Lead.

3.7 <u>DANGEROUS OPERATIONS - WARNINGS AND BARRICADES</u>

Title 29, Code of Federal Regulations, Section 1926, Subpart G-Signs, signals and barricades

- 3.7.1 Contractor shall isolate their work areas from Lockheed Martin operations, employees, and the public by using barricades or other effective means of isolation. Signs, signals and barricades shall be visible at all times where a hazard exists.
- 3.7.2 Contractor personnel shall erect and properly maintain, at all times, all necessary safeguards for the protection of Contractor personnel, Lockheed Martin employees and the public. This includes:
 - If doing any overhead work, Contractor must utilize warning signs and barricades, or station someone on the ground to prevent passers-by from entering the area below the overhead work;
 - Contractor must effectively barricade excavations, floor openings, etc., as required by OSHA regulations;
 - Contractor must construct and maintain all scaffolds and working platforms in accordance with OSHA regulations; and
 - If Contractor's equipment, barricades or other safeguards restrict fire lanes or fire equipment access, the Contractor shall notify the Lockheed Martin Project Lead about its notification to the local fire department.
- 3.7.3 Prior to commencing work, Contractor must inform Lockheed Martin Project Lead of any work posing a potential danger to personnel.

3.8 <u>EXCAVATIONS, TRENCHES, EARTHWORK</u>

Title 29, Code of Federal Regulations, Section 1926 Subpart P

3.8.1 Review the Lockheed Martin intrusive fieldwork requirements in Appendix A.

- 3.8.2 If workers are to enter excavations, a competent person must be designated and trained in soil classification and the recognition of trenching and excavation hazards.
- Excavations and trenches shall be inspected by a competent person daily and after every rainstorm, earthquake, or other hazard-increasing occurrence.
- 3.8.4 Inspect the face, banks, and top daily when workers are exposed to falling or rolling materials.
- 3.8.5 Shore, bench, slope, or use equivalent methods to protect workers in excavations four feet deep or more.
- 3.8.6 Locate soil at least two feet from the edge of the excavation, or one foot from the edge when the excavation is less than five feet deep.
- 3.8.7 Ladders or steps shall be provided and secured in all trenches four feet or more in depth. Ladders shall be located to require no more than twenty-five feet of lateral travel before having access or egress and shall extend three feet above the top of the trench bank.
- Install crossings with standard guardrails and toeboards when the excavation is more than $7\frac{1}{2}$ feet deep.
- 3.8.9 All open trenches and other excavations shall be provided with suitable barriers, signs, and lights to the extent that adequate protection is provided to the public.
- 3.8.10 Do not excavate beneath the level of adjacent foundations, retaining walls, or other structures until a qualified person has determined that the work will not be hazardous. Support undermined sidewalks.

3.9 ELECTRICAL SAFETY

Title 29, Code of Federal Regulations, Section 1926 Subpart K-Electrical Title 29, Code of Federal Regulations, Section 1910.269 Electrical Power Generation, Transmission and Distribution

- 3.9.1 Only qualified persons are permitted to work on electrical systems, as defined by *Title 29, Code of Federal Regulations Section 1910.269(a)(2)*. Qualified persons shall be trained and competent in:
 - The skills and techniques necessary to distinguish exposed live parts from other parts of electrical equipment;
 - The skills and techniques necessary to determine the nominal voltage of exposed live parts;
 - The minimum approach distances specified by OSHA corresponding to the voltages to which the qualified employee will be exposed; and

- The proper use of the special precautionary techniques, personal protective equipment, insulating and shielding materials, and insulated tools for working on or near exposed energized parts of electrical equipment.
- 3.9.2 Contractor personnel shall properly ground all electrical tools, mechanical digging or concrete breaking equipment and all other electrical equipment while in use.
- 3.9.3 All electrical work, installation and wire capacities shall be in accordance with the pertinent provisions of the National Electrical Code, ANSI and OSHA.
- 3.9.4 Covers or barriers must be installed on boxes, fittings, and enclosures to prevent accidental contact with live parts.
- 3.9.5 Temporary wiring installations must be grounded.
- 3.9.6 Electrical systems shall be de-energized utilizing appropriate lockout/tagout procedures prior to conducting work.

3.10 <u>ELEVATED LOCATIONS / FALL PROTECT</u>

Cal/OSHA General Industry Safety Orders, 8 CCR 3210 Title 29, Code of Federal Regulations, Section 1926 Subpart M – Fall Protection

- 3.10.1 <u>California employers</u>: Guardrails shall be provided on all open sides of unenclosed room openings, open and glazed sides of landings, balconies or porches, platforms, runways, ramps, or working levels more than 30 inches above the floor, ground, or other working areas. The railing must be provided with a toeboard where the platform, runway, or ramp is 6 feet or more above places where employees normally work or pass and the lack of a toeboard could create a hazard from falling tools, material, or equipment.
- 3.10.2 Contractor must provide fall protection systems whenever a worker is exposed to a fall of four feet or more (in construction the threshold is six feet). Guardrails are the most common forms of fall protection systems. If guardrail systems are not feasible, safety nets, personal fall arrest systems, positioning device systems, warning line systems, or some other demonstrated, effective means of fall protection shall be used. Fall protection systems and devices shall be inspected prior to each use Title 29, Code of Federal Regulations, Section 1926 Subpart M.

3.11 LADDERS

Title 29, Code of Federal Regulations, Section 1910 Subpart D – Walking and Working Surfaces

Title 29, Code of Federal Regulations, Section 1926 Subpart X - Ladders

- 3.11.1 The use of ladders with broken or missing rungs or steps, broken or split rails or other defective construction is prohibited.
- 3.11.2 Ladders shall extend no less than 36 inches above landing and be secured to

prevent displacement.

- 3.11.3 Portable ladders must be equipped with safety shoes.
- 3.11.4 Wooden ladders shall not be painted.
- 3.11.5 Do not use metal ladders for electrical work or near live electrical parts.

3.12 SCAFFOLDS

Title 29, Code of Federal Regulations, Section 1910.28 – Safety Requirements for Scaffolding

Title 29, Code of Federal Regulations, Section 1926 Subpart L - Scaffolds

- 3.12.1 Scaffolds must be provided for all work that cannot be done safely by employees standing on solid construction at least 20 inches wide, except where such work can be safely done from ladders.
- 3.12.2 Erection and dismantling of scaffolds shall be performed in accordance with good engineering practice.
- Footings or anchorage for any scaffold shall be sound, rigid and capable of carrying the maximum intended load without settling or displacement.
- 3.12.4 No unstable objects such as concrete blocks shall be used to support scaffolds or planks.
- 3.12.5 Any part of a scaffold weakened or damaged shall be repaired or replaced immediately.
- 3.12.6 All scaffold planking shall be free of knots and cracks (Class A number) and shall completely cover the work platform.
- 3.12.7 Scaffold planks shall be laid tight, cleated at both ends or overlapped a minimum of 12 inches and nailed or bolted to prevent movement. Overlaps to occur directly above scaffold supports.
- 3.12.8 A safe and unobstructed means of access, such as a walkway, stair, or ladder shall be provided to all scaffold platforms.

3.13 HEAVY EQUIPMENT, INDUSTRIAL VEHICLES, AND CRANES

Title 29, Code of Federal Regulations, Section 1926 Subparts N, O and W

- 3.13.1 Only trained and authorized workers may operate heavy equipment, industrial vehicles, and/or cranes.
- 3.13.2 The Contractor shall designate a competent person who shall inspect all machinery and equipment prior to each use to make sure it is in safe operating condition.

- 3.13.3 The Contractor shall comply with the manufacturer's specifications and limitations applicable to the operation of any and all heavy equipment, industrial vehicles, and cranes.
- 3.13.4 Seatbelts are required to be worn if the vehicle has Roll-Over Protection Structures (ROPS).
- 3.13.5 The swing radius of cranes shall be barricaded.
- 3.13.6 Equipment shall not be lubricated while in use.
- 3.13.7 Rated load capabilities, recommended operating speeds, special hazard warning, specific hand signal diagrams and special instructions shall be visible to the operator while he is at the control station.
- 3.13.8 Contractor's employees shall not be allowed to work under the load of cranes. Tag lines shall be used on all loads.

3.14 OVERHEAD POWER LINES

Title 29, Code of Federal Regulations, Section 1926.550 (a) (15)

- 3.14.1 If work is to be performed near overhead power lines, the lines must be deenergized and grounded by the owner or operator of the lines, or other protective measures must be provided before work is started. Protective measures (such as guarding or insulating the lines) must be designed to prevent employees from contacting the lines.
- 3.14.2 Unqualified employees and mechanical equipment must stay at least 10 feet away from overhead power lines. If the voltage is over 50,000 volts, the clearance should be increased by four inches for each additional 10,000 volts.
- 3.14.3 When mechanical equipment is being operated near overhead lines, employees standing on the ground may not contact the equipment unless it is located so that the required clearance cannot be violated even at the maximum reach of the equipment.
- 3.14.4 A person shall be designated to observe clearance of the equipment and give timely warning for all operations where it is difficult for the operator to maintain the desired clearance by visual means.
- 3.14.5 Any overhead wire shall be considered to be an energized line unless and until the person owning such line or the electrical utility authorities indicates that it is not energized.

3.15 FIRE PREVENTION / FLAMMABLE LIQUIDS

Title 29, Code of Federal Regulations, Section 1926 Subpart F or 1910 Subpart E

3.15.1 Contractor shall be responsible for fire protection in its work and operational areas,

including offices, tool rooms, and storage areas 24 hours per day, seven days per week through the duration of this Contract. Approved fire-fighting equipment, in adequate quantities, must be provided.

- 3.15.2 Contractor shall familiarize Contractor's employees with the locations of fire extinguishers in their respective work areas and ensure they are prepared to use them safely if necessary. In certain remote field locations or within abandoned (discontinued) facilities where fire extinguishers may not exist in the immediate work area, contractor shall provide and locate fire extinguisher(s) in close proximity to the active work area(s).
- 3.15.3 In case of fire, Contractor shall call 9-1-1. Contractor shall also inform all Contractor and Lockheed Martin employees in the area to evacuate to a safe place and direct arriving fire response personnel to the fire. Notify the Lockheed Martin Project Lead as soon as reasonably possible.
- 3.15.4 Contractor employees shall only attempt to put out a fire when such action can be performed safely.
- 3.15.5 If a Contractor employee uses a Lockheed Martin fire extinguisher, Contractor shall report its use to the Lockheed Martin Project Lead.
- 3.15.6 Contractor shall report all fires extinguished by the Contractor to the Lockheed Martin Project Lead.
- 3.15.7 Contractors are to store, dispense, and use flammable and combustible liquids in accordance with OSHA regulations and the Uniform Fire Code. Bonding and grounding of containers containing flammable liquids will be required.
- 3.15.8 Open flames and smoking shall not be permitted in flammable or combustible liquid storage areas.
- 3.15.9 Contractor shall provide sufficient fire extinguishers necessary for their work activities.

3.16 HAND AND POWER TOOLS

Title 29, Code of Federal Regulations, Section 1910 Subpart P – Hand and Portable Powered Tools and Other Hand-Held Equipment

Title 29, Code of Federal Regulations, section 1926 Subpart I – Tools Hand and Power

- 3.16.1 All hand and power tools, whether furnished by Contractor, or by Contractor's employee, shall be maintained in a safe condition.
- 3.16.2 Electrical power tools shall be grounded or double insulated with proper assured equipment grounding inspections or Ground Fault Interrupter (GFI) circuit protection provided.

- 3.16.3 Pneumatic power tools shall be secured to the hose or whip by some positive means.
- 3.16.4 Only properly trained Contractor employees shall operate power-actuated tools.
- 3.16.5 All grinding machines shall conform to OSHA and ANSI requirements.

3.17 COMPRESSED GAS CYLINDERS

Title 29, Code of Federal Regulations, Section 1910.101 – Compressed Gases Title 29, Code of Federal Regulations, Section 1926.350 – Gas Welding and Cutting

- 3.17.1 Compressed gas cylinders shall be secured in an upright position at all times.
- 3.17.2 When transporting, moving and storing cylinders, valve protection caps shall be in place and secured.
- 3.17.3 Compressed gas cylinders shall be kept away from excessive heat, shall not be stored where they might be damaged or knocked over by passing or falling objects, and shall be stored at least 20 feet away from highly combustible materials.
- 3.17.4 Cylinders shall be labeled as to the nature of their contents.
- 3.17.5 Oxygen cylinders in storage shall be separated from fuel gas cylinders or combustible materials a minimum of 20 feet or by a noncombustible barrier at least five feet high having a fire-resistant rating of at least one-half hour.
- 3.17.6 Acetylene cylinders shall be stored and used in a vertical, valve-end-up position only.
- 3.17.7 Anti-flashback arrestors shall be installed on all oxygen and acetylene cylinders.

3.18 <u>INCIDENTAL CONTACT WITH ASBESTOS</u>

- 3.18.1 This section applies to all contractors who incidentally disrupt the matrix of asbestos containing material (ACM) or presumed asbestos containing material (PACM); i.e., contractors who have <u>not</u> been specifically hired to perform ACM abatement.
- 3.18.2 Contractor shall <u>immediately</u> report to the Lockheed Martin Project Lead and to other employers of employees working at the job site any discovery, disturbance, and/or spill of ACM and/or PACM. Contractor(s) is to cease all operations in the immediate area of the suspect ACM and/or PACM and demarcate the area. The approval of the Lockheed Martin Project Lead is required before resuming operations.

- 3.18.3 Contractor shall not disturb any pipe insulation, boiler insulation, or any other material reasonably suspected of containing asbestos until the Contractor notifies the Lockheed Martin Project Lead. Lockheed Martin approval is required before operations may commence.
- 3.18.4 Abatement of asbestos can be performed only by persons properly trained and licensed to perform such activities

3.19 ASBESTOS ABATEMENT CONTRACTORS

- 3.19.1 This section applies to Contractors performing maintenance, construction, repair, renovation, demolition, salvage, or any other operation in which any material containing more than 1% asbestos is sanded, abrasive blasted, sawed, shoveled, removed, or otherwise handled in a manner that would generate airborne asbestos fibers. These requirements are in addition to any requirements contained in Contractor's scope of work.
- 3.19.2 All Contractors working with asbestos shall comply with applicable federal and state OSHA, EPA, local air district, and other applicable Federal, State, municipal, and local statutes, regulations, rules, and ordinances; and specific contract terms and conditions regarding the handling of, use of, and work involving asbestos.
- 3.19.3 The contractor shall ensure that a competent person, as defined by OSHA supervises all asbestos work performed within regulated areas.
- 3.19.4 Before commencing work, all asbestos abatement contractors shall supply to Lockheed Martin proof of:
 - Asbestos abatement contractor certification by the state Contractor's License Board
 - Liability insurance for Contractor employees engaged in asbestos work operations
 - Copies of asbestos work notification letters to state OSHA
 - Local air district Asbestos Demolition/Renovation Notification
- 3.19.5 Contractors shall minimize the creation and spread of airborne asbestos fibers by using appropriate work practices, engineering controls, and established procedures (i.e., wet methods, HEPA filter vacuums, negative pressure enclosure, local exhaust ventilation equipped with HEPA filter dust collection system, etc.).
- 3.19.6 All Class I, II and III asbestos work shall be conducted within regulated areas. The regulated area shall be demarcated in any manner that minimizes the number of persons within the area and protects persons outside the area from exposure to airborne asbestos. Where critical barriers or negative pressure enclosures are used, they may demarcate the regulated area. Signs shall be provided and displayed at each location where a regulated area is required to be established. Signs shall be posted at such a distance from such a location that an employee may read the signs

and take necessary protective steps before entering the area marked by the signs. Warning signs shall bear the following information:

DANGER ASBESTOS CANCER AND LUNG DISEASE HAZARD AUTHORIZED PERSONNEL ONLY

- 3.19.7 On multiple employer worksites requiring the establishment of a regulated area, the asbestos Contractor shall inform other employers on the site of the nature of the work with asbestos and/or PACM, of the existence of and requirements pertaining to regulated areas, and the measures taken to ensure that employees of such other employers are not exposed to asbestos.
- 3.19.8 Contractors shall package and label asbestos waste in accordance with federal and or applicable state OSHA requirements and federal or applicable state hazardous waste regulations. Labels shall be affixed to all products containing asbestos and to all containers containing such products, including waste containers. Labels shall be printed in large, bold letters on a contrasting background and shall contain the following information:

DANGER CONTAINS ASBESTOS FIBERS AVOID CREATING DUST CANCER AND LUNG DISEASE HAZARD

- 3.19.9 Contractors shall properly dispose of all asbestos waste. Proper disposal includes the use of hazardous waste manifests and Lockheed Martin approved and licensed waste haulers, and disposal facilities according to federal RCRA law and applicable state hazardous waste regulations. Contractor shall contact the Lockheed Martin Project Lead before transporting or disposing of any hazardous waste. Lockheed Martin must review all hazardous waste manifests prior to shipment.
- 3.19.10 Contractors shall ensure that employee exposure air monitoring is conducted as required by federal or applicable state OSHA regulations. All other air monitoring (i.e. clearance sampling) shall be conducted by a third-party contracted air monitoring firm not affiliated with the Contractor.
- 3.19.11 Contractor shall, at no cost to the employee, institute a training program for and ensure the participation of all employees engaged in asbestos-related work who may reasonably be expected to be exposed to asbestos fibers from asbestos containing construction materials.
- 3.19.12 Contractor shall institute a medical surveillance program for all employees who are or will be exposed to airborne concentrations of fibers of asbestos at or above the TWA and/or excursion limit.

3.20 <u>HAZARDOUS WASTE OPERATIONS and EMERGENCY RESPONSE</u>

(HAZWOPER)

Title 29, Code of Federal Regulations, Section 1910.120 - Hazardous Waste Operations and Emergency Response

Title 29, Code of Federal Regulations, Section 1926.65 – Hazardous Waste Operations and Emergency Response

This section applies to Contractors performing hazardous waste-type activities. This includes operations that pose a potential or reasonable possibility for employee exposure to hazardous waste/chemical contaminants during site investigations, clean-up operations, abatement, or hazardous substance removal work (remedial actions). These requirements are in addition to any requirements contained in Contractor's scope of work.

3.20.1 Contractor shall provide a **site-specific safety and health plan** at least two (2) weeks prior to field mobilization to the Lockheed Martin Project Lead (global statement – move to the beginning).

Contractor shall provide a **safety and health plan** in accordance with *Title 29*, *Code of Federal Regulations*, *Section 1910.120 - Hazardous Waste Operations and Emergency Response* or the applicable state OSHA standard and, at a minimum, shall contain the following elements:

- Safety and health risk or hazard analysis for each anticipated site task
- Employee training requirements
- Personal protective equipment to be used by employees for each of the site tasks and operations
- Medical surveillance requirements
- Frequency and types of air monitoring, personnel monitoring, and environmental sampling techniques and instrumentation to be used, including methods of maintenance and calibration of monitoring and sampling equipment to be used
- Site control measures
- Decontamination requirements and procedures
- Emergency response plan
- Confined space procedures (if applicable)
- Emergency response plan
- Confined space procedures (if applicable)
- Spill containment program
- Periodic documented safety meetings
- Periodic documented work area safety inspections and corrective actions
- 3.20.2 Contractors performing hazardous waste-type operations shall adhere to the requirements specified in 29 CFR 1910.120 Hazardous Waste Operations and Emergency Response or the applicable state OSHA standard.
- 3.20.3 <u>Training</u>: All Contractor and subcontractor employees working on site who are potentially exposed to hazardous substances shall receive initial and annual

refresher training in accordance with 29 CFR 1910.120(e) – Hazardous Waste Operations and Emergency Response or the applicable state OSHA standard. Lockheed Martin shall be provided with electronic copies of the training certificates.

- 3.20.4 <u>Medical Surveillance</u>: Contractor employees must be enrolled in a medical surveillance program prior to performing hazardous waste operations. Upon Lockheed Martin request, Contractor shall provide evidence of employee enrollment in a medical surveillance program. Lockheed Martin does not provide medical surveillance examinations to Contractor employees.
- 3.20.5 <u>Periodic work area inspections</u>: Contractor agrees to perform periodic work area inspections to determine the effectiveness of the site safety and health plan and to identify and correct unsafe conditions in contractor's responsible work area. These inspections shall be documented and available to Lockheed Martin upon request for review.

3.21 <u>MANAGEMENT OF NANOTECHNOLOGY</u>

- 3.21.1 The Lockheed Martin Project Lead shall work with the designated contractor responsible for nanotechnology to implement this procedure and ensure areas where nanomaterials (materials incorporating engineered nanoparticles or nanoscale features that exhibit unique physical and chemical properties as a result of the nanoparticles or nanoscale features) will be used meet engineering control requirements of this procedure.
- 3.21.2 The contractor shall ensure that the safety and environmental hazards of nanomaterials are managed as described in the requirements of this section.
- 3.21.3 A plan must be developed and executed that addresses the following requirements:
 - 3.21.3.1 **Hazard Analysis:** Identify potential adverse health effects and environmental impacts that could result from the chemical and physical properties exhibited by the nanomaterials and/or nanoparticles in use, to be used, under development, or to be developed at the site.
 - 3.21.3.2 **Exposure Assessment**: Evaluate all tasks involving nanomaterials and identify where exposures could occur. The evaluation must include at a minimum, an evaluation of materials; chemical intermediates; by-products; end-products; waste products; processes; process equipment; the amount of material used; material form; degree of containment; duration of use; and work space including laboratory and manufacturing space.

3.21.3.3 Exposure Control

• Implement appropriate controls to mitigate worker exposure and environmental emissions identified in sections 3.21.2.1 and 3.21.2.2 of this procedure.

• Implement Control Bands as indicated on the Control Band Matrix below.

Exposure	Bound	Potential	Free /	
Duration	Materials	Release	Unbound	
Hazard	Group A (K	nown to be i	nert)	
Short	1	1	2	
Medium	1	1	2	
Long	1	2	2	
Haz		3 (Understan	d	
	reactivity/f	unction)		
Short	1	2	2	
Medium	1	2	3	
Long	1	3	3	
Hazard Group C (Unknown Properties)				
Short	2	2	3	
Medium	2	3	4	
Long	2	4	4	

Duration Key:

Short - Less than 4 hrs/day; 2 days/week

Medium - Between 4 to 6 hrs/day; 3 to 5 days/week

Long - 6 to > 8 hrs/day; 3 to 5 days/week

Release Key:

Bound Materials: Nanoparticles in a solid matix e.g. polycarbonate

Potential Release: Nanoparticles in friable or solgel matrix Free / Unbound: Nanoparticles unbound, not aggregated

Control Band:

- 1. General Ventilation and PPE
- 2. Engineering Controls and/or Respirators and additional PPE
- 3. Containment e.g. glove box
- 4. Specialist Advise
- Establish designated areas for Control Banding. The designated area shall, at a minimum, include warning signs informing employees that they are entering a nanomaterial work area as well as signs specifying administrative controls and personal protective equipment (PPE) required for entry.
- Identify appropriate administrative controls (e.g. good housekeeping methods, HEPA vacuums, wet wipe methods, employee training, safe work practices), engineering controls (e.g. containment, exhaust ventilation) and Personal Protective Equipment (e.g. respiratory protection, protective coveralls, gloves, goggles) based on Control Band and best industry practices.
- Develop and execute procedures for housekeeping, including clean-asyou-go practices that do not re-suspend particles.
- Develop and execute procedures for management of nanomaterialassociated waste.

4 ENVIRONMENTAL

Contractors shall comply with all applicable provisions of Federal, State, municipal, local, and other environmental statutes, rules, and regulations. Contractor shall take all necessary precautions to protect the environment. Contractor shall also store, transport, dispose, or otherwise handle hazardous wastes and non-hazardous wastes to prevent discharges of materials into the environment except in accordance with applicable governmental regulations.

4.1 HAZARD COMMUNICATION - USE OF HAZARDOUS MATERIALS

4.1.1 Contractor shall develop a Waste Management Plan in accordance with the requirements outlined in the LMC Remediation Waste Management Procedure in

- Appendix B. Lockheed Martin shall approve the Waste Management Plan prior to work commencement.
- 4.1.2 Contractor must segregate hazardous from non-hazardous waste; all hazardous waste generated by its operations must be labeled in accordance with all governmental regulations.
- 4.1.3 Contractor shall dispose of all hazardous waste within the time frame stipulated by local, state, or federal regulations. Contractor shall not leave behind on Lockheed Martin remediation sites any containers of hazardous materials or waste (including drums, roll-offs, maintenance chemicals, etc.), empty or not, after the termination of operations.
- 4.1.4 In case of a spill or release of hazardous materials or waste, Contractor shall immediately notify the Lockheed Martin Project Lead and if the severity of the spill warrants, notify the local fire department (Call 9-1-1). The Contractor shall be liable for the costs of any spill resulting from Contractor's actions, including, but not limited to, costs of containment, cleanup, and disposal.

4.2 NON-HAZARDOUS WASTE DISPOSAL

4.2.1 Contractor shall develop a Waste Management Plan in accordance with the requirements outlined in the LMC Remediation Waste Management Procedure in Appendix B. This plan must be approved by the Lockheed Martin Project Lead.

4.3 WORK INVOLVING AIR EMISSIONS

- 4.3.1 Contractor shall work with the Lockheed Martin Project Lead to identify applicable Federal, state, and/or local permit application requirements for air emission sources (i.e., stationary point source, fugitive emissions, etc.) associated with the anticipated project.
- 4.3.2 Contractor shall submit permit applications and/or notifications to the Lockheed Martin Project Lead for review prior to submittal to the applicable regulatory agency.
- 4.3.3 Contractor shall abide by the requirements of the permit(s) and gather emissions data (as applicable) to document compliance. This data shall be electronically submitted to the Lockheed Martin Project Lead.
- 4.3.4 Contractor shall immediately contact the Lockheed Martin Project Lead in the event permit conditions are not met.
- 4.3.5 Ensure permits are posted on permitted equipment (or in close proximity) as required by the respective permit.

4.4 WORK INVOLVING WATER DISCHARGES

- 4.4.1 At no time is an unauthorized, unpermitted release allowed. Contractor shall notify the Lockheed Martin Project Lead in the event of a release and obtain the approval of Lockheed Martin before discharging any material into storm drains or sewers.
- 4.4.2 Contractor shall work with the Lockheed Martin Project Lead to identify applicable National Pollutant Discharge Elimination System (NPDES), Stormwater Pollution Prevention Plans (SWPPP), and POTW requirements associated with the anticipated project.
- 4.4.3 Contractor shall submit permit applications and/or Notice of Intent forms to the Lockheed Martin Project Lead for review prior to submittal to the applicable regulatory agency.
- 4.4.4 Contractor shall abide by the requirements of the discharge permit(s) and maintain discharge monitoring information and inspection data to document compliance. This documentation shall be electronically provided to the Lockheed Martin Project Lead.
- 4.4.5 Contractor shall immediately contact the Lockheed Martin Project Lead in the event permit conditions are not met.

5 HOUSEKEEPING / CLEANUP

- 5.1 Ensure discharge permits and/or SWPPP plans (as applicable) are available at the project job site.
- 5.2 Contractor shall continuously clean up its respective work area(s). Contractor shall maintain its work areas free from all slip, trip, and fall hazards at all times.
- 5.3 Debris shall be kept cleared from work areas, passageways, stairs, and in and around buildings or other structures. The work area must be left free from accumulation of waste and rubbish at the end of each work shift.
- 5.4 Combustible scrap and debris shall be removed at regular intervals during the course of work performed by Contractor. Safe means shall be provided to facilitate such removal.
- 5.5 At the end of each working day and/or the conclusion of work being performed, Contractor shall restore the work area to the same degree of neatness as when work commenced.
- 5.6 Contractor shall furnish necessary equipment and/or receptacles to remove waste and rubbish from the job site unless otherwise specified by the Lockheed Martin.

6 CHANGE MANAGEMENT

If deviations are encountered from the field work plan, the contractor shall A) notify to the Lockheed Martin Project Lead and B) suspend work to assess changes to the work plan(s) and the HASP. Changes to the work plan(s) and the HASP shall be reviewed by the PL.

7 REQUIREMENT TO PERFORM & DOCUMENT SELF-AUDITS

- 7.1 Contractor agrees to perform periodic work area/project field inspections to monitor compliance with project environmental, safety and health (ESH) requirements. The name of Contractor's jobsite ESH representative will be provided to Lockheed Martin prior to the Contractor starting work at the jobsite.
- 7.2 For jobs that are ongoing, an annual ESH audit shall be conducted and for jobs with a duration of less than one year at least one audit shall occur. A competent ESH representative designated by the Contractor shall perform the audit. Unsafe acts and/or non-compliance conditions noted during inspections shall be corrected immediately.
- 7.3 The documentation related to the audits and inspections shall be submitted electronically to the Lockheed Martin Project Lead.

8 ACCIDENT, INJURY, ILLNESS, INCIDENT and SPILL REPORTING

- 8.1 Contractor shall immediately contact the Lockheed Martin Project Lead and/or Lockheed Martin Safety & Health Manager in the event of a fatality, injury, environmental release (spill), near-miss incident, or any ESH incident that is likely to generate significant publicity. A written report of the incident/injury/spill and corrective action(s) taken shall be submitted to the Lockheed Martin Project Lead within one (1) day of the incident. Representatives from Lockheed Martin may conduct joint investigations with the contractor if deemed necessary.
- 8.2 In case of a spill or release of hazardous chemicals, Contractor shall immediately notify the Lockheed Martin Project Lead, and/or if the severity of the spill warrants, the local fire department by calling 9-1-1. Contractor shall take all necessary steps to control the spread of the release and to provide site control to prevent unauthorized personnel from entering the affected area. The Contractor shall be liable for the costs of any spill resulting from Contractor's actions, including, but not limited to, costs of containment, cleanup, and disposal.

9 FINES, PENALTIES AND COSTS

9.1 Contractor shall indemnify and hold Lockheed Martin harmless from any and all liability (including but not limited to fines and penalties), loss, cost, damage, or expense (including attorney's fees) suffered or incurred by Lockheed Martin by reason of Contractor's failure to comply with Federal, State, municipal, local or other laws, rules, regulations, ordinances and requirements, or failure to comply with generally accepted environmental safety and health practices.

10 <u>LOCKHEED MARTIN ESH MANAGER</u>

The Lockheed Martin ESH Manager is Jimmy Yeager. Contact Jimmy regarding any questions or concerns at (301) 873-1444 or via email at james.l.yeager@lmco.com.

Appendix A – LMC Requirements for Invasive Fieldwork



LMC Minimum Requirements for Inv

Appendix B – LMC Waste Management Procedure



LMC Waste Mgmt Procedure Rev 4



CONTRACTOR'S ESH HANDBOOK

COMPLIANCE AGREEMENT

The Key National Contractor Program Manager has read and understands the contents of the *Contractor's ESH Handbook*. Contractor agrees while performing work on Lockheed Martinowned or Lockheed Martin-controlled premises, that the Contractor shall require its employees and subcontractors at any tier to comply with the contents of this *Contractor's ESH Handbook* and the job specific HASP. A copy of the HASP shall be maintained at the job site and made readily available to contractor and subcontractor employees for their information. All contractor employees and subcontractors shall read and certify that they have read and understand the job specific health and safety plan (HASP). The certification forms shall be electronically sent to the Lockheed Martin Project Lead.

I further understand that this handbook and the rules and regulations it contains do not in any way relieve the Contractor (employer) of its responsibility to comply with the applicable environmental safety and health (ESH) regulations and its obligation to implement and enforce its own written ESH programs while working on this project.

Company:	 	 	
Name:	 		
Signature:	 		
Title:	 	 	
Date:			

COMPLETE, SIGN AND RETURN THIS CERTIFICATE TO THE LOCKHEED MARTIN ESH MANAGER.

ATTACHMENT II INCIDENT REPORT FORM



Report Date	Report Prepared B	у	Incident Report Number	
	INSTRUCTI	IONS:		
All incidents (including those			rect supervision of Tetra Tech	
	nel) must be docum			
Complete any additional parts	to this form as indic	cated below fo	r the type of incident selected.	
TYPE OF INCIDENT (Check all that apply)	Additional Form	s) Required for this type of incident	
Near Miss (No losses, but could have resudamage)	ulted in injury, illness, or	Comp	olete IR Form Only	
Injury or Illness		Comp	olete Form IR-A; Injury or Illness	
Property or Equipment Damage, Fire, Spill	or Release	Comp	olete Form IR-B; Damage, Fire, Spill or ase	
Motor Vehicle			olete Form IR-C; Motor Vehicle	
INFORMATION ABOUT THE INCIDENT				
Description of Incident				
Date of Incident	Time of	Incident		
		AM L	PM OR Cannot be determined	
Weather conditions at the time of the inc	ident Was the	re adequate lighti	ng?	
			Yes	
Location of Incident				
		, ,	er's work environment? Yes	
Street Address	С	ity, State, Zip Coo	le and Country	
			_	
Project Name	С	lient:		
Ti Our and an Building			41	
Tt Supervisor or Project Manager	W	las supervisor on		
WITNESS INC	RMATION (attach ac	dditional abox	Yes No No	
	•		ts if necessary)	
Name	C	ompany		
Street Address		ity, State and Zip	Code	
Olicet Audiess	C	ny, state and zip	Oout	
Telephone Number(s)				
Totophone Humber(3)				



CORRECTIVE ACTIONS					
Corrective action(s) immediately taken b	y unit reporting the incident:			
Corrective action(s	s) still to be taken (by	whom and when):			
	R	OOT CAUSE ANALYSIS I	EVEL REQUIRED		
Root Cause Analysis	s Level Required: Lev	el - 1 Level - 2 None			
Root Cause Analys	is Level Definitions				
Level - 1	Definition: A Level 1 RCA is conducted by an individual(s) with experience or training in root cause analysis techniques and will conduct or direct documentation reviews, site investigation, witness and affected employee interviews, and identify corrective actions. Activating a Level 1 RCA and identifying RCA team members will be at the discretion of the Corporate Administration office. The following events may trigger a Level 1 RCA: Work related fatality Hospitalization of one or more employee where injuries result in total or partial permanent disability Property damage in excess of \$75,000 When requested by senior management Definition: A Level 2 RCA is self performed within the operating unit by supervisory personnel with assistance of the operating unit HSR. Level 2 RCA will utilize the 5 Why RCA methodology and document the findings on the tools provided.				
Level - 2	OSHA recordNear miss in	nts will require a Level 2 RCA: dable lost time incident cident that could have triggered a sted by senior management	a Level 1 RCA		
Complete the Rooi identified within ea		orksheet and Corrective Action	n form. Identify a corrective	action(s) for each	root cause
		NOTIFICATION	ONS		
Title		Printed Name	Signature	Telephone Number	Date
Project Manager or S	Supervisor				
Site Safety Coordinator or Office H&S Representative					
Operating Unit H&S Representative					
Other:					
The signatures provided above indicate that appropriate personnel have been notified of the incident.					



INSTRUCTIONS: Complete all sections below for incidents involving injury or illness. Do NOT leave any blanks. Attach this form to the IR FORM completed for this incident. Incident Report Number: (From the IR Form) **EMPLOYEE INFORMATION Company Affiliation** Tetra Tech Employee? TetraTech subcontractor employee (directly supervised by Tt personnel)? **Full Name** Company (if not Tt employee) Street Address, City, State and Zip Code **Address Type** Home address (for Tt employees) Business address (for subcontractors) **Telephone Numbers** Cell: __ Work: __ Home: _ Occupation (regular job title) Department Was the individual performing regular job duties? Time individual began work Yes No No AM PM OR Cannot be determined Safety equipment Hard hat Type(s) provided: Protective clothing Yes No No Provided? Gloves High visibility vest Yes No If no, explain why Used? Eye protection Fall protection Safety shoes Machine guarding Respirator Other (list) **NOTIFICATIONS** Name of Tt employee to whom the injury or illness was first Was H&S notified within one hour of injury or illness? reported Yes No No **H&S Personnel Notified** Date of report Time of report Time of Report If subcontractor injury, did subcontractor's firm perform their own incident investigation?

Yes No If yes, request a copy of their completed investigation form/report and attach it to this report.



TETRA TECH, INC. INCIDENT FORM IR-A

	INJURY / IL	LNESS DETAILS			
What was the individual doing just before to individual was using. Be specific. Examples: "Only computer key-entry"	What was the individual doing just before the incident occurred? Describe the activity as well as the tools, equipment, or material the individual was using. Be specific. Examples: "Climbing a ladder while carrying roofing materials"; "Spraying chlorine from a hand sprayer"; "Daily computer key-entry"				
				_	
what Happened? Describe how the injury oc sprayed with chlorine when gasket broke during	What Happened? Describe how the injury occurred. Examples: "When ladder slipped on wet floor and worker fell 20 feet"; "Worker was sprayed with chlorine when gasket broke during replacement"; Worker developed soreness in wrist over time"				
Describe the object or substance that directly harmed the individual: Examples: "Concrete floor"; "Chlorine"; "Radial Arm Saw". If this question does not apply to the incident, write "Not Applicable".					
				_	
	MEDICAL	CARE PROVIDED			
		CARE PROVIDED			
Was first aid provided at the site: Yes N	No L If yes, des	cribe the type of first aid a	administered and by whon	ነ?	
Was treatment provided away from the site: Y	es No	If yes, provide the informa	ation below.		
Name of physician or health care profession	nal	Facility Name			
Street Address, City State and Zip Code		Type of Care?			
	_	Was individual treated in	n emergency room?	Yes No N	
	_		zed overnight as an in-pat	tient? Yes No	
Telephone Number		Did the individual die?	Yes No If y	yes, date:	
relephone Number		Will a worker's compens	sation claim be filed?	Yes No No	
NOTE: Attach any police reports or related of	diagrams to this re	port.			
SIGNATURES					
I have reviewed this report and agree that all th	e supplied informat	ion is accurate			
Affected individual (print)	Affected individu	ual (signature)	Telephone Number	Date	

This form contains information relating to employee health and must be used in a manner that protects the confidentiality of the employee to the extent possible while the information is being used for occupational safety and health purposes.



<u>INSTRUCTIONS:</u> Complete all sections below for incidents involving property/equipment damage, fire, spill or release. Do NOT leave any blanks. Attach this form to the IR FORM completed for this incident.						
Incident Report Number: (Fr	Incident Report Number: (From the IR Form)					
	ТҮРЕ	OF INCIDENT (Check all th	at apply)		
Property Damage	Equipment Da	amage	Fire or Exp	losion	Spill or Relea	se 🗌
		INCIDENT	DETAILS		•	
Results of Incident: Fully des	scribe damages, loss	ses, etc.				
Response Actions Taken:						
•						
Responding Agency(s) (i.e.	police, fire departm	ent, etc.)	Agency(s) Co	ntact Name(s)		
						2
'	EMS (List all da		extent of dar			ost)
Item:	EX	tent of damage:		Estimated	repair cost	
SPILL	S / RELEASES ((Provide inform	nation for sp	illed/released r	naterials)	
Substance	Estimated quantit			eportable Quantity		
				Exceed	ded? Yes No	o 🗌 NA 🗍
FIRES / EXPLOSIONS (Provide information related to fires/explosions)						
Fire fighting equipment used? Yes No If yes, type of equipment:						
NOTIFICATIONS						
Required notifications		Name of person		By whom	[Date / Time
Client:	Yes No					
Agency:	Yes No					
Other:	Yes No No					
Who is responsible for reporting	ng incident to outside	agency(s)? Tt	Client	Other Name:		
Was an additional written repo	ort on this incident ge	nerated? Yes	No If	yes, place in project	file.	





INSTRUCTIONS:

Complete all sections below for incidents involving motor vehicle accidents. Do NOT leave any blanks. Attach this form to the IR FORM completed for this incident.				
Incident Report Numb	per: (From the IR Form	1)		
		INCIDENT	DETAILS	
Name of road, stre occurred	et, highway or loca	tion where accident	Name of intersectin	g road, street or highway if applicable
County		City		State
Did police respond to	the accident?		Did ambulance respo	ond to the accident?
	Yes	□ No □		Yes 🗌 No 🗌
Name and location of	responding police de	partment	Ambulance company	y name and location
Officer's name/badge	#		•	
Did police complete an Request a copy of com		No If yes, poort and attach to this for	olice report number: m.	
	,		FORMATION	
How many vehicles were involved in the accident? (Attach additional sheets as applicable for accidents involving more than 2 vehicles.)				eets as applicable for accidents involving more
Vehicle Number 1 – T	etra Tech Vehicle		Vehicle Number 2 – 0	Other Vehicle
Vehicle Owner / Contact Information			Vehicle Owner / Contact Information	
Color			Color	
Make			Make	
Model			Model	
Year			Year	
License Plate #			License Plate #	
Identification #			Identification #	
Describe damage to v	vehicle number 1		Describe damage to	vehicle number 2
Insurance Company	Name and Address		Insurance Company	Name and Address
Agent Name			Agent Name	
Agent Phone No.			Agent Phone No.	
Policy Number			Policy Number	

TETRA TECH, INC. INCIDENT FORM IR-C

DRIVER INFORMATION									
Vehicle	Number 1 – T	etra Tech V	ehicle		Vehicle Number 2	- Other Vehicle			
Driver's	s Name				Driver's Name				
Driver's	s Address				Driver's Address				
Phone	Number				Phone Number				
Date of	Birth				Date of Birth				
Driver's	s License #				Driver's License #				
Licensi	ng State				Licensing State				
Gender	,	Male	Female		Gender	Male Female	e 🗌		
Was tra	ffic citation issu	ed to Tetra T	ech driver?	Yes No	Was traffic citation is	ssued to driver of other	vehicle? Yes No		
Citation	ı #				Citation #				
Citation					Citation Description				
			PASSI	ENGERS IN VEH	IICLES (NON-INJ	URED)			
List all non-injured passengers (excluding driver) in each vehicle. Driver information is captured in the preceding section. Information related to persons injured in the accident (non-Tt employees) is captured in the section below on this form. Injured Tt employee information is captured on FORM IR-A									
Vehicle	Number 1 – T	etra Tech Vo	ehicle		Vehicle Number 2	Vehicle Number 2 – Other Vehicle			
How ma	any passengers	(excluding o	Iriver) in the	vehicle?	How many passeng	How many passengers (excluding driver) in the vehicle?			
Non-Inj Passen and Ad	ger Name			Non-Injured Passenger Name and Address					
Non-Inj Passen and Ad	ger Name				Non-Injured Passenger Name and Address				
Non-Inj Passen and Ad	ger Name				Non-Injured Passenger Name and Address				
			INJUR	IES TO NON-TE	TRATECH EMPL	OYEES			
Name o	of injured perso	on 1			Address of injured person 1				
Age	Gender		Car No.	Location in Car	Seat Belt Used?	Ejected from car?	Injury or Fatality?		
	Male Fe	emale			Yes No	Yes No No	Injured Died		
Name o	of injured person	on 2			Address of injured person 2				
Age Gender Car No. Location in Car		Seat Belt Used?	Ejected from car?	Injury or Fatality?					
	Male Female		Yes No No	Yes No	Injured Died D				
				OTHER PROP	ERTY DAMAGE				
Describ	Describe damage to property other than motor vehicles								
Propert	y Owner's Nar	me			Property Owner's	Address			



COMPLETE AND SUBMIT DIAGRAM DEPICTING WHAT HAPPENED

ATTACHMENT III MEDICAL DATA SHEET

MEDICAL DATA SHEET

This Medical Data Sheet must be completed by on-site personnel and kept in the command post during the conduct of site operations. This data sheet will accompany any personnel when medical assistance is needed or if transport to hospital facilities is required.

Project _				
Name _			Home Telephone _	
Address _				
Age	Height		Weight	
Person to notify in	the event of an emergency:	Name:	_	
Drug or other Alle	rgies:			
Particular Sensitiv	rities :			
Do You Wear Cor	ntacts?			
What medications	are you presently using?			
Name, Address, a	and Phone Number of persona	l physician:		
Note: Health In	surance Portability and Acc	ountability Act ((HIPAA) Requirements	
Information (PHI) as that you may r also requires Tetr Data Sheet to cor So before you co secure location. It	April 14, 2003. Loosely interpose the entity collecting that infeport on this Medical Data Shata Tech to ensure the confideration and convey information younglete the Medical Data Shata will be maintained in a file be company an injured party to	ormation. PHI is a eet), provision of otiality of PHI. Thi ou would want a eet understand the ox or binder acce	any information about hea health care, or other infolis is Act can affect the ability Doctor to know if you were hat this form will not be r	of the Medical ending in a maintained in a maintained in a maintained in a
	information that you do not wi situation or treatment.	sh others to know	w, only information that m	ay be pertinent
Name (Print clear		Signature		Date

ATTACHMENT IV SAFE WORK PERMITS

SAFE WORK PERMIT SITE MOBILIZATION AND DEMOBILIZATION ACTIVITIES LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	No Date:	Time: From	to
l.	Work limited to the following (description activities	, area, equipment used):	Mobilization and demobilization
II.	Primary Hazards: Lifting; slips, trips and fall	lls: vehicular and foot traffic	: insect/animal bites and stings:
	poisonous plants; inclement weather.	,	, moodamma siec and chings,
III.	Field Crew:		
IV.	On-site Inspection conducted Yes	☐ No Initials of Inspe	ctorTetra Tech
	Equipment Inspection required Yes	☐ No Initials of Inspe	ctorTetra Tech
٧.	Protective equipment required	Respiratory equipment	t required
	Level D 🖾 Level B 🗌		on the reverse
	Level C 🔲 Level A 🗍	No 🖾	
	Modifications/Exceptions: Minimum requirement	ent include sleeved shirt and	d long pants, or coveralls, safety,
	glasses and safety footwear. Hard hats and		
	equipment.		
VI.	Chemicals of Concern Hazard Monitori	ng / Action Level(s)	Response Measures
	None anticipated None		None
	Primary Route(s) of Exposure/Hazard: N	IA	
	(Note to FOL and/or SHSO: Each item in Se	ctions VII, VIII, and IX must	be checked Yes, No, or NA)
VII.	Additional Safety Equipment/Procedures		
	Hard-hat ☐ Yes ☐ No		n (Plugs/Muffs) ☐ Yes ☐ No
	Safety Glasses Yes No		ss ☐ Yes 🖾 No
	Chemical/splash goggles 🔲 Yes 🔯 No		one ☐ Yes 🗵 No
	Splash Shield 🔲 Yes 🔯 No	o Barricades	☐ Yes ⊠ No
	Splash suits/coveralls Yes 🗵 No		Work) Yes ☐ No
	Impermeable apron 🔲 Yes 🖾 No		n Yes 🛛 No
	Steel toe work shoes/boots		int Boot Covers Yes No
	High visibility vest Yes No	D lape up/use inse	ct repellent Yes No
	First Aid Kit		Yes No
	Safety Shower/Eyewash		Yes No
	Modifications/Exceptions: Tyvek coverall to through areas of high grass. Use insect repell		
	Follow manufacturer's recommendations for p		
	hazards exist. Safety glasses when near eye l		
	nazaras exist. Oarety glasses when hear eye i	lazaras: Flearing protection	when in riigh hoise areas.
VIII.	Site Preparation		Yes No NA
v	Utility Locating and Excavation Clearance com	inleted	
	Vehicle and Foot Traffic Routes Established/Tr		
	Physical Hazards Identified and Isolated (Splan		
	Emergency Equipment Staged (Spill control, fi		
IX.			
	If yes, SHSO to complete or contact Health Sc		
X.			
	falls, natural hazards, etc.) Review PPE nee		
	hazards. Use safe lifting procedures and o		
	Suspend site activities in the event of incleme		
	heat/cold stress. Use sun block (SPF > 15) to		
Permit I	Issued by:	Permit Accepted by	<i>r</i> :
	- , .		

SAFE WORK PERMIT SITE CONCRETE CORING OPERATIONS LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit I	iit No Date:	Time: From	to
I.	. Work limited to the following (description, area, equipment used):	Concrete co	ring will take place in some areas
•	of the complex. This activity will employ an electrical coring machine wi		
	This activity will also include: Installation of soil gas monitoring poir		
		its, coming bor	enoie restoration and protective
	casing installation.		
II.			
	systems/utilities; electrical shock; heavy lifting; slip, trip and fall; cuts a	and lacerations	s; vehicular and foot traffic; flying
	projectiles.		
III.			
IV.		of Inspector	Tetra Tech
		of Inspector	Tetra Tech
٧.	. Protective equipment required Respiratory equipment	nent required	
	Level D ☐ Level B ☐ Yes ☐ Spec	cify on the reve	erse
	Level C 🗌 Level A 🗍 No 🔯 ்	,	
	Modifications/Exceptions:		
1/1		1/->	D
VI.			Response Measures
	<u>Dust (Concrete)</u> <u>Visual –Visible dust</u> >2 mg/m3	<u>3 Er</u>	mploy dust suppression –Wet it down
	Primary Route(s) of Exposure/Hazard: Airborne concentrations of	VOCs are no	t anticipated during this activity.
	Sand, bentonite, grout may cause mechanical irritation (eyes) as well		
	mucous membrane irritation.		
	(Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX mu	ist be shocke	d Voc. No. or NA\
		ist be checked	u res, No, or NA)
VII.			
	Hard-hat ☐ Yes ☐ No Hearing Prote	ection (Plugs/M	luffs)⊠ Yes 🔲 No
	Safety Glasses	arness	🗌 Yes 🛛 No
		r Phone	Yes No
			X Yes No
			Yes 🛚 No
			ers 🔲 Yes 🔲 No
	High visibility vest	insect repellen	t ☐ Yes 🛛 No
	First Aid Kit	her	Yes 🗌 No
	Modifications/Exceptions: Coveralls if the potential for soiling work of		
	the SSO based on conditions (rain gear, rubber boots, etc.)	Journing Exists.	Other I I E may be specified by
VIII.			Yes No NA
	Utility Locating and Excavation Clearance completed		
	Vehicle and Foot Traffic Routes Established/Traffic Control Barricades/	Signs in Place	
	Physical Hazards Identified and Isolated (Splash and containment barri	iers)	
	Emergency Equipment Staged (Spill control, fire extinguishers, first aid		
	Emorgano) Equipmont etagea (epin control, inc examgatoriole, met ala	1410, 010,1111111	
137	W. A. Lifeta and Branches and Control of the Contro		
	X. Additional Permits required (Hot work, confined space entry, excavat		
If yes,	s, SSO to complete or contact Health Sciences, Pittsburgh Office (41	12)921-7090 (I	Excavation/Penetration Permit is
Require	uired)		
Χ.	X. Special instructions, precautions: Ensure all equipment is pover	wered through	a GECL to prevent possible
7	electrocution hazards. Ensure the coring unit is stable and secured to p		
	collected using a shop vac or similar device for wet applications. This		
	Inspect the unit before use Ensure wiring, casing, and guards are not d	tamaged and t	he unit is suitable for use. As this
	activity may occur at night Ensure lighting within the work area is adequ	<u>uate. Use barri</u>	cades, signs, temporary diking to
	control water spread during coring operations. Place signs and barricad		
	not leave any core holes open and unattended. Ensure all protective of		
	existing grade. Heavy Equipment Inspection Checklist must be complet		
	existing grade. Heavy Equipment inspection offection must be complete	rea buoi io neg	mining work.
Permit I	nit Issued by: Permit Accepte	ed by:	

SAFE WORK PERMIT SITE GEOPHYSICAL/GEOGRAPHIC LAND SURVEYING LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	No Date:	Time: From	to
I.	Work limited to the following (description, area, geographical.		
II.	Primary Hazards: Potential hazards associated with		ar and foot traffic; temperature
	extremes; inclement weather; insect /animal bites or	stings, poisonous plants, etc.	
III.	Field Crew:		
IV.	On-site Inspection conducted Yes No	Initials of Inspector	Tetra Tech
	Equipment Inspection required Yes No	Initials of Inspector	Tetra Tech
V.	Protective equipment required Re Level D \(\subseteq \text{Level B} \subseteq \text{Level B} \subseteq \text{Level A} \subseteq \text{Modifications/Exceptions:} \(\subseteq \text{Level A} \subs	espiratory equipment required Yes ☐ Specify on the revers No ☑	
<u>N</u>	Chemicals of Concern lone expected during this ask Hazard Monitoring NA	Action Level(s) NA	Response Measures NA
Pr	imary Route(s) of Exposure/Hazard:		
VII.	(Note to FOL and/or SSO: Each item in Sections V Additional Safety Equipment/Procedures Hard-hat	Hearing Protection (Plugs/Muf Safety belt/harness	fs)
VIII.	Site Preparation Utility Locating and Excavation Clearance completed Vehicle and Foot Traffic Routes Established/Traffic Co Physical Hazards Identified and Isolated (Splash and Emergency Equipment Staged (Spill control, fire extin	ontrol Barricades/Signs in Place containment barriers)	
IX.	Additional Permits required (Hot work, confined spa If yes, SSO to complete or contact Health Sciences, F		Yes 🛛 No
х.	Special instructions, precautions: Suspend activities	es in the event of inclement weather	er.
Permit I	ssued by:	Permit Accepted by:	

SAFE WORK PERMIT BLOCK D SOIL BORING AND MONITORING/DEEP WELL INSTALLATION LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit			: From to
I.		description, area, equipment used): Soil	
		rmed using DPT and HSA Rigs, while the m	
		nent and the installation of vapor monitoring	ig points and installation of membrane
	interface probes.		
II.		ransfer of site contaminants; heavy equipm	
		o, trip and fall; cuts and lacerations; vehicula	
		/animal bites and stings, poisonous plants,	inclement weather, drowning.
III.	Field Crew:		
IV.	On-site Inspection conducted		ctorTetra Tech
	Equipment Inspection required	Yes No Initials of Inspec	ctorTetra Tech
	Data di cara d	D	
V.	Protective equipment required		
	Level D 🖾 Level B 🗌	Yes ☐ Specify on No ☒	the reverse
	Level C Level A Medifications/Exportions:	No 🛛	
\/I C	Modifications/Exceptions:	d Anti-ma	
	Chemicals of Concern (COCs) an		Desmanas Massauras
COCs	Hazard Monitoring PID (except on boat/barge)	Action Level(s) >1.00 ppm in BZ sustained 4 exp of 5 minutes	Response Measures Screen BZ with Draeger tubes
VOCs Benzene		Up to 5 ppm/sustained 10 minutes/4 times/day	
Dust		>2 mg/m3	Employ dust suppression –Wet it down
	Route(s) of Exposure/Hazard	Inhalation, ingestion and skin contact. Con	trols include monitoring instrument use
		afe work practices. VOCs – irritating at all	
		nely high concentrations may result in Irregi	
		nical irritation (eyes) as well as potential alk	
	ane irritation.	modification (eyee) de wen de peterniar and	an barrio, respiratory, eye, and muceue
_			
Note	to FOL and/or SSO: Each item i	n Sections VII, VIII, and IX must be check	ed Yes, No, or NA)
	Additional Safety Equipment/Pr		•
	Hard-hat		Plugs/Muffs) ⊠ Yes □ No
	Safety Glasses		🗌 Yes 🔀 No
	Chemical/splash goggles[e 🗌 Yes 🔲 No
	Splash shield		Yes 🔲 No
	Splash suits/coveralls		le/work) ⊠ Yes 🔲 No
	Impermeable apron		Yes 🔲 No
	Steel toe work shoes or boots	⊴Yes	oot covers
	High visibility vest	☑Yes ☑ No Tape up/use insect	repellent 🔲 Yes 🔲 No
	First Aid Kit		Yes No
	Safety Shower/Eyewash[☐ Yes ☐ No
		eralls if the potential for soiling work clothin	g exists. Other PPE is possible based
	on conditions (rain gear, rubber b	oots, etc.)	
VIII.	Site Preparation		Yes No NA
		earance completed	
		stablished/Traffic Control Barricades/Signs i	
		solated (Splash and containment barriers)	
	Emergency Equipment Staged (S	pill control, fire extinguishers, first aid kits, et	c)
		t work, confined space entry, excavation etc	
If yes, S		Sciences, Pittsburgh Office (412)921-7090 (L	
Χ.		ns: Any sustained VOC readings in worker	
	requiring that site activities be s	uspended. Use safe lifting/carrying techni-	ques. Inspect equipment prior to use.
		are functional and test daily. Minimize cont	
		e contaminated. Use waterless hand cleane	
		oer hands washing facilities on shore can be	reached. Heavy Equipment Inspection
	Checklist must be completed prio	to beginning work.	
-			
Permit I	ssued by:	Permit Accepted by:	

SAFE WORK PERMIT BLOCK E AND G SOIL BORING AND MONITORING/DEEP WELL INSTALLATION LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	lo. Date:	Time: Fi	rom to
I.	Soil boring will generally be perform	escription, area, equipment used): Soil boned using DPT and HSA Rigs, while the monitent and the installation of vapor monitoring parts.	toring wells will be installed via HSA.
II.	Primary Hazards: Contact and tra	nsfer of site contaminants; heavy equipment	hazards; elevated noise; energized
	systems/utilities; heavy lifting; slip,	trip and fall; cuts and lacerations; vehicular a	nd foot traffic; ambient temperature
		nimal bites and stings, poisonous plants, incl	ement weather, drowning.
III.	Field Crew:		
IV.		☐ Yes ☐ No Initials of Inspector	Tetra Tech
	Equipment Inspection required	☐ Yes ☐ No Initials of Inspector	Tetra Tech
V.	Protective equipment required	Respiratory equipment requ	ired
	Level D 🔯 Level B 🗌	Yes ☐ Specify on the	
	Level C 🔲 Level A 🗍	No 🖾	
	Modifications/Exceptions:	_	
VI.C	hemicals of Concern (COCs) and	Actions	
COCs	Hazard Monitoring	Action Level(s)	Response Measures
VOCs		>7.00 ppm in BZ sustained 4 exp of 5 minutes	Screen BZ with Draeger tubes
Benzene	Draeger Tube 0.5/a	Jp to 5 ppm/sustained 10 minutes/4 times/day	Evacuate site till background levels return
Dust		>2 mg/m3	Employ dust suppression –Wet it down
Primary	Route(s) of Exposure/Hazard: In	halation, ingestion and skin contact. Control	s include monitoring instrument use,
		e work practices. VOCs - irritating at all poi	
vision, n	arcotic effects, dizziness); Extreme	ly high concentrations may result in Irregular	heartbeats, possible cardiac arrest.
Sand, be	entonite, grout may cause mechanic	cal irritation (eyes) as well as potential alkali	burns; respiratory, eye, and mucous
membra	ne irritation.		<u> </u>
Note	to FOL and/or SSO: Each item in	Sections VII, VIII, and IX must be checked '	Yes, No, or NA)
VII.	Additional Safety Equipment/Pro	cedures	
	Hard-hat	Yes ☐ No Safety belt/harness Yes ☐ No Radio/Cellular Phone	gs/Muffs)
	Splash shield		<u> </u>
	Splash suits/coveralls	Yes ☐ No Gloves (Type – nitrile/v	
	Impermeable apron		
	Steel toe work shoes or boots		
	High visibility vest	Yes No Tape up/use insect repo	ellent
	First Aid Kit	Yes No Fire extinguisher	Yes No
	Safety Shower/Eyewash		Yes No
		alls if the potential for soiling work clothing e	xists. Other PPE is possible based
	on conditions (rain gear, rubber boo	ots, etc.)	
VIII.	Site Preparation		Yes No NA
		arance completed	
		ablished/Traffic Control Barricades/Signs in P	
	Physical Hazards Identified and Iso	lated (Splash and containment barriers)	
	Emergency Equipment Staged (Spi	Il control, fire extinguishers, first aid kits, etc)	
IX.	Additional Permits required (Hot	work, confined space entry, excavation etc.)	Yes No
If yes, S	SO to complete or contact Health So	ciences, Pittsburgh Office (412)921-7090 (Exc	avation Permit is Required)
Χ.		: Any sustained VOC readings in worker BZs	
		spended. Use safe lifting/carrying technique	
		e functional and test daily. Minimize contact	
		contaminated. Use waterless hand cleaner pr	
		er hands washing facilities on shore can be rea	ached. Heavy Equipment Inspection
	Checklist must be completed prior t	o beginning work.	
Permit Is	ssued by:	Permit Accepted by:	

SAFE WORK PERMIT BLOCK F SOIL BORING AND MONITORING/DEEP WELL INSTALLATION LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	No. Date:		Time: Fro	om	to
I.	Work limited to the following (d Soil boring will generally be perform This task includes well development	ned using DPT and HSA	Rigs, while the monito	oring wells will be ins	stalled via HSA.
II. III.	interface probes. Primary Hazards: Contact and trassystems/utilities; heavy lifting; slip, extremes; flying projectiles; insect/a Field Crew:	trip and fall; cuts and la	cerations; vehicular an	d foot traffic; ambie	nt temperature
IV.	On-site Inspection conducted Equipment Inspection required		nitials of Inspector nitials of Inspector		
V.	Protective equipment required Level D ☐ Level B ☐ Level C ☐ Level A ☐ Modifications/Exceptions:	Yes No	tory equipment requi ☐ Specify on the r		
	chemicals of Concern (COCs) and				
VOCs Benzene Dust	Hazard Monitoring PID (except on boat/barge) Draeger Tube 0.5/a Visual –Visible dust Route(s) of Exposure/Hazard: In	Action Level(s) >1,000 ppm in BZ susta Up to 5 ppm/sustained 1 >2 mg/m3	0 minutes/4 times/day	Employ dust supp	raeger tubes background levels return bression –Wet it down
	ntrol, use of PPE, and following saf				
vision, r	narcotic effects, dizziness); Extreme	ely high concentrations r	nay result in Irregular	heartbeats, possible	cardiac arrest.
	entonite, grout may cause mechani	cal irritation (eyes) as w	<u>ell as potential alkali b</u>	urns; respiratory, ey	e, and mucous
membra	ne irritation.				
	to FOL and/or SSO: Each item in Additional Safety Equipment/Pro	cedures		•	
	Hard-hat		earing Protection (Plug		
	Safety Glasses Chemical/splash goggles		afety belt/harness adio/Cellular Phone		
	Splash shield		arricades		
	Splash suits/coveralls	Yes □ No G	loves (Type - nitrile/w	ork) 🔯 Yes	□ No
	Impermeable apron	∣Yes ⊠ No W	ork/rest regimen		
	Steel toe work shoes or boots	Yes No C	hemical resistant boot	covers Yes	□ No
	High visibility vest	Yes ∐ No Ia	ape up/use insect repe	llent ∐ Yes	∐ No
	Safety Shower/Eyewash	· <u> </u>	re extinguisherther		
	Modifications/Exceptions: Cove				
	on conditions (rain gear, rubber bo				
VIII.	Site Preparation			Yes No	NA
	Utility Locating and Excavation Cle				
	Vehicle and Foot Traffic Routes Es				
	Physical Hazards Identified and Iso				\vdash
— IV	Emergency Equipment Staged (Sp Additional Permits required (Hot				 □ No
	SSO to complete or contact Health S				_
<u>п уса, с</u> Х.					
Λ.	requiring that site activities be su				
	Ensure emergency stop devices a	e functional and test dai	ly. Minimize contact v	with potentially conta	aminated media
	and assume soils/groundwater are				
	after sampling until access to prope		es on shore can be rea	ched. Heavy Equipr	nent Inspection
	Checklist must be completed prior	o beginning work.			
Permit Is	ssued by:	Permit Accept	ed by:		

SAFE WORK PERMIT Block H SOIL BORING AND MONITORING/DEEP WELL INSTALLATION LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	No. Date:	Time: From	m to
I.	Soil boring will generally be perform	scription, area, equipment used): Soil boring ed using DPT and HSA Rigs, while the monitor and the installation of vapor monitoring points.	ing wells will be installed via HSA.
II. 	interface probes. Primary Hazards: Contact and trasystems/utilities; heavy lifting; slip, extremes; flying projectiles; insect/a	nsfer of site contaminants; heavy equipment hirip and fall; cuts and lacerations; vehicular and himal bites and stings, poisonous plants, inclen	azards; elevated noise; energized I foot traffic; ambient_temperature
III. IV.	Field Crew: On-site Inspection conducted Equipment Inspection required	Yes No Initials of Inspector No Initials of Inspector	Tetra Tech Tetra Tech
V.	Protective equipment required Level D ☐ Level B ☐ Level C ☐ Level A ☐ Modifications/Exceptions:	Respiratory equipment require Yes ☐ Specify on the re No ☐	
VI.C	chemicals of Concern (COCs) and	Actions	
VOCs Benzene Dust	<u>Draeger Tube 0.5/a</u> L	Action Level(s) >10.00 ppm in BZ sustained 4 exp of 5 minutes p to 5 ppm/sustained 10 minutes/4 times/day 2 mg/m3	Response Measures Screen BZ with Draeger tubes Evacuate site till background levels return Employ dust suppression –Wet it down
		nalation, ingestion and skin contact. Controls i	
		work practices. VOCs - irritating at all points	
vision, r	narcotic effects, dizziness); Extreme	y high concentrations may result in Irregular h	eartbeats, possible cardiac arrest.
		al irritation (eyes) as well as potential alkali bu	rns; respiratory, eye, and mucous
membra	ne irritation.		
VII.	Additional Safety Equipment/Prod Hard-hat	Yes ☐ No Hearing Protection (Plugs Yes ☐ No Safety belt/harness	/Muffs)
	Utility Locating and Excavation Cleavehicle and Foot Traffic Routes Est Physical Hazards Identified and Isol	rance completed ablished/Traffic Control Barricades/Signs in Plac ated (Splash and containment barriers) control, fire extinguishers, first aid kits, etc)	
	Additional Permits required (Hot v	vork, confined space entry, excavation etc.)	Yes No
		iences, Pittsburgh Office (412)921-7090 (Excav	
Х.	requiring that site activities be sus Ensure emergency stop devices are and assume soils/groundwater are	Any sustained VOC readings in worker BZs in pended. Use safe lifting/carrying techniques. In functional and test daily. Minimize contact work work washing facilities on shore can be react beginning work.	Inspect equipment prior to use. ith potentially contaminated media ducts or disinfecting wipes on boat
Permit Is	ssued by:	Permit Accepted by:	

SAFE WORK PERMIT MARINE OPERATIONS (FROM WATER VESSEL) LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	lo Date:	Time	e: From	to
I.	Work limited to the following (description, are samples. These sampling activities will be conduct from a barge will be part of this activity.			
II. 	Primary Hazards: Drowning. Suspend activities in electrical storms). Other hazards could include, sm Field Crew:			
III.	rieid Crew:			
IV.	• = =	lo Initials of Inspe-		
V. 	Protective equipment required Level D Level B Level C Level A Modifications/Exceptions: Coast Guard approved	Respiratory equipment Yes	n the reverse	
COC's VOCs Benzene	PID (except on boat/barge) >1.75 ppm in B. Draeger Tube 0.5/a Up to 5 ppm/sus	on Level(s) Z sustained 4 exp of 5 ministained 10 minutes/4 times/	Stop site activity levels return to n	Oraeger tubes until background
Prima	ry Route(s) of Exposure/Hazard: incidental inc (Note to FOL and/or SSO: Each item in Sections	estion, direct contact with		•
VII.	Additional Safety Equipment/Procedures Hard-hat	Hearing Protection Safety belt/harness Radio/Cellular Pho Barricades Gloves (Type – Wo Work/rest regimen Chemical Resistan Tape up/use insect Fire Extinguisher Other	(Plugs/Muffs) Yes S	No N
VIII.	Site Preparation Utility Locating and Excavation Clearance complete Vehicle and Foot Traffic Routes Established/Traffic Physical Hazards Identified and Isolated (Splash ar Emergency Equipment Staged (Spill control, fire ex	Control Barricades/Signs of containment barriers).	s in Place	NA ⊠ □
IX.	Additional Permits required (Hot work, confined s If yes, SSO to complete or contact Health Sciences			⊠ No
X.	Special instructions, precautions: Minimize co. Wash hands before performing any hand-to-mouth wipes on boat after sampling until access to prextinguisher and first aid kit to be maintained on by vessel requirements including PFDs, fire extinguisher contents of the cont	n activities. Use waterle oper hands washing fac- poat at all times. The bo- uishers, and visual distr	ess hand cleaner products cilities on shore can be at employed will meet the ess signals. Complete	s or disinfecting reached. Fire minimum safe Boating Safety
Permit Is	ssued by:	Permit Accepted by:		

SAFE WORK PERMIT Block D MULTI MEDIA SAMPLING AND WELL DEVELOPMENT LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	No Date:		Time: From	n to
I.	Work limited to the following (des			
	subsurface soils, groundwater, storn	<u>n water, IDW. This t</u>	<u>ask also includes soil vapo</u>	or sampling and indoor air quality
	sampling. Primary Hazards: Contact with site of		r of contemination: hogy	lifting: alia trip and fall: auto and
	lacerations; vehicular and foot traff			
	plants, inclement weather.	no, ambient tempera	ture extremes, msectrami	mai bites and stings, poisonous
III.	Field Crew:			
IV.	On-site Inspection conducted	☐ Yes ☐ No	Initials of Inspector	Tetra Tech
	Equipment Inspection required	☐ Yes ☐ No	Initials of Inspector	Tetra Tech
	V. Protective equi	pment required	Respiratory equip	oment required
	Level D 🛛 Level B 🗌	Ye		verse
	Level C 🗌 Level A 🗌	No	oxdot	
	Modifications/Exceptions:			
VI.	Chemicals of Concern (COCs) and			
OCs	Hazard Monitoring	Action Level(s)		Response Measures
<u>DCs</u>	PID (except on boat/barge) Draeger Tube 0.5/a	>1.00 ppm in BZ su	stained 4 exp of 5 minutes ed 10 minutes/4 times/day	Screen BZ with Draeger tubes Evacuate site till background levels r
<u>nzene</u> Ist	Visual –Visible dust	>2 mg/m3	ed 10 minutes/4 times/day	Employ dust suppression –Wet it do
<u> </u>	viodai viololo duot	- = mg/mo		Employ addit supplession With the
st co	mponents may include metals, PCBs, I	PAHs, sand, grout. Er	countering airborne conce	entrations above background levels
	reathing zone (BZ) during this activity			
	packground levels at least daily.	•		
	Route(s) of Exposure/Hazard: Inh			
	(Note to FOL and/or SSO: Each ite	m in Sections VII, V	III, and IX must be check	ed Yes, No, or NA)
VII.			D /DL /	M (()
	Hard-hat		Hearing Protection (Plugs/ Safety Belt/Harness	
	Safety Glasses		Radio/Cellular Phone	
	Splash Shield		Barricades	
	Splash Suits/Coveralls	Yes ☐ No	Gloves (Type – Nitrile)	
	Impermeable Apron	Yes ⊠ No	Work/rest regimen	
	Steel Toe Work Shoes or Boots. X	Yes 🗌 No	Chemical Resistant Boot C	Covers 🗌 Yes 🔯 No
	High Visibility Vest	Yes ☐ No	Tape/Insect Repellent	Yes No
	First Aid Kit		Fire Extinguisher	
	Safety Shower/Eyewash	Yes ☐ No	Other	Yes No
	Modifications/Exceptions:			
VIII.	Site Preparation			Yes No NA
	Utility Locating and Excavation Clear			
	Vehicle and Foot Traffic Routes Esta			
	Physical Hazards Identified and Isola Emergency Equipment Staged (Spill			
ΙΥ	Additional Permits required (Hot w			
ıA.	If yes, SSO to complete or contact H			
Х.				
- **	readings in worker breathing zones			
	suspended until the source of elevat			
	is contaminated and avoid contact th			
	may occur at night Ensure lighting w	ithin the work area ar	e at least 5 foot candles. I	Prior to placing Summa Canisters
	ventilate indoor area if elevated read	<u>lings (>10 ppm) are ε</u>	ncountered upon entering	building to achieve readings less
	than 10 ppm.			
ermit I	ssued by:	P(ermit Accepted by:	

SAFE WORK PERMIT BLOCK E AND G MULTI MEDIA SAMPLING AND WELL DEVELOPMENT LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Cs PID (except on boat/barge) >7.00 ppm in BZ sustained 4 exp of 5 minutes Screen BZ with Draeger tubes evacuate site till background levels results.	ermit N	No Date:		Time: Fro	om to
subsurface soils, groundwater, storm water, IDW. This task also includes soil vapor sampling and indoor air quality sampling. II. Primary Hazards: Contact with site contaminants, transfer of contamination; heavy lifting, slip, trip and fall; cuts and lacerations; vehicular and foot traffic; ambient temperature extremes; insectanimal bites and stings, poisonous plants, inclement weather. III. Field Crew: V. On-site Inspection conducted					
Sampling. Primary Hazards: Contact with site contaminants; transfer of contamination; heavy lifting, slip, trip and fall; cuts and lacerations; vehicular and foot traffic; ambient temperature extremes; insect/animal bites and stings, poisonous plants, inclement weather.	I.				
II. Primary Hazards: Contact with site contaminants; transfer of contamination, heavy lifting; slip, trip and fall; cuts and lacerations; vehicular and foot traffic: ambient temperature extremes; insect/animal bites and stings, poisonous plants, inclement weather.			torm water, IDW. This	task also includes soil va	por sampling and indoor air quality
lacerations; vehicular and foot traffic: ambient temperature extremes: insect/animal bites and stings, poisonous plants, inclement weather. III. Field Crew:			 		
	II.				
III. Field Crew: V. On-site Inspection conducted Yes No Initials of Inspector Tetra Tech V. On-site Inspection required Yes No Initials of Inspector Tetra Tech V. On-site Inspection required Yes No Initials of Inspector Tetra Tech V. Chevil D Level B West No Specify on the reverse V. Level D Level B Specify on the reverse Yes Specify on the reverse Modifications Exceptions Exceptions Action Level(s) Specify on the reverse No North of		lacerations; vehicular and foot t	traffic; ambient temper	<u>rature extremes; insect/ai</u>	nimal bites and stings, poisonous
V. On-site Inspection conducted Yes No Initials of Inspector Tetra Tech Tetra Tech Equipment Inspection required Yes No Initials of Inspector Tetra Tech Tetra Tech V. Protective equipment required Yes Specify on the reverse Specify on					
Equipment inspection required				laitiala af la anastan	Tatas Task
V.	IV.				
Level D		<u> </u>		<u> </u>	
Level C					
Modifications/Exceptions: VI. Chemicals of Concern (COCs) and Actions Action Level(s)					everse
VI. Chemicals of Concern (COCs) and Action Level(s) Cs		_	ľ	No 🗵	
Cs PLIC (except on boat/barge)					
PID (except on boat/barge) PID (except on					_
Dager Tube 0.5/a Visual –Visible dust 22 mg/m3 Evacuate site till background levels re Employ dust suppression –Wet it dow st components may include metals, PCBs, PAHs, sand, grout. Encountering airborne concentrations above background levels he breathing zone (B2) during this activity is not anticipated based on historical source concentrations. SSO to take and ord background levels at least daily. mary Route(s) of Exposure/Hazard: Inhalation, ingestion and skin contact. Controls include monitoring instrument use, et control, use of PPE, and following safe work practices. VOCs – irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness): Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, d. bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA)	OCs				
st components may include metals, PCBs, PAHs, sand, grout. Encountering airborne concentrations above background levels he breathing zone (BZ) during this activity is not anticipated based on historical source concentrations. SSO to take and ord background levels at least daily. mary Route(s) of Exposure/Hazard: Inhalation, ingestion and skin contact. Controls include monitoring instrument use, at control, use of PPE, and following safe work practices. VOCs – irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness). Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, d., bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) VII. Additional Safety Equipment/Procedures Hard-hat.	<u>OCs</u>				
st components may include metals. PCBs. PAHs, sand, grout. Encountering airborne concentrations above background levels he breathing zone (BZ) during this activity is not anticipated based on historical source concentrations. SSO to take and ord background levels at least daily. Mary Route(s) of Exposure/Hazard:				110 minutes/4 times/day	
he breathing zone (BZ) during this activity is not anticipated based on historical source concentrations. SSO to take and ord background levels at least daily. mary Route(s) of Exposure/Hazard: Inhalation, ingestion and skin contact. Controls include monitoring instrument use, at control, use of PPE, and following safe work practices. VOCs – irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness): Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, dt, bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane Irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) VII. Additional Safety Equipment/Procedures Hard-hat	ıst	visuai –visibie dust	>2 mg/m3		Employ dust suppression –vvet it dow
he breathing zone (BZ) during this activity is not anticipated based on historical source concentrations. SSO to take and ord background levels at least daily. mary Route(s) of Exposure/Hazard: Inhalation, ingestion and skin contact. Controls include monitoring instrument use, at control, use of PPE, and following safe work practices. VOCs – irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness): Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, dt, bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane Irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) VII. Additional Safety Equipment/Procedures Hard-hat	ict co	mnonanta may inaluda matala DCE	Do DALlo cond grout [Encountaring airbarna agn	contrations above background levels
mary Route(s) of Exposure/Hazard: Inhalation, ingestion and skin contact. Controls include monitoring instrument use, at control, use of PPE, and following safe work practices. VOCs — irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness): Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, ad, bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane Irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) VII. Additional Safety Equipment/Procedures Hard-hat					
mary Route(s) of Exposure/Hazard: Inhalation, ingestion and skin contact. Controls include monitoring instrument use, at control, use of PPE, and following safe work practices. VOCs – irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness): Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, and, bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) VII. Additional Safety Equipment/Procedures Hard-hat			ivity is not anticipated	based on historical source	e concentrations. SSO to take and
tt control, use of PPE, and following safe work practices. VOCs – irritating at all points of contact; CNS effects (blurred on, narcotic effects, dizziness); Extremely high concentrations may result in Irregular heartbeats, possible cardiac arrest, and, bentonite, grout may cause mechanical irritation (eyes) as well as potential alkali burns; respiratory, eye, and mucous mbrane irritation. (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VIII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VIII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VIII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VIII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SSO: Each item in Sections VIII, VIII, and IX must be checked Yes, No, or NA) (Note to FOL and/or SNA; No, or NA) (Note to FOL and	Join D	ackground levels at least daily.			
Additional Safety Equipment/Procedures Hard-hat			med midden (eyee) de	wen de petermai aman s	arno, respiratory, eye, and macouc
Additional Safety Equipment/Procedures Hard-hat		(Note to FOL and/or SSO: Each	itom in Sections VII	VIII and IX must be show	kad Vas Na ar NA)
Hard-hat	VII			viii, and ix must be chec	Red Tes, No, of NA)
Safety Glasses	۷ ۱۱۰			Hearing Protection (Plug	s/Muffs)
Chemical/Splash Goggles				Safety Belt/Harness	□ Yes ⊠ No
Splash Shield					
Splash Suits/Coveralls					
Impermeable Apron					
Steel Toe Work Shoes or Boots. Yes No Chemical Resistant Boot Covers Yes No High Visibility Vest Yes No Tape/Insect Repellent Yes No First Aid Kit. Yes No Safety Shower/Eyewash Yes No Other Yes No Modifications/Exceptions: VIII. Site Preparation Yes No NA Utility Locating and Excavation Clearance completed Yehicle and Foot Traffic Routes Established/Traffic Control Barricades/Signs in Place Physical Hazards Identified and Isolated (Splash and containment barriers) Yes No Modifications/Exceptions: IX. Additional Permits required (Hot work, confined space entry, excavation etc.) Yes No Modifications Yes No Modifications Yes No		Impermeable Apron	☐ Yes ⊠ No		
High Visibility Vest		Steel Toe Work Shoes or Boots.	⊠ Yes □ No		
First Aid Kit					
Safety Shower/Eyewash					
VIII. Site Preparation Utility Locating and Excavation Clearance completed					
Utility Locating and Excavation Clearance completed		Safety Shower/Eyewash	∐ Yes ∐ No	Other	Yes No
Utility Locating and Excavation Clearance completed			∐ Yes ∐ No	Other	Yes No
Vehicle and Foot Traffic Routes Established/Traffic Control Barricades/Signs in Place	VIII.	Modifications/Exceptions:	Yes	Other	Yes No
Physical Hazards Identified and Isolated (Splash and containment barriers)	VIII.	Modifications/Exceptions: Site Preparation		Other	Yes No NA
 IX. Additional Permits required (Hot work, confined space entry, excavation etc.)	VIII.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl	learance completed	Other	Yes □ No Yes No NA □ □
 IX. Additional Permits required (Hot work, confined space entry, excavation etc.)	VIII.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E	learance completed Established/Traffic Cont	Other	Yes No NA
If yes, SSO to complete or contact Health Sciences, Pittsburgh Office (412)921-7090 X. Special instructions, precautions: VOCs are most likely to be present at REC 1, 11, and 12. Any sustained readings in worker breathing zones will suggest an unanticipated condition that will require that site activities be suspended until the source of elevated readings is determined. Use safe lifting/carrying techniques. Assume media is contaminated and avoid contact through the use of safe work practices, PPE and decontamination. As this activity may occur at night Ensure lighting within the work area are at least 5 foot candles. Prior to placing Summa Canisters ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.	VIII.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is	learance completed Established/Traffic Cont solated (Splash and cor	Other	Yes No NA
X. Special instructions, precautions: VOCs are most likely to be present at REC 1, 11, and 12. Any sustained readings in worker breathing zones will suggest an unanticipated condition that will require that site activities be suspended until the source of elevated readings is determined. Use safe lifting/carrying techniques. Assume media is contaminated and avoid contact through the use of safe work practices, PPE and decontamination. As this activity may occur at night Ensure lighting within the work area are at least 5 foot candles. Prior to placing Summa Canisters ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.		Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S	learance completed Established/Traffic Cont solated (Splash and cont Spill control, fire extingu	crol Barricades/Signs in Plantainment barriers)ishers, first aid kits, etc)	Yes No NA
readings in worker breathing zones will suggest an unanticipated condition that will require that site activities be suspended until the source of elevated readings is determined. Use safe lifting/carrying techniques. Assume media is contaminated and avoid contact through the use of safe work practices, PPE and decontamination. As this activity may occur at night Ensure lighting within the work area are at least 5 foot candles. Prior to placing Summa Canisters ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.		Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho	learance completed Established/Traffic Cont solated (Splash and co Spill control, fire extingui of work, confined space	orol Barricades/Signs in Plantainment barriers)ishers, first aid kits, etc)	Yes No NA
suspended until the source of elevated readings is determined. Use safe lifting/carrying techniques. Assume media is contaminated and avoid contact through the use of safe work practices, PPE and decontamination. As this activity may occur at night Ensure lighting within the work area are at least 5 foot candles. Prior to placing Summa Canisters ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact	learance completed Established/Traffic Cont solated (Splash and col Spill control, fire extingui of work, confined space of Health Sciences, Pitts	other	Yes No NA
is contaminated and avoid contact through the use of safe work practices, PPE and decontamination. As this activity may occur at night Ensure lighting within the work area are at least 5 foot candles. Prior to placing Summa Canisters ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precautions	learance completed Established/Traffic Cont solated (Splash and cor Spill control, fire extingui ot work, confined space of Health Sciences, Pitts ons: VOCs are most	other	Yes No NA
may occur at night Ensure lighting within the work area are at least 5 foot candles. Prior to placing Summa Canisters ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precaution	learance completed Established/Traffic Cont solated (Splash and con Spill control, fire extingui of work, confined space of Health Sciences, Pitts ons: VOCs are most nes will suggest an ur	orther	Yes No NA Yes No NA Ace Ace Ace Ace Ace Ace Ace Ace Ace Ace Ace Yes Yes Yes Yes Any sustained of twill require that site activities be
ventilate indoor area if elevated readings (>10 ppm) are encountered upon entering building to achieve readings less than 10 ppm.	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precaution readings in worker breathing zoonsuspended until the source of elec	learance completed Established/Traffic Cont solated (Splash and con Spill control, fire extingui of work, confined space of Health Sciences, Pitts ons: VOCs are most nes will suggest an ur evated readings is dete	other	Yes No NA Yes No NA Ace
than 10 ppm.	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precaution readings in worker breathing zoon suspended until the source of elections in the source of e	learance completed Established/Traffic Cont solated (Splash and con Spill control, fire extingui of work, confined space of Health Sciences, Pitts ons: VOCs are most nes will suggest an ur evated readings is dete of through the use of sa	other Irrol Barricades/Signs in Plantainment barriers)	Yes No NA Yes No NA Ace
	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precaution readings in worker breathing zoon suspended until the source of elections of the secondary occur at night Ensure lighting	learance completed Established/Traffic Cont solated (Splash and con Spill control, fire extingui of work, confined space of Health Sciences, Pitts ons: VOCs are most nes will suggest an ur evated readings is dete of through the use of sa g within the work area	other Irol Barricades/Signs in Plantainment barriers) ishers, first aid kits, etc) e entry, excavation etc.) sburgh Office (412)921-70 likely to be present at Rinanticipated condition that rmined. Use safe lifting/cafe work practices, PPE are at least 5 foot candles.	Yes No NA NO NA Yes No NA NO NO NA NO NO NA NO NO NA NO N
mit Issued by: Permit Accepted by:	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precaution readings in worker breathing zoon suspended until the source of elections is contaminated and avoid contact may occur at night Ensure lighting ventilate indoor area if elevated in	learance completed Established/Traffic Cont solated (Splash and con Spill control, fire extingui of work, confined space of Health Sciences, Pitts ons: VOCs are most nes will suggest an ur evated readings is dete of through the use of sa g within the work area	other Irol Barricades/Signs in Plantainment barriers) ishers, first aid kits, etc) e entry, excavation etc.) sburgh Office (412)921-70 likely to be present at Rinanticipated condition that rmined. Use safe lifting/cafe work practices, PPE are at least 5 foot candles.	Yes No NA NO NA Yes No NA NO NO NA NO NO NA NO NO NA NO N
, ·	IX.	Modifications/Exceptions: Site Preparation Utility Locating and Excavation Cl Vehicle and Foot Traffic Routes E Physical Hazards Identified and Is Emergency Equipment Staged (S Additional Permits required (Ho If yes, SSO to complete or contact Special instructions, precaution readings in worker breathing zoon suspended until the source of elections is contaminated and avoid contact may occur at night Ensure lighting ventilate indoor area if elevated in	learance completed Established/Traffic Cont solated (Splash and con Spill control, fire extingui of work, confined space of Health Sciences, Pitts ons: VOCs are most nes will suggest an ur evated readings is dete of through the use of sa g within the work area	other Irol Barricades/Signs in Plantainment barriers) ishers, first aid kits, etc) entry, excavation etc.) sburgh Office (412)921-70 likely to be present at Rinanticipated condition that rmined. Use safe lifting/cafe work practices, PPE and are at least 5 foot candles.	Yes No NA No NA Yes No NA

SAFE WORK PERMIT BLOCK F MULTI MEDIA SAMPLING AND WELL DEVELOPMENT LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit I	No Date:	Time: From	ı to
			_
I.		cription, area, equipment used): Multimedia	
	subsurface soils, groundwater, storn	n water, IDW. This task also includes soil vapo	or sampling and indoor air quality
	sampling.		
II.	Primary Hazards: Contact with site of	contaminants; transfer of contamination; heavy	lifting; slip, trip and fall; cuts and
	lacerations; vehicular and foot traff	ic; ambient temperature extremes; insect/anii	mal bites and stings, poisonous
	plants, inclement weather.	•	<u> </u>
III.	Field Crew:		
IV.	On-site Inspection conducted	☐ Yes ☐ No Initials of Inspector _	Tetra Tech
	Equipment Inspection required	Yes No Initials of Inspector	
٧.	Protective equipment required	Respiratory equipment require	4
••	Level D 🛛 Level B 🗌	Yes Specify on the rev	
	Level C Level A	No ⊠	76136
	Modifications/Exceptions:	140	
		A . Ø	
VI.	Chemicals of Concern (COCs) and		
COCs	Hazard Monitoring	Action Level(s)	Response Measures
<u>VOCs</u>	PID (except on boat/barge)	>1,000 ppm in BZ sustained 4 exp of 5 minutes	Screen BZ with Draeger tubes
<u>Benzene</u>		Up to 5 ppm/sustained 10 minutes/4 times/day	Evacuate site till background levels retu
Dust	Visual –Visible dust	>2 mg/m3	Employ dust suppression –Wet it down
_			
		PAHs, sand, grout. Encountering airborne conce	
		is not anticipated based on historical source	concentrations. SSO to take and
record b	ackground levels at least daily.		
		alation, ingestion and skin contact. Controls in	
dust co	ntrol, use of PPE, and following safe	work practices. VOCs - irritating at all points	of contact; CNS effects (blurred
		high concentrations may result in Irregular he	
		l irritation (eyes) as well as potential alkali bur	
	ane irritation.		, , , , , , , , , , , , , , , , , , ,
	(Note to FOL and/or CCO, Fook its	m in Costiana VIII VIIII and IV must be aback	ad Vac No. av NA)
		m in Sections VII, VIII, and IX must be check	ed Yes, No, or NA)
VII.			
	Hard-hat		Muffs) ∐ Yes ∐ No
	Safety Glasses 🖂 🗎		
	Chemical/Splash Goggles		Yes No
	Splash Shield	'es ⊠ No Barricades	🗌 Yes 🔲 No
	Splash Suits/Coveralls	'es ☐ No Gloves (Type – Nitrile)	🛛 Yes 🗌 No
	Impermeable Apron		
	Steel Toe Work Shoes or Boots.	es ☐ No Chemical Resistant Boot C	
	High Visibility Vest		
	First Aid Kit		
	Safety Shower/Eyewash	es ☐ No Other	I res I No
	Modifications/Exceptions:		
VIII.	Site Preparation		Yes No NA
	Utility Locating and Excavation Clear	ance completed	
		blished/Traffic Control Barricades/Signs in Plac	
		ted (Splash and containment barriers)	
		control, fire extinguishers, first aid kits, etc)	
ΙΥ		ork, confined space entry, excavation etc.)	
ıA.		ealth Sciences, Pittsburgh Office (412)921-7090	
v			
Χ.		VOCs are most likely to be present at REC	
		will suggest an unanticipated condition that	
		ed readings is determined. Use safe lifting/car	
		rough the use of safe work practices, PPE and	
	may occur at night Ensure lighting wi	thin the work area are at least 5 foot candles. I	Prior to placing Summa Canisters
		ings (>10 ppm) are encountered upon entering	
	than 10 ppm.	<u> </u>	
			<u></u>
Jarm:+ 1	scuad by:	Darmit Asserted by	
CHILL I	ssued by:	Permit Accepted by:	

SAFE WORK PERMIT BLOCK H MULTI MEDIA SAMPLING AND WELL DEVELOPMENT LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit I	No Date:		Time: Fro	m to
l.				dia sampling including surface and por sampling and indoor air quality
II.	Primary Hazards: Contact with s			y lifting; slip, trip and fall; cuts and nimal bites and stings, poisonous
III.	Field Crew:			
IV.	On-site Inspection conducted	Yes No	Initials of Inspector	Tetra Tech
:	Equipment Inspection required		Initials of Inspector	Tetra Tech
V.	Protective equipment required Level D ☐ Level B ☐ Level C ☐ Level A ☐ Modifications/Exceptions:	Yes No	tory equipment requir Specify on the re	
VI.	Chemicals of Concern (COCs)			
COCs	Hazard Monitoring PID (except on boat/barge)	Action Level(s) >10.00 ppm in BZ sustaine	ad 4 avm of 5 minutes	Response Measures Screen BZ with Draeger tubes
VOCs Benzene Dust		Up to 5 ppm/sustained 10 n >2 mg/m3		Evacuate site till background levels return Employ dust suppression –Wet it down
in the b	mponents may include metals, PC preathing zone (BZ) during this according the properties of the proper	Bs, PAHs, sand, grout. Enc- tivity is not anticipated base	ountering airborne cond sed on historical source	centrations above background levels e concentrations. SSO to take and
dust co vision, i Sand, b	ntrol, use of PPE, and following snarcotic effects, dizziness); Extre	safe work practices. VOCs mely high concentrations n	s – irritating at all point may result in Irregular h	include monitoring instrument use, ts of contact; CNS effects (blurred neartbeats, possible cardiac arrest. urns; respiratory, eye, and mucous
VII.	(Note to FOL and/or SSO: Each Additional Safety Equipment/P	Procedures		•
	Hard-hat		earing Protection (Plugs	
	Safety Glasses Chemical/Splash Goggles		adio/Cellular Phone	☐ Yes ⊠ No ☐ Yes ☐ No
	Splash Shield		arricades	
	Splash Suits/Coveralls		loves (Type – Nitrile)	
	Impermeable Apron		ork/rest regimen	🗌 Yes 🔲 No
	Steel Toe Work Shoes or Boots.		hemical Resistant Boot	Covers ☐ Yes ⊠ No
	High Visibility Vest		ape/Insect Repellent	
	First Aid Kit	Yes No Fi	re Extinguisher	
	Safety Shower/Eyewash	☐ Yes ☐ No O	ther	Yes No
	Modifications/Exceptions:			Van NI- NIA
VIII.	Site Preparation Utility Locating and Excavation C Vehicle and Foot Traffic Routes I Physical Hazards Identified and I	Established/Traffic Control Isolated (Splash and contai	Barricades/Signs in Pla inment barriers)	ice
	Emergency Equipment Staged (S			
IX. X.	Additional Permits required (H If yes, SSO to complete or conta Special instructions, precautions)	ct Health Sciences, Pittsbu	rgh Office (412)921-70	
	readings in worker breathing zo suspended until the source of ele	ones will suggest an unan evated readings is determi	ticipated condition that ned. Use safe lifting/ca	t will require that site activities be arrying techniques. Assume media
				nd decontamination. As this activity Prior to placing Summa Canisters
				g building to achieve readings less
	than 10 ppm.			g a submig to do no to toddingo 1000
Permit I	Issued by:	Per	mit Accepted by:	

SAFE WORK PERMIT SITE IDW MANAGEMENT LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit	No	Date:	Time: From	to	
SECTION	ON I: General Job Scope				
I.	Work limited to the following (description, containerization, staging, monitoring for leaks of ID decontamination wash waters.				
II.	Primary Hazards: Lifting, pinches and comp contamination.	ressions; flying p	orojectiles; slip	s, trips, and falls ar	nd chemica
III. IV.	Field Crew: On-site Inspection conducted Yes No Requipment Inspection required Yes No		spector	Tetra Tech Tetra Tech	_
SECTION	ON II: General Safety Requirements (To be filled i				
V.	- · · · · · · · · · · · · · · · · · · ·	Respiratory equi Yes No			_
VI.	Chemicals of Concern Hazard Monone anticipated N/A	nitoring /Action L	evel(s)	Response Measures N/A	
ļ	Primary Route of Exposure/Hazard: inhalation, d	ermal, ingestion			
	(Note to FOL and/or SHSO: Each item in Section		must be chec	ked Yes or No)	
VIII.	Additional Safety Equipment/Procedures Hard-hat	Hearing Proceedings of the second sec	otection (Plugs//harness	Muffs)	ed. If power vek coveral ct repellants lication and
	Vehicle and Foot Traffic Routes Established/Traffic Physical Hazards Identified and Isolated Emergency Equipment Staged (Spill control, fire e	c Control Barricade xtinguishers, first a	es/Signs in Plac aid kits, etc)	e	
IX.	Additional Permits required (Hot work, confined If yes, SHSO to complete or contact Health Science)
X.	Special instructions, precautions: Suspend site techniques. When/where possible use heavy equip label and retention ring nut on the outside where distance of 4-feet between pallet rows. An IDW invand volumes. This inventory should be provided to	e activities in the ement to move and it is readily visible ventory shall be ge	event of incleme place container e. Place 4-drum nerated to prov	ent weather. Employ pres. When placing drums ns to a pallet. Maintain ide the number of drun	 Place the a minimum
Permit	Issued by:	Permit Accer	oted by:		

Multi-media Sampling CTO 0836

SAFE WORK PERMIT SITE DECONTAMINATION ACTIVITIES LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit is	iototo
l.	Work limited to the following (description, area, equipment used): Decontamination of sampling equipment (i.e. reusable stainless steel trowels, etc.). Brushes and spray bottles will be used to decontaminate small sampling
II.	equipment. Primary Hazards: Chemical exposure, transfer of contamination, inclement weather, noise.
III.	Field Crew:
IV.	On-site Inspection conducted Yes No Initials of Inspector Tetra Tech Equipment Inspection required Yes No Initials of Inspector Tetra Tech
V.	Protective equipment required Level D Level B Yes Specify on the reverse Level C Level A Specify on the reverse No Modifications/Exceptions: Minimum requirement include sleeved shirt and long pants, safety glasses, safety footwear, and nitrile gloves. Impermeable aprons are preferred protection against soiling work clothes when lifting auger flights because of the need to carry close to the body. If it (impermeable apron) does not offer adequate protection, PVC rains suits or PE or PVC coated Tyvek should be employed. Chemical resistant boot covers if excessive liquids are generated or to protected footwear. PID with 10.6eV lamp [Note: This instrument will be used to determine if any volatile contaminants have been removed. It will not be used for purposes of monitoring exposure.
	Chemicals of Concern Hazard Monitoring / Action Level(s) Response Measures Decontamination Fluids Refer to MSDS refer to MSDS
P	rimary Route(s) of Exposure/Hazard: Inhalation and direct contact and ingestion
VII.	(Note to FOL and/or SHSO: Each item in Sections VII, VIII, and IX must be checked Yes, No, or NA) Additional Safety Equipment/Procedures Hard-hat Yes No Hearing Protection (Plugs/Muffs) Yes No Safety Glasses Yes No Safety belt/harness Yes No Chemical/splash goggles Yes No Radio/Cellular Phone Yes No Splash Shield Yes No Barricades Yes No Splash suits/coveralls Yes No Gloves (Type – Nitrile) Yes No Impermeable apron Yes No Work/rest regimen Yes No Steel toe Work shoes or boots Yes No Chemical Resistant Boot Covers Yes No High Visibility vest Yes No Tape up/use insect repellent Yes No First Aid Kit Yes No Fire Extinguisher Yes No Modifications/Exceptions Chemical resistant boot covers if excessive liquids are generated or to protect footwear.
VIII.	Site Preparation Ves No NA Utility Locating and Excavation Clearance completed
IX.	Additional Permits required (Hot work, confined space entry, excavation etc.)
X.	Special instructions, precautions: Suspend site activities in the event of inclement weather. Employ proper lifting techniques. When/where possible use heavy equipment to move and place containers.
Permit Is	Permit Accented by:

Multi-media Sampling CTO 0836

SAFE WORK PERMIT FOR BLOCK E FORMER BUILDING D MULTI-MEDIA SAMPLING / RADIOLOGICAL SURVEYING LOCKHEED MARTIN MIDDLE RIVER COMPLEX MIDDLE RIVER, MARYLAND

Permit N	lo. Date: Time: From to				
SECTION I: General Job Scope					
I.					
II. III.	Required Monitoring Instrument(s): <u>beta/gamma detectors (Micro R meter and frisker such as the Ludlum Model 19)</u> Field Crew:				
IV.	On-site Inspection conducted Yes No Initials of InspectorTetra Tech Equipment Inspection required Yes No Initials of InspectorTetra Tech				
SECTION II: General Safety Requirements (To be filled in by permit issuer)					
V.	Protective equipment required Respiratory equipment required				
	Level D ☑ Level B ☐ Full face APR ☐ Escape Pack ☐ Level C ☐ Level A ☐ Half face APR ☐ SCBA ☐				
	Detailed on Reverse PAPR Bottle Trailer				
	Skid Rig $\overline{\square}$ None $\overline{\boxtimes}$				
	Modifications/Exceptions: None anticipated				
VI.	Chemicals of Concern Action Level(s) Response Measures				
_	Alpha, Beta, Gamma Radiation Dose rates above 50 µR/hr Exit work area and evaluate control				
_	<u>measures</u>				
_					
VII	Additional Safety Equipment/Procedures				
VII.	Hard-hat ☐ Yes ☐ No Hearing Protection (Plugs/Muffs) ☐ Yes ☐ No				
	Safety Glasses ☐ Yes ☐ No Safety belt/harness ☐ Yes ☐ No				
	Chemical/splash goggles ☐ Yes ☒ No Radio ☐ Yes ☒ No				
	Splash Shield				
	Splash suits/coveralls				
	Modifications/Exceptions: Gloves required during sampling activities or whenever contact with potentially				
	contaminated media exists.				
VIII.	Procedure review with permit acceptors Yes NA Yes NA				
	Safety shower/eyewash (Location & Use)				
	Procedure for safe job completion				
	Contractor tools/equipment/PPE inspected				
IX	Site Preparation Yes No NA				
	Utility Locating and Excavation Clearance completed				
	Vehicle and Foot Traffic Routes Cleared and Established				
	Physical Hazards Barricaded and Isolated				
	Emergency Equipment Staged				
Χ.	Additional Permits required (Hot work, confined space entry, excavation etc.)				
XI.	Special Instructions, Precautions: It is anticipated that remedial action activities have resulted in the removal of contaminated soils. This sampling effort is being conducted to evaluate the effectiveness of the remediation effort.				
	However, contact with potentially contaminated media will be minimized through the use of avoidance practices and the				
	use of ppe. Site workers must wash hands and face before performing any hand to mouth activities. Avoid inhalation				
	of any airborne dusts, however, soil sampling activities are unlikely to generate dusts. First aid kits will be available at				
	all remote sampling locations. Avoid insect/animal nesting areas. Sampling areas may be tick, gnat, wasp, and				
	mosquito infested. Maintain a means to contact emergency services (cell phone) and verify they are functional.				
Permit I	ssued by: Permit Accepted by:				
Permit Issued by: Permit Accepted by:					

Multi-media Sampling CTO 0836

ATTACHMENT V EQUIPMENT INSPECTION CHECKLIST FOR DRILL/DPT RIGS

Equipment Inspection Checklist for Drill/DPT Rigs

Compa	any:		Unit/Serial No#:		
Inspec	tion Dat	:e:	/ Time: : Equipment Type: (e.g., Drill Rigs Hollow S	Stem Mud Rotary Direct Push HDD)	
Project Name: Project No#:					
Yes	No	NA	Requirement	Comments	
			Emergency Stop Devices • Emergency Stop Devices (At points of operation) • Have all emergency shut offs identified been communicated to the field crew?		
			 Has a person been designated as the Emergency Stop Device Operator? 		
			Highway Use Cab, mirrors, safety glass? Turn signals, lights, brake lights, etc. (front/rear) for equipment		
			approved for highway use?Seat Belts?Is the equipment equipped with audible back-up alarms and back-up lights?		
			 Horn and gauges Brake condition (dynamic, park, etc.) Tires (Tread) or tracks Windshield wipers Exhaust system Steering (standard and emergency) Wheel Chocks? Are tools and material secured to prevent movement during transport? Especially those within the cab? 		
			 Are there flammables or solvents or other prohibited substances stored within the cab? Are tools or debris in the cab that may adversely influence operation of the vehicle (in and around brakes, clutch, gas pedals) 		

Unit/Serial No#:	Inspection Date: _	 	

Yes	No	NA	Requirement	Comments
			Fluid Levels:	
			High Pressure Hydraulic Lines Obvious damage Operator protected from accidental release Coupling devices, connectors, retention cables/pins are in good condition and in place	
			Mast Condition	
			 Hooks Are the hooks equipped with Safety Latches? Does it appear that the hook is showing signs of wear in excess of 10% original dimension? Is there a bend or twist exceeding 10% from the plane of an 	
			 unbent hook? Increase in throat opening exceeding 15% from new condition Excessive nicks and/or gouges Clips Number of U-Type (Crosby) Clips (cable size 5/16 - 5/8 = 3 clips minimum) (cable size 3/4 - 1 inch = 4 clips minimum) (cable size 1 1/8 - 1 3/8 inch = 5 clips minimum) 	

Equipment Inspection Checklist for Drill Rigs Page 3

nit/Serial No#:	Inspection Date: /////
-----------------	------------------------

Yes	No	NA	Requirement	Comments		
			Power cable and/or hoist cable			
			 Reduction in Rope diameter π 			
			(5/16 wire rope>1/64 reduction nominal size -replace)			
			(3/8 to 1/2 wire rope>1/32 reduction nominal size-replace)			
			(9/16 to 3/4 wire rope>3/64 reduction nominal size-replace)			
			Number of broken wires			
			(6 randomly broken wires in one rope lay)			
			(3 broken wires in one strand)Number of wire rope wraps left on the Running Drum at nominal			
			use (≥3 required)			
			- Lead (primary) sheave is centered on the running drum			
			Lubrication of wire rope (adequate?)			
			 Kinks, bends – Flattened to > 50% diameter 			
			Hemp/Fiber rope (Cathead/Split Spoon Hammer)			
			Minimum ¾; maximum 1 inch rope diameter (Inspect for			
	_		physical damage)			
			Rope to hammer is securely fastened			
			Safety Guards –			
			Around rotating apparatus (belts, pulleys, sprockets, spindles,			
			drums, flywheels, chains) all points of operations protected from accidental contact?			
			Hot pipes and surfaces exposed to accidental contact?			
	l H		High pressure lines			
	ΙĦ		Nip/pinch points			
			Operator Qualifications			
			 Does the operator have proper licensing where applicable, (e.g., 			
			CDL)?			
			Does the operator, understand the equipment's operating			
			instructions?			
			Is the operator experienced with this equipment?			
			Is the operator 21 years of age or more?			

Equipment Inspection Checklist for Drill Rigs Page 4

Unit/S	erial No	#: <u></u>	Inspection Date:	<u> </u>
Yes	No	NA	Requirement	Comments
			PPE Required for Drill Rig Exclusion Zone • Hardhat • Safety glasses • Work gloves • Chemical resistant gloves • Steel toed Work Boots • Chemical resistant Boot Covers • Apron • Coveralls Tyvek, Saranex, cotton) Other Hazards • Excessive Noise Levels? dBA • Chemical hazards (Drilling supplies - Sand, bentonite, grout, fuel, etc.) - MSDSs available? • Will On-site fueling occur - Safety cans available? - Fire extinguisher (Type/Rating)	
Approv	ed for U	Jse [Yes No See Comments	
Site He	ealth and	d Safety	Officer Operator	

ATTACHMENT VI TETRA TECH SWP 5-6 SAFE WORKING PRACTICES FOR WORKING OVER OR NEAR WATER



TETRA TECH, INC. SAFE WORK PRACTICES for WORKING OVER OR NEAR WATER

Revision Date: 10/1/2008						
Document Control Number:						
SWP 5-6						
Page 1 of 3						

The following sections discuss general procedures for working over or near water, underwater work, and cold water procedures.

1.0 SCOPE

This safe work practice (SWP) provides guidelines for all Tetra Tech employees and subcontractors who work over or near bodies of water three (3) or more feet deep or swiftly moving water. This SWP was developed in accordance with the Occupational Safety and Health Administration (OSHA) standard specified in Title 29 of the *Code of Federal Regulations* (CFR), Part 1926.106, "Working Over or Near Water."

2.0 RESPONSIBILITIES

The project manager (PM) is responsible for identifying all health and safety requirements of each project, including all tasks that may involve worker exposure to hazards or working in or near bodies of water. The PM will appoint a site safety coordinator (SSC) to ensure that this SWP is followed in the field. Workers will follow this SWP whenever working near or in any body of water that is over three (3) feet deep or swiftly moving.

3.0 GENERAL PROCEDURES

When working over or near water, the following precautions will be taken:

- All staff and team members must wear a personal flotation device (PFD) when working within 15 feet of a water body. Personnel will be provided with U.S. Coast Guard (USCG)-approved life jackets or work vests. The PFD should be Class III, which will support the head of an unconscious person above water.
- Life jackets and work vests will be inspected before and after each use.
- Ring buoys with at least 90 feet of line shall be provided and readily available for employee rescue operations.
- The distance between ring buoys shall not exceed 200 feet.

The online version of this document supersedes all other versions. Paper copies of this document are uncontrolled. The controlled version of this document can be found on the Tetra Tech Intranet.



TETRA TECH, INC. SAFE WORK PRACTICES for WORKING OVER OR NEAR WATER

Revision Date: 10/1/2008

Document Control Number:

SWP 5-6

Page 2 of 3

- A USCG-approved life-saving skiff will be available.
- Under no circumstances will team members enter water bodies without protective clothing such as rubber boots or waders.
- At least one person will remain on shore as a look-out.

If a team member falls into the water, a ring buoy, branch, paddle, pole, or other floating object should be extended to the person in the water. Resist the impulse to dive in; employees should not attempt a deep water rescue unless they have been trained in water lifesaving skills. When the person in the water grabs the extended item, the worker should be pulled toward the shore or boat. If the person is unconscious, the PFD, clothing, or hair should be hooked to pull the person toward the shore or boat. Once the person has been safely retrieved, necessary emergency medical procedures should be performed by qualified personnel. If none are necessary, the retrieved team member should change into dry clothing as soon as possible after any necessary personal decontamination.

4.0 UNDERWATER WORK

Underwater work should be performed in accordance with the procedures and guidelines of the Diving Safety Program (Document Control No. 2-15).

5.0 COLD WATER PROCEDURES

When the water temperature is below 45 °F, hypothermia is a serious risk. A person can loose feeling in the extremities within 5 minutes. Additional protective equipment such as cold water immersion suits may be required. All field staff members should be familiar with cold water survival techniques or should receive training from an American Red Cross-certified swimming instructor in cold water survival techniques when site conditions warrant such knowledge. Cold water safe work practices must be addressed in site specific safety documents.

After a person has been rescued from cold water, he or she should change into dry clothes as soon as possible. If the person who has fallen into the water displays hypothermia symptoms, he or she should be treated immediately and taken to a medical facility. Under no circumstances should the hypothermia victim be given hot liquids because this could



TETRA TECH, INC. SAFE WORK PRACTICES for WORKING OVER OR NEAR WATER

Revision Date: 10/1/2008					
Document Control Number:					
SWP 5-6					
Page 3 of 3					

accelerate shock. Drinks no warmer than normal body temperature are acceptable. If symptoms are severe and evacuation to a medical facility cannot be quickly conducted, any wet clothing should be removed, the victim should be placed in blankets or sleeping bags in a sheltered location, and the rescuer should climb into the blankets or sleeping bag with victim to provide additional warmth. The victim should also be treated continuously for shock, elevating feet and monitoring the victim's pulse and breathing rate.

If a team member falls into cold water, he or she should not remove any clothing while in the water because clothing provides additional insulation. Although clothing creates an added drag while swimming, the insulation outweighs the disadvantage of the additional drag. Each team member should carry a wool hat to place on his or her head in case he or she falls into the water. A wool hat, even when wet, provides good insulation for the head, where a large amount of body heat is lost.

Disclaimer: This safe work practice (SWP) is the property of Tetra Tech, Inc. (Tetra Tech). Any reuse of the SWP without Tetra Tech's permission is at the sole risk of the user. The user will hold harmless Tetra Tech for any damages that result from unauthorized reuse of this SWP. Authorized users are responsible for obtaining proper training and qualification from their employer before performing operations described in this SWP.

Revision Date Document Authorizer		Revision Details
10/1/2008	Chris McClain	Update from 1998 format

ATTACHMENT VII BOAT SAFETY CHECKLIST

TETRA TECH, INC. SAFE BOATING CHECKLIST

Owner/Operator Name	e:										
Registration Number											
Location			C	ounty:	:_			State:H	IN:		
Length of Boat:	<16		16	-25		2 6-39		40-65 🗆 >	- 65 □)	
Area of Operations:	Inland		Co	astal		ב					
Powered by:	Gas		Die	esel		☐ Sail		Other \Box			
Туре:	PWC		Ор	en		C abin		Other 🗖			
VESSEL SAFETY CI	HECK R	FOLIIR	FMF	NTS		RECC	MMENE	DED AND DISCUSSIO	N ITEM	/IS	
Item		Yes		NA		Item					NA
1. Display of Numbers						(While encou	ıraged,	items below are not i			
2. Registration / Docume	entation					I. Marine F					
3. Personal Flotation	n Device	es				II. Dewater	ing Devi	ce & Backup			
(PFD)											
4. Visual Distress Signa	ls (VDS)					III. Mounted					
5. Fire Extinguishers						IV. Anchor					
6. Ventilation		_						V Kits (**over)			
7. Backfire Flame Control								stress Signals			
8. Sound Producing Dev	/ices / Be	ell						of Compliance			
9. Navigation Lights10. Pollution Placard								s: (as applies) reporting / owne	-		
io. i oliulion i lacalu								reporting / Owne	1		
11. MARPOL Trash Place	ard					responsibility b. Offshore operations			1		
12. Marine Sanitation Dev								s / navigation aids			
13. Navigation Rules						d. Surviv					
14. State and/		al			İ			management			1

This checklist has been modified for use from the United States Coast Guard Auxiliary Vessel Safety Check (VSC) Program. USCG AUX. Form 204 (7-2000)

f. Float plan / weather & sea conditions

g. Insurance considerations

h. Boating check list

i. Safe boating classes

Requirements

15. Overall Vessel Condition:

a. Deck free of hazards / clean bilge

b. Electrical / fuel systems

c. Galley / heating systems

(as applies)

Explanation of Required Items

- □ 1. NUMBERING: The boat's registration number must be permanently attached to each side of the forward half of the boat. Characters must be plain, vertical, block style, not less than three (3) inches high, and in a color contrasting with the background. A space or hyphen must separate the letters from the numbers.
- □ 2. REGISTRATION / DOCUMENTATION: Registration or Documentation papers must be on board and available. Documentation numbers must be permanently marked on a visible part of the interior structure. The documented boat's name and hailing port must be displayed on the exterior hull in letters not less than 4 inches in height.
- □ 3. PERSONAL FLOTATION DEVICES (PFDs): Acceptable PFDs (also known as Life Jackets) must be U.S. Coast Guard approved and in good, serviceable condition. A wearable PFD of suitable size is required for the each person on the boat. Wearable PFDs shall be "readily accessible." Boats 16 Feet or longer, must also have one Type IV (throwable) device, which shall be "immediately available." PFDs shall NOT be stored in unopened plastic packaging.
- **4. VISUAL DISTRESS SIGNALS:** Boats 16 feet and over are required to carry a minimum of either:
 - 1) three day and three night pyrotechnic devices
 - 2) one day non-pyrotechnic device (flag) and one night non-pyrotechnic device (auto SOS light)
 - 3) a combination of 1) and 2).

Boats less than 16 feet need only carry night visual distress signals when operating from sunset to sunrise. It is recommended, but not required, that boats operating on inland waters should have some means of making a suitable day and night distress signal. The number and type of signals is best judged by considering conditions under which the boat will be operating.

- **5. FIRE EXTINGUISHERS:** Fire extinguishers are required if one of the following conditions exists:
 - 1) Inboard engine(s)
 - 2) Double bottom hulls not completely sealed or not completely filled with flotation materials
 - 3) Closed living space
 - 4) Closed stowage compartments that contain flammable materials or
 - 5) Permanently installed fuel tanks. Boats less than 26 feet, and propelled by outboard motors are NOT required to have fire extinguishers unless one or more of the conditions (2-5) listed above applies.

Coast Guard Classification of Fire Extinguishers							
Classification (type size)	B-I	B-II					
Foam (minimum gallons)	1.25	2.5					
Carbon Dioxide (minimum lbs.)	4	15					
Dry Chemical (minimum lbs.)	2	10					
Halon (minimum lbs.)	2.5	10					

NOTE: Fire extinguishers must be readily accessible and verified as serviceable.

Minimum Number of Extinguishers Required								
Boat Length	No Fixed System	With Fixed System						
Less than 26'	one B-1	0						
26' to less than 40'	two B-1 or one B-2	one B-1						
40' to 65'	three B-1 or one B-1 & one B-2	two B-1 or one B-2						

■ 6. VENTILATION: Boats with gasoline engines in closed compartments, built after 1 August 1980 must have a powered ventilation system. Those built prior to that date must have natural or powered ventilation. Boats with closed fuel tank compartments built after 1 August 1978 must

have either natural or powered ventilation in the fuel tank compartment. ☐ 7. BACKFIRE FLAME ARRESTER: Gasoline powered inboard/outboard or inboard motor boats must be equipped with an approved backfire flame control device. □ 8. SOUND PRODUCING DEVICES: To comply with Navigation Rules and for distress signaling purposes boats must carry a sound producing device (whistle, horn, siren, etc.) capable of a 4second blast audible for ½ mile. Boats larger than 39.4 ft. are also required to have a bell (see Navigation Rules.) 9. NAVIGATION LIGHTS: Boats must be able to display navigation lights between sunset and sunrise and in conditions of reduced visibility. Boats 16 feet or more in length must have properly installed, working navigation lights and an all-around anchor light capable of being lit independently from the red/green/white "running" lights. □ 10. POLLUTION PLACARD: Boats 26 feet and over with a machinery compartment must display an oily waste "pollution" placard. ☐ 11. MARPOL TRASH PLACARD: Boats 26 feet and over in length, operating in U.S. navigable waters, must display a "MARPOL" trash placard. Oceangoing boats 40 feet and over must also have a written trash disposal plan available onboard. ☐ 12. MARINE SANITATION DEVICE: Any installed toilet must be a Coast Guard approved device. Overboard discharge outlets must be capable of being sealed. ☐ 13. NAVIGATION RULES: Boats 39.4 feet and over must have on board a current copy of the Navigation Rules. ☐ 14. STATE AND LOCAL REQUIREMENTS: A boat must meet the requirements of the state in which it is being examined.

meet requirements by displaying a "certificate of compliance." Boats built before that date must

- ☐ 15. OVERALL BOAT CONDITION: As it applies to this Vessel. Including, but not limited to:
 - a. Deck free of hazards and clean bilge The boat must be free from fire hazards, in good overall condition, with bilges reasonably clean and visible hull structure generally sound. The use of automobile parts on boat engines is not acceptable. The engine horsepower must not exceed that shown on the capacity plate.
 - b. Electrical and Fuel Systems: The electrical system must be protected by fuses or manual reset circuit breakers. Switches and fuse panels must be protected from rain or water spray. Wiring must be in good condition, properly installed and with no exposed areas or deteriorated insulation. Batteries must be secured and terminals covered to prevent accidental arcing. If installed, self-circling or kill switch mechanism must be in proper working order.
 - c. Fuel Systems Portable fuel tanks (normally 7 gallon capacity or less) must be constructed of non-breakable material and free of corrosion and leaks. Vents must be capable of being closed. The tank must be secured and have a vapor-tight, leak-proof cap. Each permanent fuel tank must be properly ventilated.
 - **d. Galley and Heating Systems -** System and fuel tanks must be properly secured with no flammable materials nearby.

ATTACHMENT VIII TETRA TECH SWP 5-15 HEAT STRESS AND 5-26 PREVENTION OF SUN EXPOSURE



Revision Date: 10/1/2008

Document Control Number:

SWP 5-15

Page 1 of 4

This safe work practice (SWP) describes situations where heat stress is likely to occur and provides procedures for the prevention and treatment of heat-related injuries and illnesses. Wearing personal protective equipment (PPE), especially during warm weather, puts employees at considerable risk of developing heat-related illness. Health effects from heat stress may range from transient heat fatigue or rashes to serious illness or death.

Many factors contribute to heat stress, including PPE, ambient temperature and humidity, workload, and the physical condition of the employee, as well as predisposing medical conditions. However, the primary factors are elevated ambient temperatures in combination with fluid loss. Because heat stress is one of the more common health concerns that may be encountered during field activities, employees must be familiar with the signs, symptoms, and various treatment methods of each form of heat stress. Heat stroke is the most serious heat-related illness—it is a threat to life and has a 20 percent mortality rate. Direct exposure to sun, poor air circulation, poor physical condition, and advanced age directly affect the tendency to heat stroke. Table 1 lists the most serious heat conditions, their causes, signs and symptoms, and treatment.

Training is an important component of heat stress prevention. Employees are instructed to recognize and treat heat-related illnesses during 8-hour health and safety refresher and first aid training courses. When working in hot environments, specific steps should be taken to lessen the chances of heat-related illnesses. These include the following:

- Ensuring that all employees drink plenty of fluids (Gatorade® or its equivalent)
- Ensuring that frequent breaks are scheduled so overheating does not occur
- Revising work schedules, when necessary, to take advantage of the cooler parts of the day (such as working from 5:00 a.m. to 11:00 a.m. and 6:00 p.m. to nightfall).

When PPE must be worn (especially Levels A and B), suggested guidelines relating to ambient temperature and maximum wearing time per excursion are as shown in Table 2.



Revision Date: 10/1/2008

Document Control Number:

SWP 5-15

Page 2 of 4

TABLE 1 HEAT STRESS CONDITIONS

Condition	Causes	Signs and Symptoms	Treatment
Heat cramps	Fluid loss and electrolyte imbalance from dehydration	 Painful muscle cramps, especially in legs and abdomen Faintness Profuse perspiration 	 Move affected worker to cool location Provide sips of liquid such as Gatorade® Stretch cramped muscles Transport affected worker to hospital if condition worsens
Heat Exhaustion	Blood transport to skin to dissipate excessive body heat, resulting in blood pooling in the skin with inadequate return to the heart	 Weak pulse Rapid and shallow breathing General weakness Pale, clammy skin Profuse perspiration Dizziness Unconsciousness 	 Move affected worker to cool area Remove as much clothing as possible Provide sips of cool liquid or Gatorade® (only if conscious) Fan the person but do not overcool or chill Treat for shock Transport to hospital if condition worsens
Heat Stroke	Life threatening condition from profound disturbance of body's heat-regulating mechanism	 Dry, hot, and flushed skin Constricted pupils Early loss of consciousness Rapid pulse Deep breathing at first, and then shallow breathing Muscle twitching leading to convulsions Body temperature reaching 105 or 106 °F or higher 	 Immediately transport victim to medical facility Move victim to cool area Remove as much clothing as possible Reduce body heat promptly by dousing with water or wrapping in wet cloth Place ice packs under arms, around neck, at ankles, and wherever blood vessels are close to skin surface Protect patient during convulsions



Revision Date: 10/1/2008

Document Control Number:

SWP 5-15

Page 3 of 4

TABLE 2
SUGGESTED GUIDELINES WHEN WEARING PPE

Ambient Temperature	Maximum PPE Wearing Time per Excursion	
Above 90 °F	15 minutes	
85 to 90 °F	30 minutes	
80 to 85 °F	60 minutes	
70 to 80 °F	90 minutes	
60 to 70 °F	120 minutes	
50 to 60 °F	180 minutes	

Source: National Institute for Occupational Safety and Health (NIOSH). 1985. Memorandum Regarding Recommended Personal Protective Equipment Wearing Times at Different Temperatures. From Austin Henschel. To Sheldon Rabinovitz. June 20.

To monitor the level of an employee's heat stress, the following should be measured:

- Heart Rate: Count the radial (wrist) pulse during a 30-second period as early as possible
 in the rest period; if heart rate exceeds 110 beats per minute at the beginning of the rest
 period, shorten the next work cycle by one-third and keep the rest period the same.
 - If the heart rate still exceeds 110 beats per minute at the next period, shorten the following work cycle by one-third.
- Oral Temperature: Use a clinical thermometer (3 minutes under the tongue) to measure the oral temperature at the end of the work period. If oral temperature exceeds 99.6 °F (37.6 °C), shorten the next work cycle by one-third without changing the rest period. If oral temperature still exceeds 99.6 °F at the beginning of the next rest period, shorten the following work cycle by one-third. Do not permit a worker to wear impermeable PPE when his or her oral temperature exceeds 100.6 °F (38.1 °C).

Disclaimer: This safe work practice (SWP) is the property of Tetra Tech, Inc. (Tetra Tech). Any reuse of the SWP without Tetra Tech's permission is at the sole risk of the user. The user will hold harmless Tetra Tech for any damages that result from unauthorized reuse of this SWP. Authorized users are responsible for obtaining proper training and qualification from their employer before performing operations described in this SWP.



Revision Date: 10/1/2008

Document Control Number:

SWP 5-15

Page 4 of 4

Revision Date	Document Authorizer	Revision Details
10/1/2008	Chris McClain	Update from 1998 format

ATTACHMENT IX TETRA TECH DECONTAMINATION OF FIELD EQUIPMENT AND WASTE HANDLING STANDARD OPERATING PROCEDURE



TETRA TECH NUS, INC.

Subject DECONTAMINATION OF FIELD EQUIPMENT

STANDARD OPERATING PROCEDURES

Number	Page
SA-7.1	1 of 8
Effective Date	Revision
09/03	3

Applicability

Tetra Tech NUS, Inc.

Prepared

Earth Sciences Department

Approved D. Senovich

TABLE OF CONTENTS

SECT	<u>PAGE</u>
1.0	PURPOSE2
2.0	SCOPE2
3.0	GLOSSARY2
4.0	RESPONSIBILITIES3
5.0	PROCEDURES3
	5.1DECONTAMINATION DESIGN/CONSTRUCTIONS CONSIDERATIONS35.1.1Temporary Decontamination Pads35.1.2Decontamination Activities at Drill Rigs/DPT Units45.1.3Decontamination Activities at Remote Sample Locations55.2EQUIPMENT DECONTAMINATION PROCEDURES55.2.1Monitoring Well Sampling Equipment55.2.2Down-Hole Drilling Equipment65.2.3Soil/Sediment Sampling Equipment65.3CONTACT WASTE/MATERIALS75.3.1Decontamination Solutions75.4DECONTAMINATION EVALUATION7

Subject DECONT	AMINATION OF FIELD N	umber	Page
EQUIPME	ENT	SA-7.1	2 of 8
	R	evision	Effective Date
		3	09/03

1.0 PURPOSE

Decontamination is the process of removing and/or neutralizing site contaminants that have contacted and/or accumulated on equipment. The objective/purpose of this SOP is intended to protect site personnel, general public, and the sample integrity through the prevention of cross contamination onto unaffected persons or areas. It is further intended through this procedure to provide guidelines regarding the appropriate procedures to be followed when decontaminating drilling equipment, monitoring well materials, chemical sampling equipment and field analytical equipment.

2.0 SCOPE

This procedure applies to all equipment including drilling equipment, heavy equipment, monitoring well materials, as well as chemical sampling and field analytical equipment decontamination that may be used to provide access/acquire environmental samples. Where technologically and economically feasible, single use sealed disposable equipment will be employed to minimize the potential for cross contamination. This procedure also provides general reference information on the control of contaminated materials.

3.0 GLOSSARY

<u>Acid</u> - For decontamination of equipment when sampling for trace levels of inorganics, a 10% solution of nitric acid in deionized water should be used. Due to the leaching ability of nitric acid, it should not be used on stainless steel.

Alconox/Liquinox - A brand of phosphate-free laboratory-grade detergent.

<u>Decontamination Solution</u> - Is a solution selected/identified within the Health and Safety Plan or Project-Specific Quality Assurance Plan. The solution is selected and employed as directed by the project chemist/health and safety professional.

<u>Deionized Water (DI)</u> - Deionized water is tap water that has been treated by passing through a standard deionizing resin column. This water may also pass through additional filtering media to attain various levels of analyte-free status. The DI water should meet CAP and NCCLS specifications for reagent grade, Type I water.

<u>Potable Water</u> - Tap water used from any municipal water treatment system. Use of an untreated potable water supply is not an acceptable substitute for tap water.

<u>Pressure Washing</u> - Employs high pressure pumps and nozzle configuration to create a high pressure spray of potable water. High pressure spray is employed to remove solids.

<u>Solvent</u> - The solvent of choice is pesticide-grade Isopropanol. Use of other solvents (methanol, acetone, pesticide-grade hexane, or petroleum ether) may be required for particular projects or for a particular purpose (e.g. for the removal of concentrated waste) and must be justified in the project planning documents. As an example, it may be necessary to use hexane when analyzing for trace levels of pesticides, PCBs, or fuels. In addition, because many of these solvents are not miscible in water, the equipment should be air dried prior to use. Solvents should not be used on PVC equipment or well construction materials.

<u>Steam Pressure Washing</u> - This method employs a high pressure spray of heated potable water. This method through the application of heat provides for the removal of various organic/inorganic compounds.

019611/P Tetra Tech NUS, Inc.

Subject DECONTAMINATION OF FIELD EQUIPMENT	Number SA-7.1	Page 3 of 8
	Revision 3	Effective Date 09/03

4.0 RESPONSIBILITIES

<u>Project Manager</u> - Responsible for ensuring that all field activities are conducted in accordance with approved project plan(s) requirements.

<u>Field Operations Leader (FOL)</u> - Responsible for the onsite verification that all field activities are performed in compliance with approved Standards Operating Procedures or as otherwise dictated by the approved project plan(s).

<u>Site Health and Safety Officer (SHSO)</u> - The SHSO exercises shared responsibility with the FOL concerning decontamination effectiveness. All equipment arriving on-site (as part of the equipment inspection), leaving the site, moving between locations are required to go through a decontamination evaluation. This is accomplished through visual examination and/or instrument screening to determine the effectiveness of the decontamination process. Failure to meet these objectives are sufficient to restrict equipment from entering the site/exiting the site/ or moving to a new location on the site until the objectives are successfully completed.

5.0 PROCEDURES

The process of decontamination is accomplished through the removal of contaminants, neutralization of contaminants, or the isolation of contaminants. In order to accomplish this activity a level of preparation is required. This includes site preparation, equipment selection, and evaluation of the process. Site contaminant types, concentrations, media types, are primary drivers in the selection of the types of decontamination as well as where it will be conducted. For purposes of this SOP discussion will be provided concerning general environmental investigation procedures.

The decontamination processes are typically employed at:

- Temporary Decontamination Pads/Facilities
- Sample Locations
- Centralized Decontamination Pad/Facilities
- Combination of some or all of the above

The following discussion represents recommended site preparation in support of the decontamination process.

5.1 Decontamination Design/Constructions Considerations

5.1.1 Temporary Decontamination Pads

Temporary decontamination pads are constructed at satellite locations in support of temporary work sites. These structures are generally constructed to support the decontamination of heavy equipment such as drill rigs and earth moving equipment but can be employed for smaller articles.

The purpose of the decontamination pad is to contain wash waters and potentially contaminated soils generated during decontamination procedures. Therefore, construction of these pads should take into account the following considerations

Subject DECONTAMINATION OF FIELD EQUIPMENT	Number SA-7.1	Page 4 of 8
	Revision 3	Effective Date 09/03

- Site Location The site selected should be within a reasonable distance from the work site but should avoid:
 - Pedestrian/Vehicle thoroughfares
 - Areas where control/custody cannot be maintained
 - Areas where a potential releases may be compounded through access to storm water transport systems, streams or other potentially sensitive areas.
 - Areas potentially contaminated.
- Pad The pad should be constructed to provide the following characteristics
 - Size The size of the pad should be sufficient to accept the equipment to be decontaminated as well as permitting free movement around the equipment by the personnel conducting the decontamination.
 - Slope An adequate slope will be constructed to permit the collection of the water and potentially contaminated soils within a trough or sump constructed at one end. The collection point for wash waters should be of adequate distance that the decontamination workers do not have to walk through the wash waters while completing their tasks.
 - Sidewalls The sidewalls should be a minimum of 6-inches in height to provide adequate containment for wash waters and soils. If splash represents a potential problem, splash guards should be constructed to control overspray. Sidewalls maybe constructed of wood, inflatables, sand bags, etc. to permit containment.
 - Liner Depending on the types of equipment and the decontamination method the liner should be of sufficient thickness to provide a puncture resistant barrier between the decontamination operation and the unprotected environment. Care should be taken to examine the surface area prior to placing the liner to remove sharp articles (sticks, stones, debris) that could puncture the liner. Liners are intended to form an impermeable barrier. The thickness may vary from a minimum recommended thickness of 10 mil to 30 mil. Achieving the desired thickness maybe achieved through layering lighter constructed materials. It should be noted that various materials (rubber, polyethylene sheeting) become slippery when wet. To minimize this potential hazard associated with a sloped liner a light coating of sand maybe applied to provide traction as necessary.
 - Wash/drying Racks Auger flights, drill/drive rods require racks positioned off of the ground to permit these articles to be washed, drained, and dried while secured from falling during this process. A minimum ground clearance of 2-feet is recommended.
 - Maintenance The work area should be periodically cleared of standing water, soils, and debris. This action will aid in eliminating slip, trip, and fall hazards. In addition, these articles will reduce potential backsplash and cross contamination. Hoses should be gathered when not in use to eliminate potential tripping hazards.

5.1.2 Decontamination Activities at Drill Rigs/DPT Units

During subsurface sampling activities including drilling and direct push activities decontamination of drive rods, Macro Core Samplers, split spoons, etc. are typically conducted at an area adjacent to the operation. Decontamination is generally accomplished using a soap/water wash and rinse utilizing buckets and brushes. This area requires sufficient preparation to accomplish the decontamination objectives.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number SA-7.1	Page 5 of 8
		Revision 3	Effective Date 09/03

Buckets shall be placed within mortar tubs or similar secondary containment tubs to prevent splash and spills from reaching unprotected media. Drying racks will be employed as directed for temporary pads to permit parts to dry and be evaluated prior to use/re-use.

5.1.3 Decontamination Activities at Remote Sample Locations

When sampling at remote locations sampling devices such as trowels, pumps/tubing should be evacuated of potentially contaminated media to the extent possible. This equipment should be wrapped in plastic for transport to the temporary/centralized decontamination location for final cleaning and disposition.

5.2 Equipment Decontamination Procedures

The following represents procedures to be employed for the decontamination of equipment that may have contacted and/or accumulated contamination through site investigation activities.

5.2.1 Monitoring Well Sampling Equipment

- 5.2.1.1 <u>Groundwater sampling pumps This includes pumps inserted into the monitoring well such</u> as Bladder pumps, Whale pumps, Redi-Flo, reusable bailers, etc.
- 1) Evacuate to the extent possible, any purge water within the pump.
- 2) Scrub using soap and water and/or steam clean the outside of the pump and tubing, where applicable.
- 3) Insert the pump and tubing into a clean container of soapy water. Pump a sufficient amount of soapy water through the pump to flush any residual purge water. Once flushed, circulate soapy water through the pump to ensure the internal components are thoroughly flushed.
- 4) Remove the pump and tubing from the container, rinse external components using tap water. Insert the pump and tubing into a clean container of tap water. Pump a sufficient amount of tap water through the pump to evacuate all of the soapy water (until clear).
- 5) Rinse equipment with pesticide grade isopropanol
- Repeat item #4 using deionized water through the hose to flush out the tap water and solvent residue as applicable.
- 7) Drain residual deionized water to the extent possible, allow components to air dry.
- 8) Wrap pump in aluminum foil or a clear clean plastic bag for storage.

5.2.1.2 <u>Electronic Water Level Indicators/Sounders/Tapes</u>

During water level measurements, rinsing with the extracted tape and probe with deionized water and wiping the surface of the extracted tape is acceptable. However, periodic full decontamination should be conducted as indicated below.

019611/P Tetra Tech NUS, Inc.

^{* -} The solvent should be employed when samples contain oil, grease, PAHs, PCBs, and other hard to remove materials. If these are not of primary concern, the solvent step may be omitted. In addition, do not rinse PE, PVC, and associated tubing with solvents.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number SA-7.1	Page 6 of 8
		Revision 3	Effective Date 09/03

- 1) Wash with soap and water
- 2) Rinse with tap water
- 3) Rinse with deionized water

Note: In situations where oil, grease, free product, other hard to remove materials are encountered probes and exposed tapes should be washed in hot soapy water.

5.2.1.3 Miscellaneous Equipment

Miscellaneous equipment including analytical equipment (water quality testing equipment) should be cleaned per manufacturer's instructions. This generally includes wiping down the sensor housing and rinsing with tap and deionized water.

Coolers/Shipping Containers employed to ship samples are received from the lab in a variety of conditions from marginal to extremely poor. Coolers should be evaluated prior to use for

- Structural integrity Coolers missing handles or having breaks within the outer housing should be removed and not used. Notify the laboratory that the risk of shipping samples will not be attempted and request a replacement unit.
- Cleanliness As per protocol only volatile organic samples are accompanied by a trip blank. If a
 cooler's cleanliness is in question (visibly dirty/stained) or associated with noticeable odors it should
 be decontaminated prior to use.
 - 1) Wash with soap and water
 - 2) Rinse with tap water
 - 3) Dry

If these measures fail to clean the cooler to an acceptable level, remove the unit from use as a shipping container and notify the laboratory to provide a replacement unit.

5.2.2 Down-Hole Drilling Equipment

This includes any portion of the drill rig that is over the borehole including auger flights, drill stems, rods, and associated tooling that would extend over the borehole. This procedure is to be employed prior to initiating the drilling/sampling activity, then between locations.

- 1) Remove all soils to the extent possible using shovels, scrapers, etc. to remove loose soils.
- Through a combination of scrubbing using soap and water and/or steam cleaning remove visible dirt/soils.
- 3) Rinse with tap water.
- 4) Rinse equipment with pesticide grade isopropanol
- 5) To the extent possible allow components to air dry.
- 6) Wrap or cover equipment in clear plastic until it is time to be used.

5.2.3 Soil/Sediment Sampling Equipment

This consists of soil sampling equipment including but not limited to hand augers, stainless steel trowels/spoons, bowls, dredges, scoops, split spoons, Macro Core samplers, etc.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number SA-7.1	Page 7 of 8
		Revision 3	Effective Date 09/03

- 1) Remove all soils to the extent possible.
- 2) Through a combination of scrubbing using soap and water and/or steam cleaning remove visible dirt/soils.
- 3) Rinse with tap water.
- 4) Rinse equipment with pesticide grade isopropanol
- 5) Rinse with deionized water
- 6) To the extent possible allow components to air dry.
- 7) If the device is to be used immediately, screen with a PID/FID to insure all solvents (if they were used) and trace contaminants have been adequately removed.
- 8) Once these devices have been dried wrap in aluminum foil for storage until it is time to be used.

5.3 Contact Waste/Materials

During the course of field investigations disposable/single use equipment becomes contaminated. These items include tubing, trowels, PPE (gloves, overboots, splash suits, etc.) broken sample containers.

With the exception of the broken glass, single use articles should be cleaned (washed and rinsed) of visible materials and disposed of as normal refuse. The exception to this rule is that extremely soiled materials that cannot be cleaned should be containerized for disposal in accordance with applicable federal state and local regulations.

5.3.1 Decontamination Solutions

All waste decontamination solutions and rinses must be assumed to contain the hazardous chemicals associated with the site unless there are analytical or other data to the contrary. The waste solution volumes could vary from a few gallons to several hundred gallons in cases where large equipment required cleaning.

Containerized waste rinse solutions are best stored in 55-gallon drums (or equivalent containers) that can be sealed until ultimate disposal at an approved facility. These containers must be appropriately labeled.

5.4 Decontamination Evaluation

Determining the effectiveness of the decontamination process will be accomplished in the following manner

- Visual Evaluation A visual evaluation will be conducted to insure the removal of particulate matter. This will be done to insure that the washing/rinsing process is working as intended.
- Instrument Screening A PID and/or an FID should be used to evaluate the presence of the contaminants or solvents used in the cleaning process. The air intake of the instrument should be passed over the article to be evaluated. A positive detection requires a repeat the decontamination process. It should be noted that the instrument scan is only viable if the contaminants are detectable within the instruments capabilities.

Subject DECONTAMINATION OF FIELD EQUIPMENT	Number SA-7.1	Page 8 of 8
	Revision 3	Effective Date 09/03

- Rinsate Blanks It is recommended that Rinsate samples be collected to
 - Evaluate the decontamination procedure representing different equipment applications (pumps versus drilling equipment) and different decontamination applications.
 - Single use disposable equipment The number of samples should represent different types of equipment as well as different Lot Numbers of single use articles.

The collection and the frequency of collection of rinsate samples are as follows:

- Per decontamination method
- Per disposable article/Batch number of disposable articles

It is recommended that an initial rinsate sample be collected early in the project to ensure that the decontamination process is functioning properly and in an effort to avoid using a contaminated batch of single use articles. It is recommended that a follow up sample be collected during the execution of the project to insure those conditions do not change. Lastly, rinsate samples collection may be driven by types of and/or contaminant levels. Hard to remove contaminants, oils/greases, some PAHs/PCBs, etc. may also support the collection of additional rinsates due to the obvious challenges to the decontamination process. This is a field consideration to be determined by the FOL.

ATTACHMENT X OSHA POSTER

Job Safety and Health It's the law!

EMPLOYEES:

- You have the right to notify your employer or OSHA about workplace hazards. You may ask OSHA to keep your name confidential.
- You have the right to request an OSHA inspection if you believe that there are unsafe and unhealthful conditions in your workplace. You or your representative may participate in that inspection.
- You can file a complaint with OSHA within 30 days of retaliation or discrimination by your employer for making safety and health complaints or for exercising your rights under the OSH Act.
- You have the right to see OSHA citations issued to your employer. Your employer must post the citations at or near the place of the alleged violations.
- Your employer must correct workplace hazards by the date indicated on the citation and must certify that these hazards have been reduced or eliminated.
- You have the right to copies of your medical records and records of your exposures to toxic and harmful substances or conditions.
- Your employer must post this notice in your workplace.
- You must comply with all occupational safety and health standards issued under the OSH Act that apply to your own actions and conduct on the job.


EMPLOYERS:

- You must furnish your employees a place of employment free from recognized hazards.
- You must comply with the occupational safety and health standards issued under the OSH Act.

This free poster available from OSHA – The Best Resource for Safety and Health

OSHA

Occupational Safety and Health Administration U.S. Department of Labor



Free assistance in identifying and correcting hazards or complying with standards is available to employers, without citation or penalty, through OSHA-supported consultation programs in each state.

1-800-321-OSHA

www.osha.gov

OSHA 3165-12-06R

APPENDIX B—WASTE MANAGEMENT PLAN

Waste Management Plan Middle River Complex Middle River, Maryland

Prepared for:
Lockheed Martin Corporation
Prepared by:
Tetra Tech, Inc.

Michael Martin, P.G. Regional Manager

Milal Mart

April 2012

TABLE OF CONTENTS

Sect	ion		Page
1	PUR	RPOSE	1-1
2	RES	SPONSIBILITIES AND TRAINING REQUIREMENTS	2-1
3	HAZ	ZARDOUS WASTE DETERMINATION AND PROCESS	3-1
4	SHIF	PPING REQUIREMENTS	4-1
	4.1	PRE-SHIPMENT REQUIREMENTS4.1.1 Packing	
		4.1.2 Labeling	
		4.1.3 Storing	
		4.1.4 Material Identification and Classification	4-3
		4.1.5 Waste Shipment	4-3
	4.2	SHIPPING REQUIREMENTS	4-4
	4.3	POST-SHIPMENT REQUIREMENTS	4-4
5	REP	PORTING REQUIREMENTS	5-1
	5.1	BIENNIAL REPORTING REQUIREMENTS	5-1
	5.2	WASTE MINIMIZATION	5-2
		APPENDICES	
APP	ENDIX	(A—WASTE IDENTIFICATION AND CLASSIFICATION FORM	
APP	ENDIX	(B—HAZARDOUS WASTE MANIFEST SIGNATURE AUTHORIZATION FORM	
APP	ENDIX	C—HAZARDOUS MATERIAL/WASTE SHIPMENT CHECKLIS	т
APP	ENDIX	C D—DRUM INVENTORY FORM	
APP	ENDIX	(E—SITE CONTACT SHEET	
APP	ENDIX	(F—EESH REMEDIATION OPERATING PROCEDURE NO: ER EESH REMEDIATION WASTE MANAGEMENT	OP-03,

LIST OF FIGURES

Figure 1-1	Site Location Map Middle River Complex	1-3
Figure 4-1	Middle River Complex Investigation Derived Waste Storage Area	4-6

ACRONYMS

CFR Code of Federal Regulations
COMAR Code of Maryland Regulation

EESH Energy, Environment, Safety, and Health

HAZWOPER hazardous waste operations IDW Investigation-derived waste

LMCPI Lockheed Martin Corporation Properties, Inc.

Lockheed Martin Corporation

MDE Maryland Department of the Environment
MDOT Maryland Department of Transportation

MRC Middle River Complex

OERR Office of Emergency Remedial Response

OSHA Occupational Safety and Health Administration

PPE personal protective equipment

Tetra Tech, Inc.

TSD treatment, storage, and disposal

USDOT United States Department of Transportation

USEPA United States Environmental Protection Agency

This page intentionally left blank.

Section 1 Purpose

On behalf of Lockheed Martin Corporation (Lockheed Martin), Tetra Tech, Inc. (Tetra Tech) has prepared this *Waste Management Plan* to address management of the potentially contaminated nature of the waste that will be generated as part of field investigations at the Lockheed Martin Middle River Complex (MRC) (Figure 1-1). Both solid- and liquid-waste will be generated and handled as investigation-derived waste (IDW). Following proper IDW procedures, the IDW generated will be collected in U.S. Department of Transportation- (USDOT)-approved steel drums, stored at a designated on-site location (considered a temporary satellite accumulation area), sampled for waste profiling and characterization and, once characterized, disposed of off-site at a Lockheed Martin-approved facility. The IDW generated during these field investigations will include but is not limited to soil, sediment, and water (surface, groundwater, purge and/or decontamination water).

A Tetra Tech geologist will be on-site for all MRC field activities. All work by any subcontractor will be directed by the Tetra Tech geologist and will fully comply with Maryland Department of Transportation (MDOT) and other local, state, and federal regulations, including the federal Resource Conservation Recovery Act, Toxic Substances Control Act, Occupational Safety and Health Administration (OSHA) regulation 1910.120, and Lockheed Martin's EROP-03 procedure. In addition, IDW will be handled in accordance with the U.S. Environmental Protection Agency (USEPA) guidance *Management of Investigation-Derived Wastes During Site Inspections* [USEPA Office of Emergency Remedial Response (OERR) directive 9345.3-02, May 1991].


This plan is organized as follows:

<u>Section 2—Responsibilities and Training Requirements:</u> Presents the requirements and responsibilities of Tetra Tech and their appointed subcontractor,

<u>Section 3—Hazardous Waste Determinations:</u> Briefly describes how the determination of waste characterization is completed, and

<u>Section 4—Shipping Requirements:</u> Details pre-shipment, shipping, and post-shipping requirements.

<u>Section 5—Reporting Requirements:</u> Details biennial reporting and waste minimization requirements.



Map Document: (K:\GProject\middle_river\Maps\Tax Blocks_26Jan10.mxd) 1/26/2010 -- 10:53:39 AM

Responsibilities and Training Requirements

All Tetra Tech personnel and subcontractors must be trained in accordance with all state and federal protocols. All personnel will complete the appropriate OSHA hazardous waste operations (HAZWOPER) training and annual refresher training, as specified in 29 *Code of Federal Regulations* (CFR) §1910.120. All subcontractor training certifications shall be provided electronically to the Lockheed Martin project lead. Certificates for Tetra Tech personnel are maintained internally and can be provided to Lockheed Martin upon request.

U.S. Department of Transportation HAZMAT Employee training is required for anyone involved in the shipment, preparation, offering for transport, and transportation of hazardous waste, including signing hazardous waste manifests (see 49 CFR 172, Subpart H). The waste management subcontractor will have completed HAZMAT employee training and will renew the training as necessary to meet USDOT requirements for transporting hazardous waste. Facilities that generate more than 1,000 kilograms per month of hazardous waste must comply with the emergency preparedness and personnel training requirements outlined in 40 CFR §265.16 (see 40 CFR §262.34(a)(4)). This training is intended for the waste generator's (i.e., Lockheed Martin) contractors (i.e., Tetra Tech) and includes training by a person qualified in hazardous waste management and emergency response procedures.

This page intentionally left blank.

Hazardous Waste Determination and Process

Hazardous waste determinations shall be made in accordance with 40 CFR 262.11, combining process knowledge and/or analytical evaluation of waste samples. Hazardous waste determinations shall be reevaluated whenever any of the following occurs:

- the process that produces the waste changes (e.g. a new chemical constituent is discovered, the treatment process changes)
- the treatment media changes (e.g., new media vendor or media type)
- waste was tainted by inadvertent mixing with another waste
- a change occurs in the hazardous waste regulations

Waste generated during field investigations will include, but is not limited to, soil, sediment, water (surface, groundwater, purge, and/or decontamination water), and/or disposable personal protective equipment (PPE). PPE IDW will be brushed off, placed in trash bags, and disposed of in a facility trash receptacle designated by MRC personnel. IDW generated during field activities will be segregated into drums based upon historical data (as applicable), labeled to indicate the wells and/or locations from which the waste was generated, and the generation date. IDW generated during this activity will be further characterized and disposed of in accordance with the state regulations, unless state requirements are less stringent than federal requirements, in which case the federal requirements will apply.

When available, analytical data obtained during the investigations will be provided to the subcontractor for IDW classification (i.e., non-hazardous versus hazardous). IDW materials that will be generated at the MRC during future sampling events are not expected to be characterized as hazardous, since IDW generated during previous sampling events was classified as non-hazardous. All analytical data shall be presented to the IDW subcontractor for them to classify

the IDW generated from the field project. Based on the analytical data, the IDW subcontractor will determine whether additional IDW sampling is required to complete the waste profiles. If additional sampling is required for waste characterization parameters, Tetra Tech will schedule a site visit and oversee the sampling conducted by the IDW subcontractor.

Following receipt of the approved analytical data, the IDW subcontractor shall develop a waste profile. Waste profiles are to be sent to the Tetra Tech project manager for initial review. The Tetra Tech project manager will review them and forward the waste profile forms to the appropriate site contact. All forms related to IDW from the MRC will be signed and approved by Mr. Mike Musheno of Lockheed Martin Corporation Properties, Inc. (LMCPI) at the MRC.

The Waste Listing Assessment form is presented in Appendix A. The Tetra Tech project manager will complete this form as the first step in IDW classification/removal process. This form is the first notification and is presented to the managing contractor for review. The form presents pertinent information such as the project name, waste description, generation date, type, and classification information.

Lockheed Martin may choose to issue a Lockheed Martin Hazardous Waste Manifest Signatory Authorization Form (see Appendix B). This form authorizes a Lockheed Martin subcontractor to sign for the IDW. The authorization certifies that the representative signing on behalf of Lockheed Martin has completed the appropriate USDOT training (as delineated at 49 CFR Part 172, *et seq.*) to sign hazardous waste manifests and is in compliance with all state and federal requirements for hazardous waste manifesting. Lockheed Martin shall remain responsible and liable for the hazardous waste being disposed of, regardless of the signatory authorization on the form.

After Lockheed Martin or an authorized representative signs the waste profile forms, the IDW is scheduled for removal from the site. The Tetra Tech project manager will coordinate the IDW removal with the appropriate Lockheed Martin site contact. The Lockheed Martin site contact (or their authorized representative) shall be on-site to sign bills of lading (for non-hazardous IDW) or hazardous waste manifests (for hazardous IDW). Signed copies of the returned bills of lading and hazardous waste manifests will be kept on file for a minimum of three years. The signed documentation for transporting the waste off-site will be properly filed and available for review upon request.

Before IDW leaves the site, the Lockheed Martin site contact or their authorized representative will complete a waste shipment checklist. The Hazardous Material/Waste Shipment Checklist is presented in Appendix C for reference. Completion of the checklist assures that all protocols, standards, and requirements have been adhered to and the waste can be properly removed from the site. The checklist covers various items to ensure the truck is fitted with the proper waste placards, is properly constructed with double walled containment, and the waste manifests and bills of lading contain the proper information. IDW is removed from the site subsequent to the Lockheed Martin representative completing the checklist. Both the Lockheed Martin representative and the Tetra Tech geologist then receive a copy of the associated paperwork. Tetra Tech will record the drums on a master Drum Inventory form for each site (see Appendix D).

A Site Contact List is presented in Appendix E as a reference in case of an emergency, or if questions arise with regards to IDW disposal. The emergency contingency plan has been incorporated into the on-site health and safety plan and will comply with all current and applicable regulations and requirements including, but not limited, to OSHA 29 CFR 1903, 1904, 1910, and 1926. Lockheed Martin Corporation will be listed as the waste generator on all paperwork, including the waste profile sheets on which the generator was initially listed as "Middle River Complex." The areas of Lockheed Martin investigations at MRC, including the "Tax Block" sites, are identified for purposes of waste disposal by USEPA ID number MDR000524413.

This page intentionally left blank.

Section 4

Shipping Requirements

4.1 PRE-SHIPMENT REQUIREMENTS

Waste generated during the field investigation will include, but is not limited to soil, sediment, and water (groundwater, surface, purge, and/or decontamination water). IDW generated during previous investigations has been characterized as non-hazardous. Pre-shipping requirements were discussed in detail in Section 3.0.

4.1.1 Packing

All waste materials will be collected in new or reconditioned USDOT-approved 55-gallon drums that will be sealed at the end of each day's sampling activities. Special consideration will be given to manage certain wastes (e.g., bentonite grout) separately from other IDW, to avoid increasing the volume of material that may be classified as hazardous due to elevated pH.

4.1.2 Labeling

Drums will be marked with the appropriate "Hazardous" or "Nonhazardous" labels containing the following information:

- Site will list the name of the site where waste was generated (i.e., Middle River Complex)
- **Location** will list the location where the waste was generated (i.e., well identification, soil boring, test pit, sediment and surface water location number)
- **Date** will include the date when waste materials accumulation began
- **Drum Number** will list the number of the drum in the series of drums from this sampling event
- **Contents** will list the waste that was generated (i.e., sediment, soil, and water)
- Volume will list an estimated volume not to exceed three quarters of the drum capacity and

• **Site Contact and Emergency Contact Information** will list the contact information for the designated authorized Lockheed Martin representative for the site and the telephone number of the local fire department.

4.1.3 Storing

Investigation derived waste storage areas will meet the following specifications to permit access to the drums and conduct spill/leak monitoring, sampling, and extraction (once the disposal route is determined):

- drums will be placed on a hard flat surface designated by the facility
- drum labels will be attached to each drum and will include the information presented in Section 4.1.2
- keep the retaining bolt and label readily visible on the outside of storage containers
- provide at least four feet between each row of pallets/drums to allow access to the containers for sampling, drum removal, and spill response
- maintain on-site a copy of work plans, waste disposal forms, and the IDW inventory list, and provide this information to the project manager at the end of each shift
- maintain spill response equipment at the site in case it is required
- whenever possible, use appropriate equipment for moving containers to avoid injury to the worker or damage to the container, when that is not possible, obtain help to manipulate containers
- Monitor and maintain all storage containers weekly to ensure that the containers remain in their original condition and that no leaks or spills have occurred. Weekly inspections should be documented in a dedicated field notebook and should include photographs of the containers and storage area.

The MRC's IDW drum storage area is on a flat concrete area in Lot D (Figure 4-1), inside the secured facility boundary. An alternate IDW storage area may be used to minimize transportation of drums on site, due to the dispersed nature of sampling locations throughout the MRC. MRC IDW storage areas will be determined by Lockheed Martin personnel at the start of field activities.

If any drums are classified as hazardous based on the waste characterization samples, the following additional measures will be instituted:

• A temporary spill containment system, constructed of polyethylene sheeting and 2-inch × 6-inch boards creating a bermed edge, will be placed under the drums to contain spilled or leaked materials. The dimensions of the temporary spill containment area will

depend on the number of 55-gallon drums at the site. For most jobs, the spill containment area is estimated to be 10-feet \times 20-feet. Containment system integrity will be monitored periodically.

- The drums will be placed on self-containing plastic secondary containment pallets with four (or fewer) drums per pallet. Self-containing pallets will be stored on a hard flat surface covered with polyethylene sheeting. These pallets will be capable of containing the entire contents of one 55-gallon drum. All hazardous IDW drums will be stored on secondary containment until they can be removed from the site.
- Caution tape and/or temporary fencing will be placed around the drums to identify and secure the area.
- Signs will be posted in front of the IDW storage area identifying the site, location, collection date, number of drums, drum contents, volume of contents, site and emergency contact information, and the location of spill control materials for the wastes.
- Inform appropriate authorities/organizations of hazardous waste on-site and emergency response procedures. Identify the emergency coordinator and document emergency planning for the site.

Lockheed Martin has 90 days to remove the non-hazardous- and/or hazardous waste drums from the facility. Access for the subcontractor's representative and IDW transport carrier will be coordinated by Tetra Tech.

4.1.4 Material Identification and Classification

All waste materials shall be identified and classified per USDOT requirements.

4.1.5 Waste Shipment

Tetra Tech will subcontract all IDW removal to an approved vendor(s). In the event hazardous waste is encountered, Tetra Tech will ensure the use of Lockheed Martin Corporate Purchasing Agreements and the associated list of Corporate Approved Waste Management Vendors, to ensure that the waste is transported by an approved vendor to a treatment, storage, and disposal (TSD) facility listed on the Lockheed Martin Corporate Hazardous Waste Approved Vendors List. Non-hazardous waste shall be transported to an approved industrial waste disposal facility, but it does not have to be managed by corporate-approved waste management vendors. Attachment D is the Lockheed Martin Hazardous Waste Manifest Signatory Authorization Form, which must be filled out by the Lockheed Martin project lead in coordination with the Tetra Tech project manager if the IDW is hazardous.

4.1.5.1 Hazardous Waste Generator Identification Number

The Lockheed Martin USEPA identification number for hazardous waste generation at MRC is MDR000524413. All IDW will be removed from the site by a subcontractor adhering to the shipping requirements in Section 4.2.

4.2 SHIPPING REQUIREMENTS

United States Department of Transportation HAZMAT Employee training is required for anyone involved in shipment preparation, offering for transport, and transportation of hazardous waste, including signing hazardous waste manifests (see 49 CFR 172, Subpart H).

Certification and accuracy verification of the physical waste shipment against the manifested waste shipment must be provided. Non-hazardous materials do not require the signature of a USDOT HAZMAT trained individual. A bill of lading will be signed for all non-hazardous waste. A hazardous waste manifest will be signed for all hazardous waste.


For non-hazardous waste, Tetra Tech will use Lockheed Martin's Hazardous Material/Waste Shipment Checklist (see Appendix B) during the preparation and pre-transport review of waste shipments, and will submit a completed electronic copy to the Lockheed Martin project lead along with the shipping documentation. Detailed records of authorized work will be maintained by the subcontractor including:

- all manifests of waste transported to the approved off-site disposal facility
- receipts that the waste has been accepted by the approved treatment/disposal facility
- certification that the waste has been disposed of at the approved facility
- receipts that waste containers have been received by the approved disposal facility
- certification of the disposal of waste containers by the approved disposal facility
- weigh slips
- any other documentation required by local, state, or federal requirements

4.3 POST-SHIPMENT REQUIREMENTS

Records of waste characterization, chain of custody, transportation, and destruction will be scanned and electronically submitted to the Lockheed Martin project lead for records retention. This includes

profile sheets, the Hazardous Material/Waste Checklist, the generator's copy of the waste manifest, a copy of the signed TSD manifest, Land Disposal Restriction forms, and certificates of waste destruction (where applicable). All records of monitoring events will be submitted for each year's waste generation activities in the first quarter of the following year, or per the project lead's direction. The documentation noted above must be retained for three years. All documents should be properly stored and available for review upon request.



Section 5

Reporting Requirements

5.1 BIENNIAL REPORTING REQUIREMENTS

The Code of Maryland Regulations (COMAR) 26.13.03.06B requires facilities that manage hazardous waste to file a Biennial Report once every two years which includes hazardous waste activity for the preceding calendar. Facilities are required to submit the Biennial Report, for a given site, if:

1. Either:

- a. They generate hazardous waste and ship it off-site to a facility in the United States; or
- b. They treat, store or dispose of hazardous waste on-site: and
- 2. They are regulated under Maryland's hazardous waste regulations by:
 - a. Generating 220 pounds or more of hazardous waste, or more than 2.2 pounds of acute hazardous waste, in a calendar month; or
 - b. Accumulating, art any time, more than 220 pounds of hazardous waste or more than 2.2 pounds of acute hazardous waste.

Guidance for completing the Biennial Report form is available at the Maryland Department of the Environment's (MDE) Biennial Report web page, which is available at http://www.mde.state.md.us/Programs/LandPrograms/Hazardous_Waste/home/index.asp.

The report must be completed and filed, typically by March 1 of even numbered years (e.g. 2010, 2012) with the:

Maryland Department of the Environment Technical Services and Operations Program 1800 Washington Boulevard, Suite 610 Baltimore, Maryland 21230-1719

Before each report is filed, the Maryland hazardous waste regulations must be consulted to confirm or update regulatory thresholds.

5.2 WASTE MINIMIZATION

Hazardous waste generators, when preparing a manifest, are required to certify they have taken steps to minimize the volume and toxicity of hazardous waste generated. Waste minimization efforts are required under COMAR 26.13.03.06B(1)(d)(vi) to be reported on the Biennial Report submittal.

Efforts should be taken, to the degree economically practicable, to reduce the volume and toxicity of hazardous waste generated and a reasonable method of treatment, storage, or disposal should be selected which will minimize the present and future threat to human health and the environment.

APPENDIX A — WASTE IDENTIFICATION AND CLASSIFICATION FO	RM

7650 TETRA TECH: LOCKHEED MARTIN, 2012 WASTE MANAGEMENT PLAN FOR MIDDLE RIVER COMPLEX

	Waste Identificati	on and Classification Form	
LMC Remediation Project Description of Waste Generic Name		State Generated Solid, Liquid, Gas Additional Info.	
Date of Waste Generation		Ongoing (Y/N)?	
Description of Process Generating Wa	ıste		
Listed Waste ? (Y/N) Justification for Waste Classification (F,K, P or U Codes, if app attach support documentation)	olicable	
Completed Comp			

APPENDIX B — HAZARDOUS WASTE MANIFEST SIGNATURE AUTHORIZATION FORM

Lockheed Martin Hazardous Waste Manifest Signatory Authorization

This Authorization Agreement, effective for the remediation site and period of performance written below, is entered into by and between:

LOCKHEED MARTIN CORPORATION (hereinafter "Lockheed Martin"), having a business office at 6801 Rockledge Drive, Bethesda, Maryland 20817

USA, and incorporated in the State of Maryland, and

cori, and meorporated in the state of	
(hereinafter "	")
having a business office at	
WHEREAS, (company) will sign Haza	(company representative) of ardous Waste Manifests on behalf of
	hazardous waste, as defined at 40 CFR Pt.
261 et seq. indicated below.	
Remediation Site:	
Site Address:	
Period of Performance:	
Hazardous Waste Description:	
Hazardous Waste Disposal Facility a	nd Location:

This Authorization Agreement certifies that the representative signing on behalf of Lockheed Martin has taken the appropriate Department of Transportation training, as delineated at 49 CFR Part 172 *t seq.* to sign Hazardous Waste Manifests and is in compliance with all state and federal requirements for hazardous waste manifesting.

Lockheed Martin shall remain responsible and liable for the hazardous waste being disposed regardless of the Signatory Authorization provided herein.

LOCKHEED MARTIN CORPORATION	
By:	Ву:
Name:	Name:
Title:	Title:
Date:	Date:

APPENDIX C — HAZARDOUS MATERIAL/WASTE SHIPMENT CHECKLIST

Lockheed Martin Hazardous Material/Waste Shipment Checklist

Pr	nte: oject Site Name: iipping Document No.:
A.	DESCRIPTION A1 UN/NA Identification Number, Proper Shipping Name, Hazard Class/Division Number, Packing Group A2 Subsidiary hazard class(es) or division number(s), if any, in parenthesis A3 Total Quantity of Material A4 24-Hour Emergency Phone Number and Response Information ERG No.: A5 Page of Pages, for multiple shipping papers/EPA Manifest/Air Decs. A6 Shipper's Certification, as applicable A7 Small Quantity Exception/Dangerous Goods In Excepted Quantities/Diagnostic Specimen/Sample
B.	ADDITIONAL DESCRIPTIONS - GENERAL B1.
	MARKING FOR NON-BULK PACKAGINGS C1. Proper Shipping Name, UN/NA Identification Number C2. (technical name) C3. (EPA waste identification number) C4. "RQ" C5. Exemption Packagings "DOT-E-ex.#" C6. Consignee's Name & Address C7. Net or Gross quantity for non-rad Dangerous Goods (adjacent to PSN & UN#) C8. Ltd. Qty - PSN only per 172.301(a)(1) or UN ID# placed in square-on-point border per 172.315 C9. Package Orientation Arrows, for liquids in inner packagings C10. "Inhalation Hazard", unless these words appear on the label prescribed in 172.416 or 172.429 C11. "Overpack" adjacent to proper shipping name marking [see 173.25(a)(4)] C12. TSCA PCB Marking (for actual or source concentration greater than or equal to 50 ppm *) (* Note Potential Vehicle Marking Requirements in 40 CFR 761.40)
D.	MARKING FOR BULK PACKAGINGS (DUMP TRUCKS OR ROLL-OFFS) D1 UN/NA Identification Number on orange panel or placard or white square-on-point display configuration as prescribed by 172.302 and 172.332
E.	LABELING E1 Primary Hazard Label(s): E2 Subsidiary Hazard Label(s) with class/division: E3 Hazardous Wastes Label(s)
F.	PLACARDING F1. 172.504 Table 1 Materials - Any Amount F1.1 Dangerous When Wet (4.3) F1.2 Poison (6.1, Inhalation Hazard, Zone A or B)* (Primary or Subsidiary (*Materials subject to the "Poison-Inhalation Hazard" notation must be placarded with a POISON INHALATION HAZARD or POISON GAS placard, as appropriate, and also placarded for any other hazard class required for that material in 172.504) F1.3 Radioactive (7, LSA/SCO Exclusive Use Shipments) F2. 172.504 Table 2 Materials - 1,001 lb:

Page 1 of 2 March 2009

Lockheed Martin Hazardous Material/Waste Shipment Checklist

	pleted By:	Company:	Date:
	H5NRC Manifest #540 for radioactive	e waste shipment for land dispo	sal.
	H2 Radioactive Excepted Package s H3Limited Quantity Radioactive Mat H4 Health Physics Information	tatement per 10.8.8.3.3 on Airw erial for multiple hazard limited	ay Bill quantity Class 7.
	H1 Instructions for Maintenance of E	xclusive Use Shipments	
15.	PAPERWORK AND MISCELLANEOUS ITE	EMS	
14.	I4.1 Radioactive (7, LSA/SCO Exclusion		
14	I3.3. "Radioactive Material, Excepted F PLACARDING (172.504 TABLE 1 MATERI	Package" handling label	
	I3.2 "EMPTY" Label	5 I III III III	
	I3.1 Radioactive Labels I3.2 "EMPTY" Label		
I3.	LABELING	on Typo A	
	I2.5 "USA" on all IP and Type A packa I2.6 Packaging manufacturer marking	agings Lon Type A	
	I2.4 IP-1, IP-2, IP-3 markings		
	I2.3 Package Certification Number, for	or radioactive material packages	r, as appropriate
	I2.2 "Radioactive"; "Radioactive – LS	A"; "Radioactive – SCO"	
ıΖ.	I2.1Gross Weight, for radioactive mat) lb
เว	I1.6 "Exclusive Use Shipment" MARKING FOR NON-BULK PACKAGINGS		
	I1.5 Fissile Excepted, if applicable		
	I1.4 Radioactive Labels I1.5 Fissile Excepted, if applicable		
	I1.3 Activity per Package	opoolal form	
	I1.1 Radionuclide Symbol(s), per 173. I1.2 Physical & Chemical Form, if not		
11.	SHIPPING PAPER DESCRIPTIONS	125	
	DITIONAL REQUREMENTS FOR RADIOAC	CTIVE MATERIAL SHIPMENTS	6
по.	s LINC Notification instructions		
H/. ⊔o	Z. Emergency Telephone Number Notif B. LMC Notification Instructions	ication, if required, see 172.604	(b)
H6.	Check Driver's Qualifications	institut if an arrival 1 470 001	(1-)
H5.	5 Vehicle Inspection		
H4.	Photograph, <i>if applicable</i>		
		atomont on racinage, rer rre. r	ompriorito, Dolla statement per 2.7.7.
H3	B Small Quantity/Excepted Quantity St	atement on Package for 173.4	shinments / DGFQ statement per 2.7.7
H1.	Shipping Paper/Hazardous Waste Market	anitest/Bill of Lading/Airway Bill/ isiya I Isa Shinmants	Shipper's Declaration
	PERWORK AND MISCELLANEOUS ITEMS		
G4.	I Loaded and Closed As Required		
G3	B Container Type: (Bulk Pkg) Loaded and Closed As Required		
	2 Container Type: (Outer Pkg)		
G2	Container Type: (Inner Pkg)		

APPENDIX D — DRUM INVENTORY FORM				



Tetra Tech NUS, Inc.

DRUM INVENTORY

PROJECT NAM	PROJECT NAME: PROJECT NUMBER:				
CLIENT:	CLIENT: LOCATION:				
Tt NUS PERSO	NNEL:			DATE (START):	
IDW CONTRAC	CTOR:			DATE (END):	
DRUM ID	GENERATION LOCATION			COMMENTS	
COMMENTS:					

APPENDIX E— SITE CONTACT SHEET	

Site Contact List

1) Tom Ambrose: Facilities Supervisor: Office: 410-682-1308

2) Steve Thompson: Facilities Manager: Office: 410-682-1304

3) Scott Lapp: Maintenance: Office: 410-682-0365

Cell: 410-967-8745

4) Mike Musheno: ESH / Projects: Office: 484-875-2819

5) John Wells: Lead Facilities Electrician: Work: 410-682-1307

6) Tom McVickers: Facilities Electrician: Office: 410-682-1307

7) A&A Environmental / Spill Response: 1-800-404-8037

8) Tony Apanavage: Project Manager: Office: 1-301-528-3021

Cell: 1-301-233-8230

9) Michael Martin: Program Manager: Office: 1-301-528-3022

Cell: 1-410-707-5259

10) Baltimore County Police & Fire Department: 911

11) State of Maryland Emergency Response Center: (410-974-3551)



Corporate Energy, Environment, Safety, & Health EESH Remediation Operating Procedure No: EROP-03

Effective: 04/17/2009 Revision No.: 4

Subject: EESH Remediation Waste Management

Ref:

- 1. Code of Federal Regulations, Title 40, Parts 260, 261, 262, 264, 265, 268, 761, and 763
- 2. Code Federal Regulations, Title 49, Parts 100 through 180
- 3. Corporate Functional Procedure No: ESH-06
- 4. Corporate Functional Procedure No: ESH-08
- 4. Corporate Policy Statement 527

1.0 Purpose

This procedure establishes practices for management and transportation of solid and hazardous waste (waste in this context also refers to DOT hazardous materials) generated at remediation project sites in a manner that complies with Subtitle C of the. Resource Conservation and Recovery Act (RCRA), Department of Transportation (DOT) regulations, and similar state and/or host country waste regulations. Additionally, this procedure ensures waste disposal is managed in accordance with Corporate Functional Procedure <u>ESH-06</u> and <u>ESH-08</u>, and records retained in accordance with <u>Corporate Policy Statement 527</u>.

2.0 Applicability

This procedure applies to the Energy, Environment, Safety and Health (EESH) Remediation Organization (the Organization) and to the remediation projects for which the Organization has waste management responsibility. Each member of the Organization, including IWTA, contractor staff and, where applicable, support organizations (e.g. Global Supply Chain Management), is responsible for execution of this procedure.

The materials to which this practice applies are solid wastes generated as a result of remediation project activities, including such things as investigation derived waste, environmental sampling, treatment of contaminated media, and routine operations and maintenance, unless such solid waste is exempt under applicable regulations.

3.0 Key National Agreement

Waste management requirements shall be included within the EESH Key National Agreements (KNA). The KNA establishes the requirements under which Remediation Contractors perform work for Lockheed Martin.

The KNA will stipulate that the Remediation Contractor shall comply with Lockheed Martin waste management, transportation, and disposal requirements and all applicable state, federal, and/or host country laws and regulations.

4.0 Statement of Work Requirements

4.1 Waste Management Plan

All remediation project statements of work that include the generation of solid waste, excluding office trash (e.g. food wastes, consumer packaging) that may be disposed of at a municipal solid waste facility, shall include a requirement for the waste management contractors (i.e. Remediation Contractors and/or Corporate Approved Waste Management Vendors) to submit a waste management plan to Lockheed Martin. A site specific waste management plan shall be prepared that identifies all potential solid waste streams that may reasonably be expected to be generated or discovered during project activities. The plan will address the required elements listed below; however, if the waste is determined to be non-hazardous following completion of Element A, then only the additions of Elements D and E are required.

Element A) Hazardous Waste Determination

- i) Listing assessment (See Attachment #1 Waste Listing Assessment Form)
- ii) Characteristic determination

Hazardous waste determinations shall be made in accordance with 40 CFR 262.11 using a combination of process knowledge and/or analytical evaluation of waste sampling. Hazardous waste determinations shall be reevaluated whenever any of the following circumstances occur:

- A change in the process that produces the waste (e.g. a new chemical constituent is discovered, the treatment process changes);
- A change in the treatment media is made (e.g. new media vendor or media type);
- A waste was tainted by inadvertent mixing with another waste; or
- A change occurred to the hazardous waste regulations that apply to that waste.

Characteristic waste determinations based on analytical sampling shall be reevaluated at some reasonable frequency to verify the accuracy of the initial waste determination. The waste determination reevaluation frequency for ongoing remediation or treatment operations should be specified in the waste management plan and be profiled at least once a year.

Element B) Responsibilities and Training Requirements

i) Contractor staff responsibilities with regard to waste management and training requirements necessary to comply with Section 6.0 and all state, federal, and/or host country laws and regulations. Contractor training certifications shall be provided electronically to the Lockheed Martin Project Lead.

Element C) Pre-Shipment Requirements

- i) Material identification and classification per DOT requirements
- ii) Packaging, storage, segregation, marking, labeling, and accumulation of waste
- iii) Waste shipment documentation
 - (1) Hazardous Waste Generator Identification Number

- iv) Hazardous Material Transportation Plan
 - (1) Hazardous material transportation risk identification, prioritization, and mitigation plan
 - (2) Emergency Response (material information to be provided with shipments, actions to be taken in the event of an incident, staffing the emergency response phone number)
 - (3) Hazmat Security Plan (as required based on thresholds outlined in 49 CFR §172.800)
 - (4) Transportation and disposal logistics

Lockheed Martin Project Leads shall ensure the use of the Lockheed Martin Corporate Purchasing Agreements and the associated <u>Corporate Approved Waste Management Vendors</u> (WMV) for hazardous waste management and ensure that waste is transported to a treatment, storage, and disposal (TSD) facility on the <u>Lockheed Martin Corporate Hazardous Waste Approved Vendors List</u> as outlined in the ESH-06. Remediation contractors can contract directly with the WMV.

Additionally, hazardous waste manifests shall be signed only by a DOT trained and qualified Lockheed Martin employee or authorized designee (See Attachment #2 – Hazardous Waste Manifest Authorization Form). In addition to completing the Authorization Form, Project Leads shall verify that the designee is DOT trained and qualified to sign manifests and has adequate DOT experience. It is preferable to have contractors designated to sign that are involved in the waste characterization and oversight. For contractor personnel handling hazardous waste, appropriate hazardous waste handling training shall be provided by the contractor as outlined in Section 6.0 and complying with all state, federal, and/or host country laws and regulations.

Non-hazardous waste is not required to be managed by Corporate Approved Waste Management Vendors but shall be transported to an <u>approved industrial waste disposal facility</u> as outlined in ESH-06.

Within the United States, waste shall be characterized and disposed in accordance with the state regulations where it was generated unless the state requirements are less stringent than the federal requirements. For instance, California non-RCRA hazardous waste cannot be disposed of in a non-hazardous waste facility. Within a host country, waste shall be managed in accordance with the host country regulations; however, if the host country standards are less stringent than those of the US Environmental Protection Agency (EPA), than the EPA standards shall apply.

Element D) Shipping Requirements

- i) Manifest certification and accuracy verification of physical waste shipment against manifested waste shipment (for non-hazardous waste this may not be applicable)
 - (1) For hazardous waste, the contractor responsible for waste shipment shall utilize the Lockheed Martin Hazardous Material/Waste Shipment Checklist (see Attachment #3) during the preparation and pre-transport review of waste shipments and submit a completed electronic copy to the Lockheed Martin Project Lead with the shipping documentation.

ii) For non-specification bulk containers (e.g. dump trucks and roll-offs), the contractor responsible for waste shipment shall adhere to the Lockheed Martin requirements for packing and closing (see Attachment #4). These requirements are meant to supplement the applicable regulations.

Element E) Post Shipment Requirements - Records

i) Waste characterization, chain of custody, transportation, and destruction records shall be scanned and electronically submitted to the Lockheed Martin Project Lead for records retention. This shall include profile sheets, the Hazardous Material/Waste Checklist, the generator copy of the waste manifest, a copy of the TSD signed waste manifest, Land Disposal Restriction forms, and certificates of waste destruction where applicable. For finite-duration remediation projects, waste transportation and disposal records shall be submitted to the project lead at the completion of the project unless submittals are required by regulatory agencies on a more frequent basis. For recurring remediation project activities such as annual groundwater monitoring or groundwater treatment, these records shall be submitted for each year's waste generation activities in the first quarter of the following year or per the Project Lead's direction.

The waste management plan shall be submitted in a phased approach. The first section of the waste management plan will provide the hazardous listing assessment and the characteristic determination methodology (addressing Element A). This section of the plan shall be submitted in a timeframe that allows for Lockheed Martin's review prior to waste generation. Upon approval to proceed, the second section will document the waste profiling results and must be signed off on by a Lockheed Martin Project Lead. Additionally, it shall outline the logistics for waste handling, transportation and disposal (addressing Elements B through E). This section of the plan shall specify a reevaluation frequency for waste generated as a result of ongoing remediation or treatment operations.

Following the approval of the second section by the Lockheed Martin Project Lead, the waste management contractor shall implement the waste management plan. This plan shall be updated when the remedial treatment system process, waste stream, media, or regulations change.

4.2 Health and Safety Plan

For remediation sites managing waste, a section shall be included in the site Safety and Health Plan to address the safety and health requirements for managing the site specific waste.

4.3 Electronics and Scrap Metal Recycling

Where applicable and feasible, electronics and scrap metals shall be recycled or refurbished to the extent possible in accordance with ESH-06.

5.0 Responsibilities

5.1 Project Lead

The Project Lead shall:

- Ensure that all remediation projects for which they have responsibility have a waste management plan as outlined in Section 4.0. Review and ensure updates are completed as necessary. Plans must also be submitted to the Records Manager for upload to the Document Management System (DMS).
- Consult with Corporate EESH Legal as needed to verify the listing determination.
- Ensure that the Contractor has outlined the applicable training requirements and provided a training plan or statement of completion within the waste management plan.
- Verify that the site has a Hazardous Waste Generator Identification Number prior to hazardous waste shipments, where applicable.
- Ensure that all hazardous waste manifests are signed and certified by a Lockheed Martin employee or authorized designee. For non-hazardous waste, there are no signatory requirements for waste manifests.
- Ensure that non-hazardous or hazardous waste is shipped to an approved facility per ESH-06 and that the Corporate Approved Waste Management Vendors are being used for hazardous waste transportation, storage, and/or disposal services.
- Ensure receipt of the waste characterization, chain of custody, transportation, and destruction records, where applicable, and submit them to the Records Manager for upload to the DMS.
- Ensure that the required regulatory and state hazardous waste reports are submitted (e.g. biennial waste reports).

5.2 Remediation Global Supply Chain Management Representative

The Global Supply Chain Representative shall:

- Ensure that the KNA includes the requirements defined in Section 3.0.
- Send the Remediation Contractors an updated version of the approved non-hazardous facility list quarterly.
- Send the Corporate Approved Waste Management Vendors an updated version of the Lockheed Martin Corporate Hazardous Waste Approved Vendors List quarterly.

5.3 Corporate EESH Legal

The Corporate EESH Legal Counsel shall:

- Provide the Project Lead with support when making listed waste determinations.
- Notify the Project Leads of regulation changes that would affect prior listing determinations.

6.0 Training Requirements

The EESH remediation staff training requirements are summarized in Table 1.

6.1 RCRA Hazardous Waste Handling and Emergency Procedures

RCRA Generator Status Facilities

Generators who generate more than 1,000 kg/month of hazardous waste (or more than 1 kg/month of acutely hazardous waste) must comply with the emergency preparedness and personnel training requirements outlined in 40 CFR §265.16 (see 40 CFR §262.34(a)(4)). This training is intended for all facility personnel including the generator's contractors and includes training by a qualified person on hazardous waste management and emergency response procedures. Personnel shall receive an annual refresher. Project Leads are responsible for ensuring this training is provided to contractor staff on remediation projects that meet this generator criterion. Contractor personnel training records must also be maintained by the Project Lead.

"Small quantity generators" who generate greater than 100 kg but less than 1000 kg/month of hazardous waste, must comply with the emergency preparedness and personnel training requirements at 40 CFR §262.34(d)(5). These generators "must ensure that all employees are thoroughly familiar with proper waste handling and emergency procedures, relevant to their responsibilities during normal facility operations and emergencies" (40 CFR §262.34 (d)(5)(iii)). Project Leads shall ensure that all contractor staff has had the appropriate hazardous waste handling and emergency procedure training on remediation projects that meet this generator criterion.

Federal training requirements do not apply to remediation projects that generate less than 100 kg/month of hazardous waste. However, Project Leads shall ensure that the contractor staff is familiar with hazardous waste handling and emergency procedure training appropriate for waste management.

RCRA Permitted or Interim Status Facilities

Permitted or interim status facilities must follow training requirements in accordance with 40 CFR §264.16 and 40 CFR §265.16, respectively (the same requirements apply as outlined in the first paragraph under Section 6.1).

Additional training may be required by state and/or host country hazardous waste regulations. Any such additional training shall be verified and implemented by the Project Lead.

6.2 Department of Transportation Training

Department of Transportation (DOT) Hazmat Employee training is required for a person involved in shipment preparation, offering for transport and transportation of hazardous waste, including signing of hazardous waste manifests (see 49 CFR 172, Subpart H). All Lockheed Martin Remediation representatives, designees, and/or waste management contractors shall complete the hazmat employee training and renew the training as necessary to meet DOT requirements for hazardous waste transportation.

6.3 OSHA HAZWOPER Training

All contractors working on Lockheed Martin remediation sites shall complete the appropriate OSHA hazardous waste operations (HAZWOPER) training and annual refresher training specified in 29 CFR §1910.120. Lockheed Martin employees managing projects where hazardous waste is generated shall complete the 24 hour OSHA HAZWOPER training and annual refresher training.

7.0 Deviations

All deviations from this procedure must have prior approval by the Director of Environmental Remediation. The approval shall be documented and uploaded to the DMS.

Table 1

EESH Remediation Staff Waste Management Training Matrix

Function	Task	Training Required	Requirements
EESH Remediation Employees (including IWTA and managing contractor staff (where the task description matches responsibilities))	Completing / Approving Waste Determinations	RCRA Generator Training	Refresher every 5 years
	Managing Remediation Sites where Hazardous Waste is Generated	OSHA HAZWOPER 24 HR	8 hr refresher annually
	Managing Hazardous Waste Shipments	DOT HazMat Certification (see Table 2)	Refresher every 3 years

The Lockheed Martin Project Lead shall update the Remediation Waste Management Training Matrix located on the <u>Remediation Process Asset Library</u> once training has occurred. All training and certification documentation will reside on the Remediation DMS under Training Records.

Table 2

EESH Remediation Staff DOT Requirements for Hazmat Employees		
Requirement	Completion Method	
General Awareness [49 CFR 172.704(a)(1)]	Vendor (e.g. Lions) provided Hazardous Materials Transportation Workshop DOT OJT (taught by EESH DOT SME)	
Function-Specific [49 CFR 172.704(a)(2)]	Vendor (e.g. Lions) provided Hazardous Materials Transportation Workshop DOT OJT (taught by EESH DOT SME)	
Safety [49 CFR 172.704(a)(3)]	 Vendor (e.g. Lions) provided Hazardous Materials Transportation Workshop DOT OJT (taught by EESH DOT SME) Hazwoper 24 Hour Training Site specific safety training [NOTE: This element of safety training may be fulfilled through completing any one (1) of the following three (3) options which provides the required site specific safety information: 1) Site Safety Plan Review, 2) Site HazCom/ General Employee Training or 3) Site Visitor Safety Briefing/Training. The source of the training must be entered as part of the information on the test which is administered for site specific safety training.] 	
Security Awareness [49 CFR 172.704(a)(4)]	Vendor (e.g. Lions) provided Hazardous Materials Transportation Workshop DOT OJT (taught by EESH DOT SME) Site specific security awareness training [NOTE: This element of security awareness training may be fulfilled through completing any one (1) of the following three (3) options which provides the required site specific security information: 1) Site Security Plan Review, 2) Site HazCom/General Employee Training or 3) Site Visitor Security Briefing/Training. The source of the training must be entered as part of the information on the test which is administered for site specific security training.]	
In-Depth Security (Hazmat Security Plan) Only applicable when haz material/waste meets certain class and volume thresholds (reference Section 4.1, Element C, iv, 4) [49 CFR 172.704(a)(5)]	Site Hazmat Transportation Security Plan Training	

The EESH DOT SME will certify EESH Remediation staff members as DOT Hazmat Employees on behalf of Lockheed Martin once training and safety and security tests have been completed.

Attachment #1

Waste Listing Assessment Form



Attachment #2

Hazardous Waste Manifest Signature Authorization Form



Attachment #3

Hazardous Material/Waste Shipment Checklist



Attachment #4

Non-Specification Bulk Container Packing and Closing Instructions



	Waste Identificati	on and Classification Form	
LMC Remediation Project Description of Waste Generic Name		State Generated Solid, Liquid, Gas Additional Info.	
Date of Waste Generation		Ongoing (Y/N)?	
Description of Process Generating Wa	ıste		
Listed Waste ? (Y/N) Justification for Waste Classification (F,K, P or U Codes, if app attach support documentation)	olicable	
Completed Comp			

Lockheed Martin Hazardous Waste Manifest Signatory Authorization

This Authorization Agreement, effective for the remediation site and period of performance written below, is entered into by and between:

LOCKHEED MARTIN CORPORATION (hereinafter "Lockheed Martin"), having a business office at 6801 Rockledge Drive, Bethesda, Maryland 20817

USA, and incorporated in the State of Maryland, and

(hereinafter "	")
having a business office at	
WHEREAS, (company) will sign Ha	(company representative) of zardous Waste Manifests on behalf of
= 1	l hazardous waste, as defined at 40 CFR Pt.
261 et seq. indicated below.	
Remediation Site:	
Site Address:	
Period of Performance:	
Hazardous Waste Description:	
Hazardous Waste Disposal Facility	and Location:

This Authorization Agreement certifies that the representative signing on behalf of Lockheed Martin has taken the appropriate Department of Transportation training, as delineated at 49 CFR Part 172 *t seq.* to sign Hazardous Waste Manifests and is in compliance with all state and federal requirements for hazardous waste manifesting.

Lockheed Martin shall remain responsible and liable for the hazardous waste being disposed regardless of the Signatory Authorization provided herein.

LOCKHEED MARTIN CORPORATION	
By:	Ву:
Name:	Name:
Title:	Title:
Date:	Date [.]

Lockheed Martin Hazardous Material/Waste Shipment Checklist

Pr	nte: oject Site Name: iipping Document No.:
A.	DESCRIPTION A1 UN/NA Identification Number, Proper Shipping Name, Hazard Class/Division Number, Packing Group A2 Subsidiary hazard class(es) or division number(s), if any, in parenthesis A3 Total Quantity of Material A4 24-Hour Emergency Phone Number and Response Information ERG No.: A5 Page of Pages, for multiple shipping papers/EPA Manifest/Air Decs. A6 Shipper's Certification, as applicable A7 Small Quantity Exception/Dangerous Goods In Excepted Quantities/Diagnostic Specimen/Sample
B.	ADDITIONAL DESCRIPTIONS - GENERAL B1.
	MARKING FOR NON-BULK PACKAGINGS C1. Proper Shipping Name, UN/NA Identification Number C2. (technical name) C3. (EPA waste identification number) C4. "RQ" C5. Exemption Packagings "DOT-E-ex.#" C6. Consignee's Name & Address C7. Net or Gross quantity for non-rad Dangerous Goods (adjacent to PSN & UN#) C8. Ltd. Qty - PSN only per 172.301(a)(1) or UN ID# placed in square-on-point border per 172.315 C9. Package Orientation Arrows, for liquids in inner packagings C10. "Inhalation Hazard", unless these words appear on the label prescribed in 172.416 or 172.429 C11. "Overpack" adjacent to proper shipping name marking [see 173.25(a)(4)] C12. TSCA PCB Marking (for actual or source concentration greater than or equal to 50 ppm *) (* Note Potential Vehicle Marking Requirements in 40 CFR 761.40)
D.	MARKING FOR BULK PACKAGINGS (DUMP TRUCKS OR ROLL-OFFS) D1 UN/NA Identification Number on orange panel or placard or white square-on-point display configuration as prescribed by 172.302 and 172.332
E.	LABELING E1 Primary Hazard Label(s): E2 Subsidiary Hazard Label(s) with class/division: E3 Hazardous Wastes Label(s)
F.	PLACARDING F1. 172.504 Table 1 Materials - Any Amount F1.1 Dangerous When Wet (4.3) F1.2 Poison (6.1, Inhalation Hazard, Zone A or B)* (Primary or Subsidiary (*Materials subject to the "Poison-Inhalation Hazard" notation must be placarded with a POISON INHALATION HAZARD or POISON GAS placard, as appropriate, and also placarded for any other hazard class required for that material in 172.504) F1.3 Radioactive (7, LSA/SCO Exclusive Use Shipments) F2. 172.504 Table 2 Materials - 1,001 lb:

Page 1 of 2 March 2009

Lockheed Martin Hazardous Material/Waste Shipment Checklist

H5NKC Manifest #540 for radioactive	waste snipment for land dispos	aı.
H3Limited Quantity Radioactive Mate H4Health Physics Information	erial for multiple hazard limited q	quantity Class 7.
H2. Radioactive Excepted Package sta	atement per 10.8.8.3.3 on Airwa	av Bill
I4.1. Radioactive (7, LSA/SCO Exclusive	ve Use Shipments)	
PLACARDING (172.504 TABLE 1 MATERIA	LS - ANY AMOUNT)	
I3.3. "Radioactive Material, Excepted Page 13.3."	ackage" handling label	
I3.2 "EMPTY" Label		
	on Type A	
I2.5 "USA" on all IP and Type A packag	gings	
I2.4 IP-1, IP-2, IP-3 markings		r r - r
12.3. Package Certification Number. for	radioactive material packages.	as appropriate
12.1Gloss weight, for radioactive mate	mai packages in excess of 110 i ∆" · "Radioactive – SCO"	IU
		lb.
I1.5 Fissile Excepted, if applicable		
I1.4 Radioactive Labels		
	special IUIIII	
	405	
	TIVE MATERIAL SHIPMENTS	
LINC Notification instructions		
Emergency Telephone Number Notific	cation, if required, see 172.604(b)
Check Driver's Qualifications		L.)
5 Vehicle Inspection		
Photograph, if applicable		
	tomoni on i donago, ioi iii on i	mpmeme, 2024 etatement per 21111.
Small Quantity/Excepted Quantity Sta	tement on Package. <i>for 173.4</i> s	chipments / DGEQ statement per 2.7.7.
Shipping Paper/Hazardous Waste Ma Instructions for Maintenance of Exclus	niiest/biii oi Lading/Airway biii/s sive Use Shinments	Shipper's Declaration
PERWORK AND MISCELLANEOUS ITEMS	nife of /Dill of Loding /Aimaga, Dill/C	Chinnavia Daglavation
Loaded and Closed As Required		
B Container Type: (Bulk Pkg)		
2 Container Type: (Outer Pkg)		
Container Type: (Inner Pkg)		
3	Container Type: (Bulk Pkg) Loaded and Closed As Required PERWORK AND MISCELLANEOUS ITEMS Shipping Paper/Hazardous Waste Ma Instructions for Maintenance of Exclus Small Quantity/Excepted Quantity Sta noted on Airway Bill Photograph, if applicable Vehicle Inspection Check Driver's Qualifications Emergency Telephone Number Notific LMC Notification Instructions DITIONAL REQUREMENTS FOR RADIOAC SHIPPING PAPER DESCRIPTIONS 11.1 Radionuclide Symbol(s), per 173.4 11.2 Physical & Chemical Form, if not s 11.3 Activity per Package 11.4 Radioactive Labels 11.5 Fissile Excepted, if applicable 11.6 "Exclusive Use Shipment" MARKING FOR NON-BULK PACKAGINGS 12.1 Gross Weight, for radioactive mate 12.2 "Radioactive"; "Radioactive mate 12.3 Package Certification Number, for 12.4 IP-1, IP-2, IP-3 markings 12.5 "USA" on all IP and Type A packac 12.6 Packaging manufacturer marking of 12.7. Radioactive Labels 13.1 Radioactive Labels 13.2 "EMPTY" Label 13.3 "Radioactive Material, Excepted P PLACARDING (172.504 TABLE 1 MATERIA 14.1 Radioactive (7, LSA/SCO Exclusive) PAPERWORK AND MISCELLANEOUS ITE 14 Instructions for Maintenance of Excepted Package sta 14 Limited Quantity Radioactive Material 15 Radioactive Excepted Package sta 16 Radioactive Excepted Package sta 17 Instructions for Maintenance of Excepted Package sta 18 Limited Quantity Radioactive Material 18 Limited Radioactive Material 18 Limited Radioactive Material 18 Limited Radioactive Material	Container Type: (Bulk Pkg) Loaded and Closed As Required PERWORK AND MISCELLANEOUS ITEMS Shipping Paper/Hazardous Waste Manifest/Bill of Lading/Airway Bill/3 Instructions for Maintenance of Exclusive Use Shipments Small Quantity/Excepted Quantity Statement on Package, for 173.4 s noted on Airway Bill Photograph, if applicable Vehicle Inspection Check Driver's Qualifications Emergency Telephone Number Notification, if required, see 172.604(LMC Notification Instructions DITIONAL REQUREMENTS FOR RADIOACTIVE MATERIAL SHIPMENTS SHIPPING PAPER DESCRIPTIONS 11.1. Radionuclide Symbol(s), per 173.435 11.2. Physical & Chemical Form, if not special form 11.3. Activity per Package 11.4. Radioactive Labels 11.5. Fissile Excepted, if applicable 11.6. "Exclusive Use Shipment" MARKING FOR NON-BULK PACKAGINGS 12.1. Gross Weight, for radioactive material packages in excess of 110 12.2. "Radioactive"; "Radioactive — LSA"; "Radioactive — SCO" 12.3. Package Certification Number, for radioactive material packages, 12.4. IP-1, IP-2, IP-3 markings 12.5. "USA" on all IP and Type A packagings 12.6. Packaging manufacturer marking on Type A LABELING 13.1. Radioactive Labels 13.2. "EMPTY" Label 13.3. "Radioactive Material, Excepted Package" handling label PLACARDING (172.504 TABLE 1 MATERIALS - ANY AMOUNT) 14.1. Radioactive Material, Excepted Package" handling label PLACARDING (172.504 TABLE 1 MATERIALS - ANY AMOUNT) 14.1. Radioactive Material, Excepted Package Shipments 14. Instructions for Maintenance of Exclusive Use Shipments 14. Instructions for Maintenance of Exclusive Use Shipments 14. Radioactive Excepted Package statement per 10.8.8.3.3 on Airwa 14. Limited Quantity Radioactive Material for multiple hazard limited of the United Research Processing Per 10.8.8.3.3 on Airwa 14. Health Physics Information

PACKING AND CLOSING INSTRUCTIONS FOR NON-SPECIFICATION BULK CONTAINERS (DUMP TRUCKS AND ROLL-OFFS) 04/10/2009

PRELIMINARY TASKS

- Select the transport container based on the Department of Transportation hazard classification and the packaging requirements specified in the Hazardous Materials Table.
- Perform moisture evaluation of waste material to be loaded into transport containers to determine the potential for releasing liquid.

PREPARATION OF BULK CONTAINERS FOR LOADING

- Transport containers must be inspected for any condition that may affect their safety or performance prior to each use.
- Dump trucks and roll-offs with doors must have gaskets installed at the tailgate or
 doors that when the tailgate or doors are closed the gasket is compressed sealing the
 tailgate or doors to assure package integrity and containment of materials. The gasket
 must be inspected prior to each use for overall integrity including positioning,
 damage such as holes or tears or debris which could prevent tight closure. Any
 deficiencies shall require replacement prior to use.
- An absorption pad shall be placed in the truck or roll-off bed. The pad specification shall be determined utilizing the data determined in the waste material moisture evaluation and must be capable of absorbing the liquid which could be released.
- An absorption log at the rear of the transport container along the bottom of the tailgate or rear doors.
- A minimum 6 mil poly liner shall be placed over the absorption pad and absorption log prior to loading.
- Determine the amount of waste that can be loaded into the transport container.
 (Subtract the unladen weight of the transport vehicle from the maximum licensed weight of the transport vehicle. NOTE: Do not load the maximum permissible load determined in the mathematical calculation to allow for variance in scales that may be utilized to weigh the loaded vehicle.)

LOADING AND CLOSING BULK CONTAINERS

- Waste material shall be loaded into the transport container in such a manner that does not compromise either the liner or container integrity.
- Do not load material above the height of the sides of the transport container.
- Close the poly liner over of the waste material prior to tarping the load.
- Close the transport container by putting a heavy roll tarp over the top of the transport container and secure the tarp by utilizing tie downs on all four sides.