



Vapor Intrusion Study Report for the Solvent Dock Area

Former Lockheed Martin French Road Facility
August 2007



Christopher J. Motta, C.P.G.
Project Manager



Lowell W. McBurney, P.E.
Principal in Charge

**Vapor Intrusion Study Report
for the Solvent Dock Area**

French Road Facility
Utica, New York

Prepared for:
Lockheed Martin Corporation

Prepared by:
ARCADIS
482 Congress Street
Suite 501
Portland
Maine 04101
Tel 207.828.0046
Fax 207.828.0062

Our Ref.:
AY000265.0015

Date:
August 10, 2007

This document is intended only for the use of the individual or entity for which it was prepared and may contain information that is privileged, confidential and exempt from disclosure under applicable law. Any dissemination, distribution or copying of this document is strictly prohibited.

1. Introduction	1
2. Background and Site History	1
3. Site Setting	2
3.1 Geology and Hydrogeology	2
3.2 Site Reconnaissance and Building Conditions	3
3.3 Previous Vapor Intrusion Study	4
4. Sampling Approach	4
5. Results and Findings	5
5.1 Evaluation of Subslab Soil Gas and Indoor Air Results	5
5.1.1 Comparison to Air Guideline Values	6
5.1.2 Comparison to Background Concentrations	6
5.1.3 Evaluation of Data Using NYSDOH Matrices	8
5.2 Vapor Intrusion Pathway Evaluation	9
6. Summary and Conclusions	9
7. References	11

Tables

1	Concentrations of Volatile Organic Compounds in Subslab Soil Gas Collected in February 2006
2	Concentrations of Volatile Organic Compounds in Indoor and Ambient Air Collected in February and March 2006
3	Concentrations of Volatile Organic Compounds in Subslab Soil Gas Collected in April 2007
4	Concentrations of Volatile Organic Compounds in Indoor and Ambient Air Collected in April 2007
5	Summary of Constituents Detected in Subslab Soil Gas and Indoor Air
6	Comparison of Constituents in Indoor Air to NYSDOH Air Guidelines and Background Concentrations

- 7 Evaluation of Potential Mitigation and Monitoring Actions Using NYSDOH Matrices

Figures

- 1 Site Location
- 2 Historical Groundwater Sampling Results
- 3 Subslab / Indoor Air Sample Locations
- 4 Subslab / Indoor Air Sample Locations and NYSDOH Matrix Decisions

Appendices

- A Product Inventory
- B Indoor Air and Subslab Soil Gas Sample Logs
- C Analytical Laboratory Results

1. Introduction

On behalf of Lockheed Martin Corporation (Lockheed Martin), ARCADIS has prepared this report to present the results of the vapor intrusion study for the former French Road Facility Solvent Dock Area (herein the "Site") located in Utica, New York and to evaluate the results based on the criteria set forth in the *Final – Guidance for Evaluating Soil Vapor Intrusion in the State of New York* (NYSDOH 2006). The vapor intrusion study was required by the New York State Departments of Environmental Conservation (NYSDEC) and Health (NYSDOH) to address the vapor intrusion pathway for the Site. The requirement was set forth in an 18 October 2006 letter to Lockheed Martin. The 18 October 2006 letter provided comments on the *Work Plan for the Interim Corrective Measure* (ARCADIS 2006a) including the requirement for delineation of the soil gas plume prior to development and implementation of the interim corrective measure (i.e., vapor depressurization system).

In response to this requirement, ARCADIS prepared a *Supplemental Vapor Intrusion Study* (herein "Study Work Plan") (ARCADIS 2007) dated 14 March 2007 that outlined the program for subslab soil gas and indoor air sampling at the Site, consistent with the discussions during conference calls with the NYSDEC and NYSDOH. The Study Work Plan was approved by the NYSDEC on 22 March 2007 and implemented on 12 April 2007.

This report presents information on the background and site history, the site setting including the results of a previous vapor intrusion study, the sampling approach, and the results and findings of all subslab and indoor air sampling. The summary and conclusions are presented at the end of this report.

2. Background and Site History

The 55-acre property, located in Utica, New York, was initially developed in the early 1950s by General Electric (GE) who constructed an industrial facility that included a 500,000-square foot manufacturing building (Figure 1). Production operations conducted by GE included manufacturing, assembly, and testing of electrical components for the defense and aerospace industries. These production operations were conducted by GE until April 1993, when the facility was acquired by Martin Marietta Corporation (MMC). In March 1995, MMC merged with Lockheed Corporation to form Lockheed Martin Corporation. In March 1996, Lockheed Martin sold the property to Pinnacle Park, Inc., which subsequently sold the property to the Oneida County Industrial Development Agency (OCIDA), the current owner. ConMed

Corporation, a company that manufactures and distributes medical supplies, now occupies the facility and leases it from OCIDA. Although Lockheed Martin no longer owns the property, it has retained responsibility for environmental cleanup activities related to past releases at the Solvent Dock Area which includes the former solvent dock and surrounding area where groundwater is impacted with volatile organic compounds (VOCs).

Historical environmental releases at the Site are associated with a 275-gallon fiberglass overflow retention tank and other underground storage tanks (USTs) that were installed beneath the former solvent dock (part of the loading docks along the eastern section of the building's north wall). The retention tank was designed to contain solvents incidentally spilled and subsequently collected in floor drains at the former solvent dock. Collected waste solvents were periodically sampled, pumped from the retention tank, and disposed by waste haulers. The retention tank remained in service until June 1990, when it was removed. During tank removal, elevated vapor readings were noted, indicating a release. The retention tank was also noted as dented and leaking fluid.

A series of investigations to evaluate the soil and groundwater impacts due to spills and/or leaks associated with the retention tank and other USTs beneath the former solvent dock were subsequently completed, confirming the presence of VOCs in groundwater beneath and downgradient of the former solvent dock.

3. Site Setting

This section presents information on the geology and hydrogeology, the site reconnaissance and building conditions, and a summary of a previous vapor intrusion study completed at the Site.

3.1 Geology and Hydrogeology

Geologic materials (i.e., stratigraphy) encountered during previous investigations in the Solvent Dock Area were generally described as brown silt with fine sand to a maximum depth of approximately 20 feet below land surface (bls), overlying a dense unit composed of silt and fine sand with minor gravel (likely glacial till). This stratigraphy is similar to the regional geology of the Utica area. Groundwater elevation data show that the water table ranges from 5 to 10 feet bls. The general direction of groundwater flow is south-southeast. As such, groundwater moves from the exterior loading dock to beneath the manufacturing building. The Solvent Dock Area is "capped" with asphalt

pavement in the exterior loading area or with the building's concrete foundation and slab.

Several solvent storage tanks were removed from service during the late 1970s and the early 1980s, with the last tank (the overflow retention tank) removed from the Solvent Dock Area in 1990. Due to the detection of organic vapors during the removal of the overflow tank, a series of investigations to evaluate potential soil and groundwater impacts due to spills and/or leaks from the former solvent tanks was completed. These historical investigations determined that groundwater in and around the northeast corner of the main manufacturing building (i.e., the Solvent Dock Area) had been impacted by VOCs. Groundwater samples collected during the past 10 to 15 years from piezometers installed through the building slab have yielded detectable levels of VOCs including 1,1-dichloroethane (1,1-DCA), trichloroethene (TCE), tetrachloroethene (PCE), cis-1,2-dichloroethene (cis-1,2-DCE), trans-1,2-dichloroethene (trans-1,2-DCE), and vinyl chloride. Concentrations of total VOCs in these samples have recently been in the range of 500 to 1,000 micrograms per liter ($\mu\text{g/L}$). Water quality data for wells in the Solvent Dock Area are shown on Figure 2.

3.2 Site Reconnaissance and Building Conditions

Site reconnaissance was conducted by EarthTech, on behalf of Lockheed Martin in March 2005 and February 2006. The focus of the reconnaissance was to select sampling locations, evaluate the building condition, identify chemical usage in the building, and to identify and minimize conditions that may interfere with the planned sampling activities. The building floor was noted to be in good condition and free of cracks and holes (which represent target sampling locations). Therefore, sample locations were identified in areas with potential worker exposure. During the reconnaissance, several rooms in the building were identified as being under positive pressure. These areas are shown on Figure 3.

A copy of the product inventory completed during the reconnaissance is provided in Appendix A. Workers initially indicated that solvent use was limited to citrus degreasers. However, during sampling events and additional inquiries at the ConMed facility, TCE and other chemicals, including petroleum products and methylene chloride, were identified in the eastern portion of the building near molding machines.

3.3 Previous Vapor Intrusion Study

In February 2006, EarthTech collected ten subslab soil gas and indoor air samples and one ambient air sample at the ConMed facility. Sample locations, except ambient air, are shown on Figure 3. The ambient air sample was located outside of the northwest corner of the building approximately 750 feet west of the Solvent Dock Area. Sample results were submitted to the NYSDEC in a letter report dated April 17, 2006 (EarthTech 2006). The sample results showed that both TCE and PCE were detected in subslab soil gas and indoor air at concentrations greater than NYSDOH air guidelines at some locations (Tables 1 and 2). Concentrations of TCE in indoor air ranged from non-detect to 73 micrograms per cubic meter ($\mu\text{g}/\text{m}^3$). PCE was detected in indoor air at concentrations that ranged from 2.8 $\mu\text{g}/\text{m}^3$ to 97 $\mu\text{g}/\text{m}^3$. In subslab soil gas, TCE levels ranged from 2.5 $\mu\text{g}/\text{m}^3$ to 680 $\mu\text{g}/\text{m}^3$ and PCE levels ranged from 5.0 $\mu\text{g}/\text{m}^3$ to 21,000 $\mu\text{g}/\text{m}^3$.

Based on the results of the initial sampling event and in response to the presence (and perhaps use) of TCE in the building, EarthTech conducted a second sampling event at two locations (I1 and I4) (EarthTech 2006). The results of the re-sampling event detected the same concentration of TCE at I1 (41 $\mu\text{g}/\text{m}^3$) and a lower concentration of TCE at I4 (6.7 $\mu\text{g}/\text{m}^3$).

4. Sampling Approach

The 12 April 2007 sampling event conducted by ARCADIS was implemented in accordance with the Study Work Plan (ARCADIS 2007) and the *Vapor Intrusion Work Plan - Revised* (Lockheed Martin 2005). The sampling locations are shown on Figure 3. Sampling logs are provided in Appendix B. The study area consisted of the eastern section of the manufacturing building where groundwater is impacted with VOCs.

Eight co-located subslab soil gas and indoor air sampling locations were initially identified as part of this supplemental study. As requested by NYSDEC and NYSDOH, samples were biased towards the north, south, and west and focused on the portions of the building located outside of the positive pressure rooms and where the groundwater plume is not well defined (beneath the building toward the west). All samples were collected as proposed in the Study Work Plan, with the exception of a subslab soil gas sample at location 6SD. At location 6SD, the thickness of the slab (greater than 16 inches) prevented the collection of any subslab soil gas sample. As a result, only an indoor air sample was collected from this location.

As provided for in the Study Work Plan, the subslab soil gas samples were initially analyzed. The indoor air samples were placed on hold pending receipt and review of the subslab soil gas sample results. A discussion of the subslab sampling results was held with the NYSDEC and NYSDOH on 24 April 2007. During the conference call, it was decided that analysis of five indoor air samples (i.e., AA-2SD, AA-3SD, AA-4SD, AA-6SD, and AA-8SD) would be appropriate for the study.

5. Results and Findings

In this section, the results of the subslab soil gas and indoor air sampling conducted by ARCADIS in April 2007 and EarthTech in February/March 2006 are presented and evaluated according to the criteria set forth in the *Final – Guidance for Evaluating Soil Vapor Intrusion in the State of New York* (herein “Final Guidance”). The results of the April 2007 subslab soil gas and indoor air sampling are presented in Table 3 and Table 4, respectively. The results of the February/March 2006 subslab soil gas and indoor air sampling are presented in Table 1 and Table 2, respectively. Table 5 presents a summary of the data including the frequency of detection and minimum and maximum detected concentration for each constituent. Complete analytical results from the April 2007 sampling event are provided in Appendix C.

5.1 Evaluation of Subslab Soil Gas and Indoor Air Results

Consistent with the Final Guidance, subslab soil gas and indoor air data from all sampling events (i.e., February/March 2006 and April 2007) were evaluated using the following steps.

- § First, concentrations detected in indoor air were compared to applicable NYSDOH air guideline values provided in the Final Guidance.
- § Second, concentrations detected in indoor air were compared to generic background concentrations referenced by the NYSDOH in the Final Guidance.
- § Third, the subslab soil gas data were evaluated using the matrices provided in the Final Guidance.

Each of the evaluation steps is described below.

5.1.1 Comparison to Air Guideline Values

The constituents detected in indoor air were evaluated through a comparison to air guideline values. As developed by NYSDOH, concentrations in indoor air greater than the air guidelines values may need to be addressed if the source of these exceedances is from the subsurface (i.e., groundwater or soil gas). The air guideline values were not designed to address current work place exposures associated with active manufacturing processes for which the Occupational Safety and Health Administration (OSHA) has established permissible exposure limits.

The Final Guidance presents guideline values for three VOCs: methylene chloride, TCE, and PCE. Table 6 presents the comparison of constituents in indoor air to the air guideline values. Methylene chloride was detected in indoor air at concentrations greater than its air guideline value ($60 \mu\text{g}/\text{m}^3$) during the April 2007 sampling event. In all cases, methylene chloride was detected at a higher or similar concentration in indoor air compared to subslab soil gas indicating an indoor source unrelated to groundwater. As noted in the product inventory (Appendix A), methylene chloride is stored in the facility.

TCE was detected in indoor air at concentrations greater than its air guideline value ($5 \mu\text{g}/\text{m}^3$) during the February 2006 sampling event. TCE was generally detected at higher concentrations in subslab soil gas indicating contribution from a source beneath the building, presumably related to groundwater. However, at three locations (EarthTech sampling locations 4, 5, and 8), TCE was detected at higher concentrations in indoor air indicating contribution of an indoor source unrelated to groundwater. Although sample locations were not replicated between the two sampling events, TCE concentrations measured in indoor air were lower during the April 2007 sampling round and were less than NYSDOH air guideline values. As noted in the product inventory (Appendix A), TCE is stored in the facility.

Although PCE was detected in 9 out of 15 indoor air samples, all concentrations were less than the air guideline value ($100 \mu\text{g}/\text{m}^3$).

5.1.2 Comparison to Background Concentrations

The constituents detected in indoor air were compared to the generic background indoor air concentrations reported by the USEPA (2001) as part of the building

assessment and survey evaluation (BASE) database. The BASE database includes indoor air results from approximately 100 commercial and public office buildings. As a result, these values are expected to significantly underestimate background concentrations at active manufacturing facilities where chemicals may be used as part of normal operations. However, because background data from such facilities is not currently available, the 90th percentile value from the BASE database (as recommended by NYSDOH) was used for comparative purposes (Table 6).

A total of 13 constituents including TCE, PCE, and methylene chloride were detected at least once in indoor air samples at concentrations greater than background concentrations. However, as described in Section 5.1.1, air guideline values are available for TCE, PCE, and methylene chloride and these values are used as the more appropriate criteria for comparison. The 10 constituents above background concentrations without air guidelines are as follows:

- 1,2,4-trimethylbenzene
- 1,3,5-trimethylbenzene
- 1,4-dichlorobenzene
- acetone
- 4-ethyltoluene
- ethylbenzene
- methyl ethyl ketone (MEK)
- m&p-xylene
- o-xylene
- toluene

Although these constituents, including TCE, PCE, and methylene chloride were measured at concentrations greater than conservative background levels, they are not expected to cause unacceptable human health impacts at the levels currently measured inside the building. Indeed, the background concentrations used for the above comparisons only indicate the levels typically measured inside commercial buildings and are orders of magnitude lower than health-based concentrations used for occupational settings.

5.1.3 Evaluation of Data Using NYSDOH Matrices

The final step in the data evaluation was to compare the subslab soil gas results to the matrices presented in the Final Guidance. The indoor air data were not considered in conjunction with the subslab soil gas data because, as described in Section 3.2, TCE and other chemicals, including petroleum products and methylene chloride, were identified in the eastern portion of the building near the molding machines. The results indicate that several constituents, including TCE and methylene chloride were present in indoor air due to background sources located within the building (i.e., observed storage of chemicals and their potential use). Therefore, indoor air data are not reliable indicators of the need to monitor or mitigate subslab soil gas.

Matrix 1 is applicable to TCE and carbon tetrachloride. Matrix 2 is applicable to PCE and 1,1,1-trichloroethane (1,1,1-TCA). Table 7 presents a comparison of subslab soil gas results and the matrix recommended action for TCE, PCE, and 1,1,1-TCA. Carbon tetrachloride was not detected in subslab soil gas and therefore, was not considered as part of the data evaluation. The matrices allow for four different options or actions:

- § No further action
- § Take reasonable and practical actions to identify source(s) and reduce exposures (i.e., concentration is likely associated with background)
- § Monitor
- § Mitigate

As presented on Table 7, there were 17 subslab soil gas sample results. Figure 4 shows the results of the matrix comparisons for TCE, PCE, and 1,1,1-TCA. As shown on Figure 4 and presented in Table 7, the NYSDOH matrices recommend mitigation at two locations (S1 and S2) based on TCE and/or PCE concentrations. In addition, the NYSDOH matrices recommend monitoring at five locations (S4, S5, S6, S10, and VP-2SD). At all other locations, a no further action decision would be appropriate.

In addition to background sources (i.e., sources unrelated to the subsurface impacts from former operations at the Site), groundwater was evaluated as a potential source of the TCE and PCE detected in subslab soil gas. Both TCE and PCE have high Henry's Law constants (i.e., greater than 10^{-5} atm m³/mol), therefore, the dissolved phase concentrations measured in groundwater at the Solvent Dock Area could generate the concentrations of TCE and PCE detected in subslab soil gas.

NYSDOH has recently (July 2007) added three VOCs (1,1-dichloroethene, cis-1,2-dichloroethene, and vinyl chloride) to the Final Guidance matrices (although the Final Guidance has not been updated). Therefore, these VOCs are included in the matrix evaluation presented in Table 7. The addition of these VOCs did not change the matrix recommendations based on the original VOCs presented in the Final Guidance.

5.2 Vapor Intrusion Pathway Evaluation

The potential exists for the vapor intrusion pathway (groundwater to soil gas) to be complete for several constituents including TCE and PCE. Dissolved phase concentrations in groundwater are sufficient to produce the concentrations measured in subslab soil gas for these constituents.

Several constituents detected in indoor air may not be related to subsurface conditions, but could be present due to background sources. Background constituents, including TCE, PCE and methylene chloride would not be mitigated by the subsurface depressurization system proposed in the *Work Plan for the Interim Corrective Measure* (ARCADIS 2006a). If deemed necessary or appropriate by the owner, tenant, or regulatory agency, mitigation of background constituents in indoor air should be addressed separately from Lockheed Martin's obligations at the Solvent Dock Site.

6. Summary and Conclusions

NYSDEC and NYSDOH required Lockheed Martin to conduct a vapor intrusion study to address the vapor intrusion pathway at the Solvent Dock Area of the former French Road facility in Utica, New York. Seven subslab soil gas and four indoor air samples were collected and analyzed in April 2007. Previously, ten subslab soil gas and eleven indoor air samples were collected in February/March 2006. The 17 subslab soil gas samples and 15 indoor air samples were evaluated based on the criteria set forth in the *Final – Guidance for Evaluating Soil Vapor Intrusion in the State of New York* (NYSDOH 2006). As part of the study, the groundwater quality data and subslab soil gas results were used to evaluate the vapor intrusion pathway at the Solvent Dock Area. The conclusions of the study are presented below.

§ In the northeast portion of the manufacturing building, measured concentrations of TCE and PCE in subslab soil gas warrant mitigation per the *Final – Guidance for Evaluating Soil Vapor Intrusion in the State of New York* (NYSDOH 2006). The vapor intrusion study has delineated subslab soil gas that warrants mitigation.

- § Dissolved phase concentrations of several constituents including TCE and PCE present in groundwater are sufficient to produce the concentrations measured in subslab soil gas for these constituents.
- § Measured concentrations of TCE and methylene chloride in indoor air exceed the NYSDOH air guideline values. However, the concentrations detected in indoor air are less than available OSHA work place standards.
- § Several constituents detected in indoor air do not appear to be related to subsurface conditions, but may be present due to background sources (this conclusion is supported by the observation of chemical storage and/or use in the facility). These conditions would not be mitigated by the subsurface depressurization system proposed in the *Work Plan for the Interim Corrective Measure* (ARCADIS 2006a). If deemed necessary or appropriate by the owner, tenant, or regulatory agency, mitigation of background constituents in indoor air should be addressed separately from Lockheed Martin's obligations at the Solvent Dock Site.

Lockheed Martin will resample subslab soil gas at locations S1 and S2. Pending confirmation of the subslab conditions, Lockheed Martin will seek the concurrence of the regulatory agencies to install the vapor depressurization system contemplated in the *Work Plan for the Interim Corrective Measure* (ARCADIS 2006a) to mitigate the subslab soil gas impacts beneath the northeastern portion of the manufacturing building. Prior to installation, Lockheed Martin will revise the *Work Plan for the Interim Corrective Measure* (ARCADIS 2006a) and submit the revised plan to NYSDEC and NYSDOH for review. The revisions will account for the new information reported herein and the comments offered by NYSDEC/NYSDOH in letter dated 18 October 2006. Upon agency approval, Lockheed Martin will install the vapor depressurization system.

7. References

ARCADIS. 2006a. Work Plan for the Interim Corrective Measure, Solvent Dock Area, Former Lockheed Martin French Road Facility, Utica, New York. August 25.

ARCADIS. 2006b. Letter to Mr. Larry Rosenmann, New York State Department of Environmental Conservation from Jeffrey Bonsteel, ARCADIS. RE: French Road Facility, 2006 Annual Monitoring Report for Solvent Dock Area Groundwater Treatment System, Former Lockheed Martin Facility, 525 French Road, Utica, New York. April 7.

ARCADIS. 2007. Letter to Mr. Larry Rosenmann, New York State Department of Environmental Conservation from Jeffrey Bonsteel, ARCADIS. RE: Supplemental Vapor Intrusion Study, Work Plan for Interim Corrective Measures, Solvent Dock Area, Former Lockheed Martin, French Road Facility, Utica, New York. March 14.

Lockheed Martin. 2005. Letter to Mr. Larry Rosenmann, New York State Department of Environmental Conservation from Tina Armstrong, Lockheed Martin Corporation. RE: Vapor Intrusion Work Plan – Revised, ConMed Facility, 525 French Road, Utica, New York. June 29.

EarthTech. 2006. Letter to Tina Armstrong, Lockheed Martin Corporation from Caroline Benedict, Earth Tech, Inc. RE: Vapor Intrusion Study, ConMed Facility, French Road, Utica, New York. April 17.

NYSDOH. 2006. Final – Guidance for Evaluating Soil Vapor Intrusion in the State of New York. New York State Department of Health, Center for Environmental Health, Bureau of Environmental Exposure Investigation. October.

USEPA. 2001. Draft – A Standard EPA Protocol for Characterizing Indoor Air Quality in Large Buildings. U.S. Environmental Protection Agency, Office of Air and Radiation, Washington, DC.

Table 1. Concentrations of Volatile Organic Compounds in Subslab Soil Gas Collected in February 2006, Vapor Intrusion Study Report, Solvent Dock Area Former Lockheed Martin French Road Facility, Utica, New York

Sample ID:	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10
Lab ID:	06B07706	06B07698	06B07708	06B07702	06B07712	06B07715	06B07710	06B07705	06B07704	06B07709
Sample Date:	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006
Units:	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)
1,1,1-Trichloroethane	33 U	260	67	54	120	6.3	30	77	14	0.7 U
1,1,2,2-Tetrachloroethane	42 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U
1,1-Dichloroethane	25 U	8.4	0.5 U	0.5 U	1.7	6.2	5.1	3.8	3.8	0.5 U
1,1-Dichloroethene	24 U	0.5 U	0.5 U	0.5 U	0.5 U	5.1	0.5 U	0.5 U	7.0	0.5 U
1,2,4-Trimethylbenzene	99 U	6.9	25	24	21	20	13	18	2.2	18
1,3,5-Trimethylbenzene	99 U	2.2	5.4	6.8	7.3	6.3	4.0	4.5	2.0 U	5.3
1,3-Dichlorobenzene	36 U	0.8 U	0.8 U	0.8 U	1.1	2.5 U	1.5	0.8 U	0.8 U	0.8 U
1,4-Dichlorobenzene	130 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	5.1	2.5 U
2-Hexanone	25 U	0.5 U	0.5 U	0.5 U	1.7 U	1.7 U	1.7 U	2.2	0.5 U	1.7 U
4-Ethyltoluene	99 U	2.0	5.4	6.6	7.4	6.3	4.2	4.9	2.0 U	5.1
Acetone	250	250	210	1,400	480	230	500	610	320	74
Benzene	20 U	23	3.5	53	17	5.1	31	48	9.9	2.1
Carbon Disulfide	19 U	6.0	3.1	20	10	4.0	25	6.4	1.3	1.4
Chlorobenzene	28 U	1.1	0.6 U	2.4	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
Chloroethane	16 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.5	0.4 U	0.4 U	0.4 U
Chloroform	30 U	7.0	0.6 U	9.8	2.9	12	1.5	0.6 U	0.6 U	1.8
Chloromethane	15 U	0.6	0.3 U	0.3 U	0.3 U	0.3 U	0.8	0.3 U	1.0	0.3 U
cis-1,2-dichloroethene	24 U	0.5 U	0.5 U	0.5 U	0.5 U	2.8	4.8	0.5 U	0.5 U	0.5 U
Cyclohexane	69 U	32	1.4 U	52	13	3.4	50	46	43	1.4 U
Ethanol	51	140	0.8 U	0.8 U	0.8 U	26	39	51	57	6.1
Ethyl Acetate	22 U	1.0	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
Ethylbenzene	26 U	18.0	9.0	58	26	35	14	22	2.2	13.0

Table 1. Concentrations of Volatile Organic Compounds in Subslab Soil Gas Collected in February 2006, Vapor Intrusion Study Report, Solvent Dock Area Former Lockheed Martin French Road Facility, Utica, New York

Sample ID:	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10
Lab ID:	06B07706	06B07698	06B07708	06B07702	06B07712	06B07715	06B07710	06B07705	06B07704	06B07709
Sample Date:	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006
Units:	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)
Freon 11	36 U	1.9	5.7	0.8 U	1.1	3.9	1.5	0.8 U	0.8 U	1.2
Freon 113	46 U	3.6	4.7	190	270	1.0 U	88	240	11	1.3
Freon 12	30 U	2.4	190	2.7	2.5	500	2.3	2.0	2.5	2.3
Hexane	22 U	82	3.1	140	28	8.3	120	79	57	6.7
Isopropyl Alcohol	15 U	43	95	74	110	11	13	7	110	4.5
m&p-Xylene	180 U	47	38	99	96	110	50	68	6.4	52
Methyl Ethyl Ketone	18 U	25	23	52	120	22	17	45	6.1	4.6
Methyl Isobutyl Ketone	82 U	3.8	1.7 U	1.7 U	9.6	2.9	0.5 U	1.7 U	1.7 U	0.5 U
Methylene Chloride	70 U	8.0	4.4	3.4	2.4	2.8	11.0	2.2	9.8	2.7
n-Heptane	25 U	65	3.9	96	0.5 U	9.8	0.5 U	58	15	12
o-Xylene	87 U	17	16	60	48	31	22.0	26.0	3.0	23
Propylene	11 U	0.3 U	0.3 U	0.3 U	0.3 U	0.7 U	0.3 U	0.3 U	0.3 U	0.3 U
Styrene	86 U	1.8 U	1.8 U	0.6 U	1.8 U	2.1	1.8 U	1.8 U	1.8	1.8 U
Tetrachloroethene	21,000	76	34	660	26	280	95	35	5	260
Tetrahydrofuran	59 U	6.4	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
Toluene	76 U	70	25	1.6 U	1.6 U	47	68	160	32	40
Trichloroethene	680	560	7	2.5	4.7	32	30	3.4	21	70
Vinyl Acetate	22 U	0.5 U	1.7	0.5 U	0.5 U	1.5 U	0.5 U	8.7	0.5 U	0.5 U
Vinyl Chloride	16 U	0.5	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U

Notes:

U - Not detected at the reporting limit

$\mu\text{g}/\text{m}^3$ - Micrograms per cubic meter

Table 2. Concentrations of Volatile Organic Compounds in Indoor Air and Ambient Air Collected in February and March 2006, Vapor Intrusion Study Report, Solvent Dock Area Former Lockheed Martin French Road Facility, Utica, New York

Sample ID	I1	I1-Retest	I3	I4	I4-Retest	I5	I10 (I5 DUP)	I6	I7	I8	I9	OD1
Lab ID:	06B07713	06B10826	06B07716	06B07701	06B10827	06B07703	06B07700	06B07714	06B07711	06B07707	06B07699	06B07717
Sample Date:	2/26/2006	3/30/2006	2/26/2006	2/26/2006	3/30/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006
Units:	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)
1,1,1-Trichloroethane	0.7 U	4.1 U	0.7 U	0.7 U	4.1 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U
1,1,2,2-Tetrachloroethane	0.9 U	5.2 U	0.9 U	0.9 U	5.2 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	4.0	0.9 U
1,1-Dichloroethane	0.5 U	3.1 U	0.5 U	0.5 U	3.1 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
1,1-Dichloroethene	0.5 U	3.0 U	0.5 U	0.5 U	3.0 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
1,2,4-Trimethylbenzene	18	13	13	2.0	11	8.7	9.4	10	11	17	12	2.2
1,3,5-Trimethylbenzene	4.8	3.7 U	4.0	2.0 U	3.7 U	2.6	2.6	3.0	3.3	4.7	3.6	2.0 U
1,3-Dichlorobenzene	1.0	4.5 U	2.5 U	0.8 U	4.5 U	0.8 U	0.8 U	2.5 U	0.8 U	0.8 U	0.8 U	2.5 U
1,4-Dichlorobenzene	2.5 U	4.5 U	2.5 U	6.5	4.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U
2-Hexanone	1.7 U	3.1 U	1.8	0.5 U	3.1 U	0.5 U	0.5 U	1.7 U	1.7 U	0.5 U	0.5 U	1.7 U
4-Ethyltoluene	4.3	3.7 U	4.7	2.0 U	3.7 U	2.5	2.8	3.8	3.3	4.2	3.9	0.6 U
Acetone	44	18	22	110	69	50	66	66	130	100	160	160
Benzene	1.9	2.4 U	1.4	0.4 U	2.6	0.4 U	0.4 U	1.6	1.4	1.7	2.0	0.4 U
Carbon Disulfide	0.4 U	2.4 U	0.4 U	0.4 U	2.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Chlorobenzene	0.6 U	3.5 U	0.6 U	0.6 U	3.5 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
Chloroethane	0.4 U	2.0 U	0.4 U	0.4 U	2.0 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Chloroform	0.6 U	3.7 U	0.6 U	0.6 U	3.7 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
Chloromethane	1.3	1.9 U	0.9	1.3	1.9 U	1.1	1.2	0.9	1.0	1.1	1.0	1.0
cis-1,2-dichloroethene	0.5 U	3.0 U	0.5 U	0.5 U	3.0 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
Cyclohexane	17	12	1.4 U	9.4	2.6 U	9.8	9.0	1.4 U	1.4 U	8.7	12	1.4 U
Ethanol	22	55	41	47	69	32	33	28	19	38	46	4.2
Ethyl Acetate	0.5 U	2.7 U	0.5 U	0.5 U	2.7 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
Ethylbenzene	9.7	6.1	9.9	1.8 U	6.3	4.9	4.7	9.2	9.3	12	13	0.6 U
Freon 11	2.0	4.5 U	3.3	2.5	4.5 U	0.8 U	2.5	2.5	1.3	1.9	0.8 U	0.8 U
Freon 113	1.0 U	5.8 U	1.0 U	1.0 U	5.8 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Freon 12	2.7	3.7 U	5.3	2.8	3.7 U	2.7	2.9	3.3	1.9	2.7	2.1	0.6 U
Hexane	2.3	2.7 U	1.5	0.5 U	3.0	0.5 U	0.5 U	2.4	2.1	2.2	2.6	0.5 U
Isopropyl Alcohol	46	630	180	130	9,900	200	280	290	140	79	100	0.3 U
m&p-Xylene	41	26	37	4.1	28	21	21	32	34	47	50	4.1
Methyl Ethyl Ketone	2.1	2.2 U	9.6	3.4	6.2	3.2	6.1	5.1	2.0	2.8	4.4	5.0
Methyl Isobutyl ketone	0.5 U	3.1 U	0.5 U	1.7 U	3.1 U	3.4	4.6	1.8	0.5 U	1.7 U	1.7 U	0.5 U
Methylene Chloride	3.9	20	0.8 U	5.9	27	5.6	5.1	2.1	3.8	9.7	9.7	0.8 U
n-Heptane	6.9	5.5	2.7	6.5	3.1 U	2.0	1.8	3.0	3.3	3.2	4.6	0.5 U
o-Xylene	18	10	13	1.9	10	9.6	9.5	12	16	27	27	1.7
Propylene	0.3 U	1.3 U	0.7 U	0.3 U	1.3 U	0.3 U	0.3 U	0.7 U	0.3 U	0.3 U	0.3 U	1.6
Styrene	1.8 U	3.2 U	1.9	1.8 U	3.2 U	1.8 U	1.8 U	2.0	1.8 U	1.8 U	1.8 U	0.6 U

Table 2. Concentrations of Volatile Organic Compounds in Indoor Air and Ambient Air Collected in February and March 2006, Vapor Intrusion Study Report, Solvent Dock Area Former Lockheed Martin French Road Facility, Utica, New York

Sample ID	I1	I1-Retest	I3	I4	I4-Retest	I5	I10 (I5 DUP)	I6	I7	I8	I9	OD1
Lab ID:	06B07713	06B10826	06B07716	06B07701	06B10827	06B07703	06B07700	06B07714	06B07711	06B07707	06B07699	06B07717
Sample Date:	2/26/2006	3/30/2006	2/26/2006	2/26/2006	3/30/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006
Units:	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)
Tetrachloroethene	18	5.1 U	8.5	2.8	5.1 U	10	11.0	9.5	15	97	24	0.9 U
Tetrahydrofuran	1.2 U	2.2 U	1.2 U	1.2 U	2.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
Toluene	27	32	23	8.0	33	18	15	27	29	50	53	5.3
Trichloroethene	41	41	0.7 U	73	6.7	23	18	2.8	5.7	6.0	1.9	0.7 U
Vinyl Acetate	0.5 U	2.7 U	2.4	0.5 U	2.7 U	0.5 U	0.5 U	1.5 U	0.5 U	0.5 U	0.5 U	1.5 U
Vinyl Chloride	0.4 U	1.9 U	0.4 U	0.4 U	1.9 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U

Notes:

U - Not detected at the reporting limit

$\mu\text{g}/\text{m}^3$ - Micrograms per cubic meter



Table 3. Concentrations of Volatile Organic Compounds in Subslab Soil Gas Collected in April 2007, Vapor Intrusion Study Report, Solvent Dock Area
Former Lockheed Martin French Road Facility, Utica, New York

Constituent	Sample ID: Lab ID: Date: Units:	VP-1SD C0704029-001A 4/12/2007 (µg/m ³)	VP-2SD C0704029-002A 4/12/2007 (µg/m ³)	VP-3SD C0704029-003A 4/12/2007 (µg/m ³)	VP-4SD C0704029-004A 4/12/2007 (µg/m ³)	VP-5SD C0704029-005A 4/12/2007 (µg/m ³)	VP-7SD C0704029-006A 4/12/2007 (µg/m ³)	VP-8SD C0704029-007A 4/12/2007 (µg/m ³)
1,1,1-Trichloroethane		3.8	38	0.72 J	11	0.78 J	0.83 U	1.2
1,1,2,2-Tetrachloroethane		1 U	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane		0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U
1,1-Dichloroethane		0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U
1,1-Dichloroethene		0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
1,2,4-Trichlorobenzene		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
1,2,4-Trimethylbenzene		7	8	3.1	6.6	6.5 J	3.4	3
1,2-Dibromoethane		1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
1,2-Dichlorobenzene		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
1,2-Dichloroethane		0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U
1,2-Dichloropropane		0.7 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U
1,3,5-Trimethylbenzene		2.2	2.3	1	2	4.2	1.2	1
1,3-Butadiene		0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U
1,3-Dichlorobenzene		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
1,4-Dichlorobenzene		2.4	2.3	2.3	2.5	3.9	1.3	9.7
1,4-Dioxane		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
2,2,4-Trimethylpentane		1	0.71 U	0.71 U	0.71 U	4.3	0.71 U	0.71 U
4-Ethyltoluene		2.5	2.3	1.1	1.8	4.4	1.4	1.1
Acetone		57	33	64	43	270	390	24
Allyl Chloride		ND U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U
Benzene		7.8	3.9	4.9	1.2	24	28	2
Benzyl Chloride		0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U
Bromodichloromethane		1 U	1 U	1 U	1 U	1 U	1 U	1 U
Bromoform		1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U
Bromomethane		0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U
Carbon Disulfide		18	2.3	2.4	0.85	9.8	5.6	1.8
Carbon Tetrachloride		0.96 U	0.96 U	0.96 U	0.96 U	0.96 U	0.96 U	0.96 U
Chlorobenzene		0.7 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U	0.7 U
Chloroethane		0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Chloroform		7.7	7.2	0.74 U	25	5.1	0.65 J	3.2
Chloromethane		0.42	0.84	0.31 U	0.8	0.65	0.31	0.55
cis-1,2-Dichloroethene		0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
cis-1,3-Dichloropropene		0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U
Cyclohexane		29	8	47	2.3	66	64	5
Dibromochloromethane		1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U
Ethyl Acetate		0.92 U	0.92 U	5.6	0.92 U	0.92 U	0.92 U	0.92 U
Ethylbenzene		2.6	2.4	0.71	1.5	6.2 J	2.6	0.88



Table 3. Concentrations of Volatile Organic Compounds in Subslab Soil Gas Collected in April 2007, Vapor Intrusion Study Report, Solvent Dock Area
Former Lockheed Martin French Road Facility, Utica, New York

Constituent	Sample ID: Lab ID: Date: Units:	VP-1SD C0704029-001A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	VP-2SD C0704029-002A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	VP-3SD C0704029-003A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	VP-4SD C0704029-004A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	VP-5SD C0704029-005A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	VP-7SD C0704029-006A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	VP-8SD C0704029-007A 4/12/2007 ($\mu\text{g}/\text{m}^3$)
Freon 11		1.3	2.3	0.97	1.5	1.3	0.86 U	0.97
Freon 113		5.1	85	7.6	450	9.5	2.2	1.2 U
Freon 114		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
Freon 12		0.75 U	0.75 U	0.75 U	0.75 U	0.75 U	0.75 U	0.75 U
Heptane		27	7.2	11	3.6	170	40	7
Hexachloro-1,3-Butadiene		1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U
Hexane		62	12	59	0.54 U	250	67	7.9
Isopropyl Alcohol		150	44	250	190	170	87	800
m&p-Xylene		8.5	8.4	2.4	5.4	20	7.5	3.3
Methyl Butyl Ketone		1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
Methyl Ethyl Ketone		0.9 U	0.9 U	100	46	110	41	25
Methyl Isobutyl Ketone		1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
Methyl Tert-Butyl Ether		0.55	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U
Methylene Chloride		90	37	210	93	170	42	4,600
o-Xylene		2.7	2.8	0.84	1.9	6.2 J	2.3	1.1
Propylene		0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U
Styrene		0.69	2	0.65	0.65	0.65 U	0.65 U	0.52 J
Tetrachloroethene		1.8	9.5	1 U	40	0.97 J	8.4	5.4
Tetrahydrofuran		2	0.9	1.1	5.5	1.7	0.45 U	0.45 U
Toluene		11	15	6.6	7.2	58	49	5.9
trans-1,2-Dichloroethene		0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
trans-1,3-Dichloropropene		0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U
Trichloroethene		0.76 J	110	0.76 J	45	1.6	0.82 U	36
Vinyl Acetate		0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U
Vinyl Bromide		0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U
Vinyl Chloride		0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U

Notes:

J - Analyte detected at or below quantitation limits

U - Not detected at the reporting limit

$\mu\text{g}/\text{m}^3$ - Micrograms per cubic meter



Table 4. Concentrations of Volatile Organic Compounds in Indoor Air Collected in April 2007, Vapor Intrusion Study Report, Solvent Dock Area Former Lockheed Martin French Road Facility, Utica, New York

Constituent	Sample ID: Lab ID: Date: Units:	AA-2SD C0704036-001A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	AA-3SD C0704036-002A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	AA-4SD C0704036-003A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	AA-6SD C0704036-004A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	AA-8SD C0704036-005A 4/12/2007 ($\mu\text{g}/\text{m}^3$)
1,1,1-Trichloroethane		0.83 U	0.83 U	0.83 U	0.83 U	0.83 U
1,1,2,2-Tetrachloroethane		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
1,1,2-Trichloroethane		0.83 U	0.83 U	0.83 U	0.83 U	0.83 U
1,1-Dichloroethane		0.62 U	0.62 U	0.62 U	0.62 U	0.62 U
1,1-Dichloroethene		0.61 U	0.61 U	0.61 U	0.61 U	0.61 U
1,2,4-Trichlorobenzene		1.1 U	1.13 U	1.13 U	1.13 U	1.13 U
1,2,4-Trimethylbenzene		3.2	2.5	2.4	1.2	4.7
1,2-Dibromoethane		1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
1,2-Dichlorobenzene		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
1,2-Dichloroethane		0.62 U	0.62 U	0.62 U	0.62 U	0.62 U
1,2-Dichloropropane		0.71 U	0.71 U	0.71 U	0.71 U	0.71 U
1,3,5-Trimethylbenzene		1.5	1.4	1.0	0.75 U	1.7
1,3-Butadiene		0.34 U	0.34 U	0.34 U	0.34 U	0.34 U
1,3-Dichlorobenzene		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
1,4-Dichlorobenzene		1.4	0.86 J	1.5	0.92 U	11.9
1,4-Dioxane		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
2,2,4-Trimethylpentane		0.71 U	0.71 U	0.71 U	0.71 U	0.71 U
4-Ethyltoluene		1.7	1.25	1.15	0.75 U	2.65
Acetone		68	76	90	21	92
Allyl Chloride		0.48 U	0.48 U	0.48 U	0.48 U	0.48 U
Benzene		0.55	0.49	0.49	0.78	0.46 J
Benzyl Chloride		0.88 U	0.88 U	0.88 U	0.88 U	0.88 U
Bromodichloromethane		1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Bromoform		1.6 U	1.6 U	1.6 U	1.6 U	1.6 U
Bromomethane		0.59 U	0.59 U	0.59 U	0.59 U	0.59 U
Carbon Disulfide		0.41 J	0.48 U	0.48 U	0.44 J	0.48 U
Carbon Tetrachloride		0.26 U	0.26 U	0.26 U	0.26 U	0.26 U
Chlorobenzene		0.70 U	0.70 U	0.70 U	0.70 U	0.70 U
Chloroethane		0.40 U	0.40 U	0.40 U	0.40 U	0.40 U
Chloroform		0.74 U	0.74 U	0.74 U	0.74 U	0.74 U
Chloromethane		0.32 U	0.32 U	0.32 U	0.32 U	0.32 U
cis-1,2-Dichloroethene		0.60 U	0.60 U	0.60 U	0.60 U	0.60 U
cis-1,3-Dichloropropene		0.69 U	0.69 U	0.69 U	0.69 U	0.69 U
Cyclohexane		8.6	3.5	2.5	46	5.7
Dibromochloromethane		1.3 U	1.3 U	1.3 U	1.3 U	1.3 U
Ethyl Acetate		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
Ethylbenzene		0.49 J	0.44 J	0.66 U	0.57 J	0.49 J



Table 4. Concentrations of Volatile Organic Compounds in Indoor Air Collected in April 2007, Vapor Intrusion Study Report, Solvent Dock Area Former Lockheed Martin French Road Facility, Utica, New York

Constituent	Sample ID: Lab ID: Date: Units:	AA-2SD C0704036-001A 4/12/2007 (µg/m ³)	AA-3SD C0704036-002A 4/12/2007 (µg/m ³)	AA-4SD C0704036-003A 4/12/2007 (µg/m ³)	AA-6SD C0704036-004A 4/12/2007 (µg/m ³)	AA-8SD C0704036-005A 4/12/2007 (µg/m ³)
Freon 11		0.97	0.8 J	0.8 J	0.8 J	1.26
Freon 113		1.2 U	1.2 U	1.2 U	1.2 U	0.9 J
Freon 114		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
Freon 12		2.1	2.2	2.2	2.3	2.2
Heptane		5.0	2.4	3.6	0.67	10
Hexachloro-1,3-Butadiene		1.6 U	1.6 U	1.6 U	1.6 U	1.6 U
Hexane		0.54 U	0.54 U	0.54 U	1.72	0.54 U
Isopropyl Alcohol		481	499	504	20	1,250
m&p-Xylene		1.2 J	0.93 J	0.88 J	1.19 J	1.15 J
Methyl Butyl Ketone		1.3 U	1.3 U	1.3 U	1.3 U	1.3 U
Methyl Ethyl Ketone		137	270	261	6.9	147
Methyl Isobutyl Ketone		1.3 U	1.3 U	1.3 U	1.3 U	1.3 U
Methyl Tert-Butyl Ether		0.55 U	0.55 U	0.55 U	0.55 U	0.55 U
Methylene Chloride		263	242	198	7.5	4,950
o-Xylene		0.49 J	0.66 U	0.66 U	0.49 J	0.44 J
Propylene		0.26 U	0.26 U	0.26 U	0.26 U	0.26 U
Styrene		1.9	0.91	0.65	9.3	1.3
Tetrachloroethene		1.0 U	1.0 U	1.0	1.0 U	1.0 U
Tetrahydrofuran		0.45 U	0.45 U	0.45 U	0.45 U	0.45 U
Toluene		5.2	6.3	4.0	8.4	6.2
trans-1,2-Dichloroethene		0.60 U	0.60 U	0.60 U	0.60 U	0.60 U
trans-1,3-Dichloropropene		0.69 U	0.69 U	0.69 U	0.69 U	0.69 U
Trichloroethene		0.98	0.60	1.3	0.66	0.71
Vinyl Acetate		0.54 U	0.54 U	0.54 U	0.54 U	0.54 U
Vinyl Bromide		0.67 U	0.67 U	0.67 U	0.67 U	0.67 U
Vinyl Chloride		0.39 U	0.39 U	0.39 U	0.39 U	0.39 U

Notes:

J - Analyte detected at or below quantitation limits

U - Not detected at the reporting limit

µg/m³ - Micrograms per cubic meter

Table 5. Summary of Constituents Detected in Subslab Soil Gas and Indoor Air, Vapor Intrusion Study Report, Solvent Dock Area
Former Lockheed Martin French Road Facility, Utica, New York

Constituent	Groundwater Detected (a)	Subslab Soil Gas Data						Indoor Air Data					
		FOD		%	Detected	Min	Max	FOD		%	Detected	Min	Max
1,1,1-Trichloroethane	X	14 / 17	82%	X	0.72	260	0 / 15	0%	ND	--	--		
1,1,2,2-Tetrachloroethane	ND	0 / 17	0%	ND	--	--	1 / 15	7%	X	4.0	4.0		
1,1,2-Trichloroethane	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,1-Dichloroethane	X	6 / 17	35%	X	1.7	8.4	0 / 15	0%	ND	--	--		
1,1-Dichloroethene	ND	2 / 17	12%	X	5.1	7	0 / 15	0%	ND	--	--		
1,2,4-Trichlorobenzene	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,2,4-Trimethylbenzene	NA	16 / 17	94%	X	2.2	25	15 / 15	100%	X	1.2	18		
1,2-Dibromoethane	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,2-Dichlorobenzene	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,2-Dichloroethane	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,2-Dichloropropane	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,3,5-Trimethylbenzene	NA	15 / 17	88%	X	1.0	7.3	11 / 15	73%	X	1.0	4.8		
1,3-Butadiene	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
1,3-Dichlorobenzene	ND	2 / 17	12%	X	1.1	1.5	1 / 15	7%	X	1.0	1.0		
1,4-Dichlorobenzene	ND	8 / 17	47%	X	1.3	9.7	5 / 15	33%	X	0.86	12		
1,4-Dioxane	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
2-Hexanone	NA	1 / 10	10%	X	2.2	2.2	1 / 10	10%	X	1.8	1.8		
2,2,4-Trimethylpentane	NA	2 / 7	29%	X	1.0	4.3	0 / 5	0%	ND	--	--		
4-Ethyltoluene	NA	15 / 17	88%	X	1.1	7.4	11 / 15	73%	X	1.2	4.7		
Acetone	NA	17 / 17	100%	X	24	1,400	15 / 15	100%	X	18	160		
Allyl Chloride	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Benzene	X	16 / 17	94%	X	1.2	53	12 / 15	80%	X	0.46	2.6		
Benzyl Chloride	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Bromodichloromethane	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Bromoform	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Bromomethane	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Carbon Disulfide	NA	16 / 17	94%	X	0.85	25	2 / 15	13%	X	0.41	0.44		
Carbon Tetrachloride	ND	0 / 7	0%	ND	--	--	10 / 15	67%	X	--	--		
Chlorobenzene	ND	2 / 17	12%	X	1.1	2.4	0 / 15	0%	ND	--	--		
Chloroethane	X	1 / 17	6%	X	0.5	0.5	0 / 15	0%	ND	--	--		
Chloroform	ND	12 / 17	71%	X	0.65	25	0 / 15	0%	ND	--	--		
Chloromethane	ND	9 / 17	53%	X	0.31	1.0	8 / 15	53%	X	0.9	1.3		
cis-1,2-Dichloroethene	X	2 / 17	12%	X	2.8	4.8	0 / 15	0%	ND	--	--		
cis-1,3-Dichloropropene	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Cyclohexane	NA	14 / 17	82%	X	2.3	66	11 / 15	73%	X	2.5	46		
Dibromochloromethane	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Ethanol	NA	7 / 10	70%	X	6.1	140	10 / 10	100%	X	19	69		
Ethyl Acetate	NA	2 / 17	12%	X	1.0	5.6	0 / 15	0%	ND	--	--		
Ethylbenzene	ND	16 / 17	94%	X	0.71	58	13 / 15	87%	X	0.44	13		

Table 5. Summary of Constituents Detected in Subslab Soil Gas and Indoor Air, Vapor Intrusion Study Report, Solvent Dock Area
Former Lockheed Martin French Road Facility, Utica, New York

Constituent	Groundwater Detected (a)	Subslab Soil Gas Data						Indoor Air Data					
		FOD		%	Detected	Min	Max	FOD		%	Detected	Min	Max
Freon 11	ND	12 / 17	71%	X	0.97	5.7	10 / 15	67%	X	0.80	3.3		
Freon 113	NA	14 / 17	82%	X	1.3	450	1 / 15	7%	X	0.86	0.86		
Freon 114	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Freon 12	NA	9 / 17	53%	X	2.0	500	13 / 15	87%	X	1.9	5.3		
Heptane	NA	7 / 7	100%	X	3.6	170	5 / 5	100%	X	0.67	10		
Hexachloro-1,3-Butadiene	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Hexane	NA	15 / 17	88%	X	3.1	250	8 / 15	53%	X	1.5	3		
Isopropyl Alcohol	NA	16 / 17	94%	X	4.5	800	15 / 15	100%	X	20	9,900		
m&p-Xylene	X	16 / 17	94%	X	2.4	110	15 / 15	100%	X	0.88	50		
Methyl Butyl Ketone	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Methyl Ethyl Ketone	NA	14 / 17	82%	X	4.6	120	14 / 15	93%	X	2.0	270		
Methyl Isobutyl Ketone	NA	3 / 17	18%	X	2.9	9.6	2 / 15	13%	X	1.8	4.6		
Methyl Tert-Butyl Ether	NA	1 / 7	14%	X	0.55	0.55	0 / 5	0%	ND	--	--		
Methylene Chloride	ND	16 / 17	94%	X	2.2	4,600	14 / 15	93%	X	2.1	4,950		
n-Heptane	NA	7 / 10	70%	X	3.9	96	9 / 10	90%	X	1.8	6.9		
o-Xylene	X	16 / 17	94%	X	0.84	60	13 / 15	87%	X	0.44	27		
Propylene	NA	0 / 17	0%	ND	0	0	0 / 15	0%	ND	--	--		
Styrene	NA	7 / 17	41%	X	0.52	2.1	7 / 15	47%	X	0.65	9.3		
Tetrachloroethene	X	16 / 17	94%	X	0.97	21,000	9 / 15	60%	X	1.0	97		
Tetrahydrofuran	NA	6 / 17	35%	X	0.9	6.4	0 / 15	0%	ND	--	--		
Toluene	X	14 / 17	82%	X	5.9	160	15 / 15	100%	X	4.0	53		
trans-1,2-Dichloroethene	X	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
trans-1,3-Dichloropropene	ND	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Trichloroethene	X	16 / 17	94%	X	0.76	680	14 / 15	93%	X	0.60	73		
Vinyl Acetate	NA	2 / 17	12%	X	1.7	8.7	1 / 15	7%	X	2.4	2.4		
Vinyl Bromide	NA	0 / 7	0%	ND	--	--	0 / 5	0%	ND	--	--		
Vinyl Chloride	X	1 / 17	6%	X	0.50	0.50	0 / 15	0%	ND	--	--		

Notes:

X - Detected

ND - Not detected

NA - Not analyzed

Y - Yes

N - No

FOD - Frequency of detection

Min - Minimum detected concentration

Max - Maximum detected concentration

(a) - ND based on historical data indicating constituent not present

Table 6. Comparison of Constituents Detected in Indoor Air to NYSDOH Air Guidelines and Background Concentrations, Vapor Intrusion Study Report, Solvent Dock Area
Former Lockheed Martin French Road Facility, Utica, New York

Constituent	NYSDOH Air Guideline ($\mu\text{g}/\text{m}^3$)	USEPA BASE Background Value (a) ($\mu\text{g}/\text{m}^3$)	Sample Type:	Indoor Air	Indoor Air	Soil Gas	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Indoor Air	Soil Gas	Indoor Air	Indoor Air
			Sample ID:	I1	I1-Retest	S1 (b)	S2 (b)	I3	S3 (b)	I4	I4-Retest	S4 (b)	I5	I10 (I5 DUP)
			Lab ID:	06B07713	06B10826	06B07706	06B07698	06B07716	06B07708	06B07701	06B10827	06B07702	06B07703	06B07700
			Date:	2/26/2006	3/30/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	3/30/2006	2/26/2006	2/26/2006	2/26/2006
			Units:	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)	($\mu\text{g}/\text{m}^3$)
1,1,1-Trichloroethane	--	20.6		0.7 U	4.1 U	33 U	260	0.7 U	67	0.7 U	4.1 U	54	0.7 U	0.7 U
1,1,2,2-Tetrachloroethane	--	<1.5		0.9 U	5.2 U	42 U	0.9 U	0.9 U	0.9 U	0.9 U	5.2 U	0.9 U	0.9 U	0.9 U
1,1,2-Trichloroethane	--	<1.5		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,1-Dichloroethane	--	<0.7		0.5 U	3.1 U	25 U	8.4	0.5 U	0.5 U	0.5 U	3.1 U	0.5 U	0.5 U	0.5 U
1,1-Dichloroethene	--	<1.4		0.5 U	3.0 U	24 U	0.5 U	0.5 U	0.5 U	0.5 U	3.0 U	0.5 U	0.5 U	0.5 U
1,2,4-Trichlorobenzene	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,2,4-Trimethylbenzene	--	9.5		18	13	99 U	6.9	13	25	2.0	11	24	8.7	9.4
1,2-Dibromoethane	--	<1.5		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,2-Dichlorobenzene	--	<1.2		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,2-Dichloroethane	--	<0.9		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,2-Dichloropropane	--	<1.6		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,3,5-Trimethylbenzene	--	3.7		4.8	3.7 U	99 U	2.2	4.0	5.4	2.0 U	3.7 U	6.8	2.6	2.6
1,3-Butadiene	--	<3.0		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,3-Dichlorobenzene	--	<2.4		1.0	4.5 U	36 U	0.8 U	2.5 U	0.8 U	0.8 U	4.5 U	0.8 U	0.8 U	0.8 U
1,4-Dichlorobenzene	--	5.5		2.5 U	4.5 U	130 U	2.5 U	2.5 U	2.5 U	6.5	4.5 U	2.5 U	2.5 U	2.5 U
1,4-Dioxane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
2-Hexanone	--	--		1.7 U	3.1 U	25 U	0.5 U	1.8	0.5 U	0.5 U	3.1 U	0.5 U	0.5 U	0.5 U
2,2,4-Trimethylpentane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
4-Ethyltoluene	--	3.6		4.3	3.7 U	99 U	2.0	4.7	5.4	2.0 U	3.7 U	6.6	2.5	2.8
Acetone	--	98.9		44	18	250	250	22	210	110	69	1,400	50	66
Allyl Chloride	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Benzene	--	9.4		1.9	2.4 U	20 U	23	1.4	3.5	0.4 U	2.6	53	0.4 U	0.4 U
Benzyl Chloride	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Bromodichloromethane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Bromoform	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Bromomethane	--	<1.7		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Carbon Disulfide	--	4.2		0.4 U	2.4 U	19 U	6.0	0.4 U	3.1	0.4 U	2.4 U	20	0.4 U	0.4 U
Carbon Tetrachloride	--	<1.3		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Chlorobenzene	--	<0.9		0.6 U	3.5 U	28 U	1.1	0.6 U	0.6 U	0.6 U	3.5 U	2.4	0.6 U	0.6 U
Chloroethane	--	<1.1		0.4 U	2.0 U	16 U	0.4 U	0.4 U	0.4 U	0.4 U	2.0 U	0.4 U	0.4 U	0.4 U
Chloroform	--	1.1		0.6 U	3.7 U	30 U	7.0	0.6 U	0.6 U	0.6 U	3.7 U	9.8	0.6 U	0.6 U
Chloromethane	--	3.7		1.3	1.9 U	15 U	0.6	0.9	0.3 U	1.3	1.9 U	0.3 U	1.1	1.2
cis-1,2-Dichloroethene	--	<1.9		0.5 U	3.0 U	24 U	0.5 U	0.5 U	0.5 U	0.5 U	3.0 U	0.5 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	--	<2.3		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cyclohexane	--	--		17	12	69 U	32	1.4 U	1.4 U	9.4	2.6 U	52	9.8	9.0
Dibromochloromethane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Ethanol	--	210		22	55	51	140	41	0.8 U	47	69	0.8 U	32	33

Table 6. Comparison of Constituents Detected in Indoor Air to NYSDOH Air Guidelines and Background Concentrations, Vapor Intrusion Study Report, Solvent Dock Area
Former Lockheed Martin French Road Facility, Utica, New York

Constituent	NYSDOH Air Guideline (µg/m ³)	USEPA BASE Background Value (a) (µg/m ³)	Sample Type:	Indoor Air	Indoor Air	Soil Gas	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Indoor Air	Soil Gas	Indoor Air	Indoor Air
			Sample ID:	I1	I1-Retest	S1 (b)	S2 (b)	I3	S3 (b)	I4	I4-Retest	S4 (b)	I5	I10 (I5 DUP)
			Lab ID: Date: Units:	06B07713 2/26/2006 (µg/m ³)	06B10826 3/30/2006 (µg/m ³)	06B07706 2/26/2006 (µg/m ³)	06B07698 2/26/2006 (µg/m ³)	06B07716 2/26/2006 (µg/m ³)	06B07708 2/26/2006 (µg/m ³)	06B07701 2/26/2006 (µg/m ³)	06B10827 3/30/2006 (µg/m ³)	06B07702 2/26/2006 (µg/m ³)	06B07703 2/26/2006 (µg/m ³)	06B07700 2/26/2006 (µg/m ³)
Ethyl Acetate	--	5.4		0.5 U	2.7 U	22 U	1.0	0.5 U	0.5 U	0.5 U	2.7 U	0.5 U	0.5 U	0.5 U
Ethylbenzene	--	5.7		9.7	6.1	26 U	18.0	9.9	9.0	1.8 U	6.3	58	4.9	4.7
Freon 11	--	18.1		2.0	4.5 U	36 U	1.9	3.3	5.7	2.5	4.5 U	0.8 U	0.8 U	2.5
Freon 113	--	3.5		1.0 U	5.8 U	46 U	3.6	1.0 U	4.7	1.0 U	5.8 U	190	1.0 U	1.0 U
Freon 114	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Freon 12	--	16.5		2.7	3.7 U	30 U	2.4	5.3	190	2.8	3.7 U	2.7	2.7	2.9
Heptane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Hexachloro-1,3-butadiene	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Hexane	--	10.2		2.3	2.7 U	22 U	82	1.5	3.1	0.5 U	3.0	140	0.5 U	0.5 U
Isopropyl Alcohol	--	--		46	630	15 U	43	180	95	130	9,900	74	200	280
m&p-Xylene	--	22.2		41	26	180 U	47	37	38	4.1	28	99	21	21
Methyl Butyl Ketone	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methyl Ethyl Ketone	--	12		2.1	2.2 U	18 U	25	9.6	23	3.4	6.2	52	3.2	6.1
Methyl Isobutyl Ketone	--	--		0.5 U	3.1 U	82 U	3.8	0.5 U	1.7 U	1.7 U	3.1 U	1.7 U	3.4	4.6
Methyl Tert-Butyl Ether	--	11.5		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	60	10 (c)		3.9	20	70 U	8.0	0.8 U	4.4	5.9	27	3.4	5.6	5.1
n-Heptane	--	--		6.9	5.5	25 U	65	2.7	3.9	6.5	3.1 U	96	2.0	1.8
o-Xylene	--	7.9		18	10	87 U	17	13	16	1.9	10	60	9.6	9.5
Propylene	--	--		0.3 U	1.3 U	11 U	0.3 U	0.7 U	0.3 U	0.3 U	1.3 U	0.3 U	0.3 U	0.3 U
Styrene	--	1.9		1.8 U	3.2 U	86 U	1.8 U	1.9	1.8 U	1.8 U	3.2 U	0.6 U	1.8 U	1.8 U
Tetrachloroethene	100	16 (c)		18	5.1 U	21,000	76	8.5	34	2.8	5.1 U	660	10	11.0
Tetrahydrofuran	--	--		1.2 U	2.2 U	59 U	6.4	1.2 U	1.2 U	1.2 U	2.2 U	1.2 U	1.2 U	1.2 U
Toluene	--	43		27	32	76 U	70	23	25	8.0	33	1.6 U	18	15
trans-1,2-Dichloroethene	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
trans-1,3-Dichloropropene	--	<1.3		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Trichloroethene	5	4.2 (c)		41	41	680	560	0.7 U	7	73	6.7	2.5	23	18
Vinyl Acetate	--	--		0.5 U	2.7 U	22 U	0.5 U	2.4	1.7	0.5 U	2.7 U	0.5 U	0.5 U	0.5 U
Vinyl Bromide	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Vinyl Chloride	--	<1.9		0.4 U	1.9 U	16 U	0.5	0.4 U	0.4 U	0.4 U	1.9 U	0.4 U	0.4 U	0.4 U



Table 6. Comparison of Subslab Soil Gas and Indoor Air Results for COPCs to NYSDOH Air Guidelines and Background Concentrations, Vapor Intrusion Study Report, Solvent Dock Area Lockheed Martin Corporation, French Road Facility, Utica, NY

Constituent	NYSDOH Air Guideline (µg/m³)	USEPA BASE Background Value (a) (µg/m³)	Sample Type:	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Soil Gas	Soil Gas	Soil Gas
			Sample ID:	S5 (b)	I6	S6 (b)	I7	S7 (b)	I8	S8 (b)	I9	S9 (b)	S10 (b)	S10 (b)
			Lab ID:	06B07712	06B07714	06B07715	06B07711	06B07710	06B07707	06B07705	06B07699	06B07704	06B07709	
			Date:	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	4/12/2007
			Units:	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)
1,1,1-Trichloroethane	--	20.6		120	0.7 U	6.3	0.7 U	30	0.7 U	77	0.7 U	14	0.7 U	3.8
1,1,2,2-Tetrachloroethane	--	<1.5		0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	4.0	0.9 U	0.9 U	1 U
1,1,2-Trichloroethane	--	<1.5		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.83 U
1,1-Dichloroethane	--	<0.7		1.7	0.5 U	6.2	0.5 U	5.1	0.5 U	3.8	0.5 U	3.8	0.5 U	0.62 U
1,1-Dichloroethene	--	<1.4		0.5 U	0.5 U	5.1	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	7.0	0.5 U	0.6 U
1,2,4-Trichlorobenzene	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.1 U
1,2,4-Trimethylbenzene	--	9.5		21	10	20	11	13	17	18	12	2.2	18	7
1,2-Dibromoethane	--	<1.5		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.2 U
1,2-Dichlorobenzene	--	<1.2		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.92 U
1,2-Dichloroethane	--	<0.9		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.62 U
1,2-Dichloropropane	--	<1.6		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.7 U
1,3,5-Trimethylbenzene	--	3.7		7.3	3.0	6.3	3.3	4.0	4.7	4.5	3.6	2.0 U	5.3	2.2
1,3-Butadiene	--	<3.0		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.34 U
1,3-Dichlorobenzene	--	<2.4		1.1	2.5 U	2.5 U	0.8 U	1.5	0.8 U	0.8 U	0.8 U	0.8 U	0.8 U	0.92 U
1,4-Dichlorobenzene	--	5.5		2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	5.1	2.5 U	2.4
1,4-Dioxane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.1 U
2-Hexanone	--	--		1.7 U	1.7 U	1.7 U	1.7 U	1.7 U	0.5 U	2.2	0.5 U	0.5 U	1.7 U	NA
2,2,4-Trimethylpentane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1
4-Ethyltoluene	--	3.6		7.4	3.8	6.3	3.3	4.2	4.2	4.9	3.9	2.0 U	5.1	2.5
Acetone	--	98.9		480	66	230	130	500	100	610	160	320	74	57
Allyl Chloride	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	ND U
Benzene	--	9.4		17	1.6	5.1	1.4	31	1.7	48	2.0	9.9	2.1	7.8
Benzyl Chloride	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.88 U
Bromodichloromethane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1 U
Bromoform	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.6 U
Bromomethane	--	<1.7		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.59 U
Carbon Disulfide	--	4.2		10	0.4 U	4.0	0.4 U	25	0.4 U	6.4	0.4 U	1.3	1.4	18
Carbon Tetrachloride	--	<1.3		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.96 U
Chlorobenzene	--	<0.9		0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.7 U
Chloroethane	--	<1.1		0.4 U	0.4 U	0.4 U	0.4 U	0.5	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Chloroform	--	1.1		2.9	0.6 U	12	0.6 U	1.5	0.6 U	0.6 U	0.6 U	0.6 U	1.8	7.7
Chloromethane	--	3.7		0.3 U	0.9	0.3 U	1.0	0.8	1.1	0.3 U	1.0	1.0	0.3 U	0.42
cis-1,2-Dichloroethene	--	<1.9		0.5 U	0.5 U	2.8	0.5 U	4.8	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.6 U
cis-1,3-Dichloropropene	--	<2.3		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.69 U
Cyclohexane	--	--		13	1.4 U	3.4	1.4 U	50	8.7	46	12	43	1.4 U	29
Dibromochloromethane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.3 U
Ethanol	--	210		0.8 U	28	26	19	39	38	51	46	57	6.1	NA

Table 6. Comparison of Subslab Soil Gas and Indoor Air Results for COPCs to NYSDOH Air Guidelines and Background Concentrations, Vapor Intrusion Study Report, Solvent Dock Area Lockheed Martin Corporation, French Road Facility, Utica, NY

Constituent	NYSDOH Air Guideline (µg/m ³)	USEPA BASE Background Value (a) (µg/m ³)	Sample Type: Sample ID:	Soil Gas S5 (b)	Indoor Air I6	Soil Gas S6 (b)	Indoor Air I7	Soil Gas S7 (b)	Indoor Air I8	Soil Gas S8 (b)	Indoor Air I9	Soil Gas S9 (b)	Soil Gas S10 (b)	Soil Gas VP-1SD (b) C0704029-001A
			Lab ID: 06B07712	06B07712	06B07714	06B07715	06B07711	06B07710	06B07707	06B07705	06B07699	06B07704	06B07709	4/12/2007
			Date: 2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006	2/26/2006
			Units: (µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)
Ethyl Acetate	--	5.4		0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
Ethylbenzene	--	5.7		26	9.2	35	9.3	14	12	22	13	2.2	13.0	2.6
Freon 11	--	18.1		1.1	2.5	3.9	1.3	1.5	1.9	0.8 U	0.8 U	0.8 U	1.2	1.3
Freon 113	--	3.5		270	1.0 U	1.0 U	1.0 U	88	1.0 U	240	1.0 U	11	1.3	5.1
Freon 114	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.1 U
Freon 12	--	16.5		2.5	3.3	500	1.9	2.3	2.7	2.0	2.1	2.5	2.3	0.75 U
Heptane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	27
Hexachloro-1,3-butadiene	--	<6.8		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.6 U
Hexane	--	10.2		28	2.4	8.3	2.1	120	2.2	79	2.6	57	6.7	62
Isopropyl Alcohol	--	--		110	290	11	140	13	79	7	100	110	4.5	150
m&p-Xylene	--	22.2		96	32	110	34	50	47	68	50	6.4	52	8.5
Methyl Butyl Ketone	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.2 U
Methyl Ethyl Ketone	--	12		120	5.1	22	2.0	17	2.8	45	4.4	6.1	4.6	0.9 U
Methyl Isobutyl Ketone	--	--		9.6	1.8	2.9	0.5 U	0.5 U	1.7 U	1.7 U	1.7 U	1.7 U	0.5 U	1.2 U
Methyl Tert-Butyl Ether	--	11.5		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.55
Methylene Chloride	60	N/A		2.4	2.1	2.8	3.8	11.0	9.7	2.2	9.7	9.8	2.7	90
n-Heptane	--	--		0.5 U	3.0	9.8	3.3	0.5 U	3.2	58	4.6	15	12	NA
o-Xylene	--	7.9		48	12	31	16	22.0	27	26.0	27	3.0	23	2.7
Propylene	--	--		0.3 U	0.7 U	0.7 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.26 U
Styrene	--	1.9		1.8 U	2.0	2.1	1.8 U	1.8 U	1.8 U	1.8 U	1.8 U	1.8	1.8 U	0.69
Tetrachloroethene	100	N/A		26	9.5	280	15	95	97	35	24	5	260	1.8
Tetrahydrofuran	--	--		1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	2
Toluene	--	43		1.6 U	27	47	29	68	50	160	53	32	40	11
trans-1,2-Dichloroethene	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.6 U
trans-1,3-Dichloropropene	--	<1.3		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.69 U
Trichloroethene	5	N/A		4.7	2.8	32	5.7	30	6.0	3.4	1.9	21	70	0.76 J
Vinyl Acetate	--	--		0.5 U	1.5 U	1.5 U	0.5 U	0.5 U	0.5 U	8.7	0.5 U	0.5 U	0.5 U	0.54 U
Vinyl Bromide	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.67 U
Vinyl Chloride	--	<1.9		0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.39 U



Table 6. Comparison of Subslab Soil Gas and Indoor Air Results for COPCs to NYSDOH Air Guidelines and Background Concentrations, Vapor Intrusion Study Report, Solvent Dock Area
Lockheed Martin Corporation, French Road Facility, Utica, NY

Constituent	NYSDOH Air Guideline (µg/m ³)	USEPA BASE Background Value (a) (µg/m ³)	Sample Type:	Indoor Air	Indoor Air	Indoor Air	Soil Gas	Indoor Air	Soil Gas	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Soil Gas
			Sample ID:	AA-2SD	VP-2SD (b)	AA-3SD	VP-3SD (b)	AA-4SD	VP-4SD (b)	VP-5SD (b)	AA-6SD	VP-7SD (b)	AA-8SD	VP-8SD (b)
			Lab ID:	C0704036-	C0704029-	C0704036-	C0704029-	C0704036-	C0704029-	C0704029-	C0704036-	C0704029-	C0704036-	C0704029-
			Date:	001A	002A	002A	003A	003A	004A	005A	004A	006A	005A	007A
			Units:	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)	(µg/m ³)
1,1,1-Trichloroethane	--	20.6		0.83 U	38	0.83 U	0.72 J	0.83 U	11	0.78 J	0.83 U	0.83 U	0.83 U	1.2
1,1,2,2-Tetrachloroethane	--	<1.5		1.1 U	1 U	1.1 U	1 U	1.1 U	1 U	1 U	1.1 U	1 U	1.1 U	1 U
1,1,2-Trichloroethane	--	<1.5		0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U	0.83 U
1,1-Dichloroethane	--	<0.7		0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U
1,1-Dichloroethene	--	<1.4		0.61 U	0.6 U	0.61 U	0.6 U	0.61 U	0.6 U	0.6 U	0.61 U	0.6 U	0.61 U	0.6 U
1,2,4-Trichlorobenzene	--	<6.8		1.1 U	1.1 U	1.13 U	1.1 U	1.13 U	1.1 U	1.1 U	1.13 U	1.1 U	1.13 U	1.1 U
1,2,4-Trimethylbenzene	--	9.5		3.2	8	2.5	3.1	2.4	6.6	6.5 J	1.2	3.4	4.7	3
1,2-Dibromoethane	--	<1.5		1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U	1.2 U
1,2-Dichlorobenzene	--	<1.2		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
1,2-Dichloroethane	--	<0.9		0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U	0.62 U
1,2-Dichloropropane	--	<1.6		0.71 U	0.7 U	0.71 U	0.7 U	0.71 U	0.7 U	0.7 U	0.71 U	0.7 U	0.71 U	0.7 U
1,3,5-Trimethylbenzene	--	3.7		1.5	2.3	1.4	1	1.0	2	4.2	0.75 U	1.2	1.7	1
1,3-Butadiene	--	<3.0		0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U	0.34 U
1,3-Dichlorobenzene	--	<2.4		0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
1,4-Dichlorobenzene	--	5.5		1.4	2.3	0.86 J	2.3	1.5	2.5	3.9	0.92 U	1.3	11.9	9.7
1,4-Dioxane	--	--		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
2-Hexanone	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
2,2,4-Trimethylpentane	--	--		0.71 U	0.71 U	0.71 U	0.71 U	0.71 U	0.71 U	4.3	0.71 U	0.71 U	0.71 U	0.71 U
4-Ethyltoluene	--	3.6		1.7	2.3	1.25	1.1	1.15	1.8	4.4	0.75 U	1.4	2.65	1.1
Acetone	--	98.9		68	33	76	64	90	43	270	21	390	92	24
Allyl Chloride	--	--		0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U	0.48 U
Benzene	--	9.4		0.55	3.9	0.49	4.9	0.49	1.2	24	0.78	28	0.46 J	2
Benzyl Chloride	--	<6.8		0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U	0.88 U
Bromodichloromethane	--	--		1.0 U	1 U	1.0 U	1 U	1.0 U	1 U	1 U	1.0 U	1 U	1.0 U	1 U
Bromoform	--	--		1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U
Bromomethane	--	<1.7		0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U	0.59 U
Carbon Disulfide	--	4.2		0.41 J	2.3	0.48 U	2.4	0.48 U	0.85	9.8	0.44 J	5.6	0.48 U	1.8
Carbon Tetrachloride	--	<1.3		0.26 U	0.96 U	0.26 U	0.96 U	0.26 U	0.96 U	0.96 U	0.26 U	0.96 U	0.26 U	0.96 U
Chlorobenzene	--	<0.9		0.70 U	0.7 U	0.70 U	0.7 U	0.70 U	0.7 U	0.7 U	0.70 U	0.7 U	0.70 U	0.7 U
Chloroethane	--	<1.1		0.40 U	0.4 U	0.40 U	0.4 U	0.40 U	0.4 U	0.4 U	0.40 U	0.4 U	0.40 U	0.4 U
Chloroform	--	1.1		0.74 U	7.2	0.74 U	0.74 U	0.74 U	25	5.1	0.74 U	0.65 J	0.74 U	3.2
Chloromethane	--	3.7		0.32 U	0.84	0.32 U	0.31 U	0.32 U	0.8	0.65	0.32 U	0.31	0.32 U	0.55
cis-1,2-Dichloroethene	--	<1.9		0.60 U	0.6 U	0.60 U	0.6 U	0.60 U	0.6 U	0.6 U	0.60 U	0.6 U	0.60 U	0.6 U
cis-1,3-Dichloropropene	--	<2.3		0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U
Cyclohexane	--	--		8.6	8	3.5	47	2.5	2.3	66	46	64	5.7	5
Dibromochloromethane	--	--		1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U	1.3 U
Ethanol	--	210		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA



Table 6. Comparison of Subslab Soil Gas and Indoor Air Results for COPCs to NYSDOH Air Guidelines and Background Concentrations, Vapor Intrusion Study Report, Solvent Dock Area Lockheed Martin Corporation, French Road Facility, Utica, NY

Constituent	NYSDOH Air Guideline (µg/m³)	USEPA BASE Background Value (a) (µg/m³)	Sample Type:	Indoor Air	Indoor Air	Indoor Air	Soil Gas	Indoor Air	Soil Gas	Soil Gas	Indoor Air	Soil Gas	Indoor Air	Soil Gas
			Sample ID:	AA-2SD	VP-2SD (b)	AA-3SD	VP-3SD (b)	AA-4SD	VP-4SD (b)	VP-5SD (b)	AA-6SD	VP-7SD (b)	AA-8SD	VP-8SD (b)
			Lab ID:	C0704036-001A	C0704029-002A	C0704036-002A	C0704029-003A	C0704036-003A	C0704029-004A	C0704029-005A	C0704036-004A	C0704029-006A	C0704036-005A	C0704029-007A
			Date:	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007	4/12/2007
			Units:	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)	(µg/m³)
Ethyl Acetate	--	5.4		0.92 U	0.92 U	0.92 U	5.6	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U	0.92 U
Ethylbenzene	--	5.7		0.49 J	2.4	0.44 J	0.71	0.66 U	1.5	6.2 J	0.57 J	2.6	0.49 J	0.88
Freon 11	--	18.1		0.97	2.3	0.8 J	0.97	0.8 J	1.5	1.3	0.8 J	0.86 U	1.26	0.97
Freon 113	--	3.5		1.2 U	85	1.2 U	7.6	1.2 U	450	9.5	1.2 U	2.2	0.9 J	1.2 U
Freon 114	--	<6.8		1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U	1.1 U
Freon 12	--	16.5		2.1	0.75 U	2.2	0.75 U	2.2	0.75 U	0.75 U	2.3	0.75 U	2.2	0.75 U
Heptane	--	--		5.0	7.2	2.4	11	3.6	3.6	170	0.67	40	10	7
Hexachloro-1,3-butadiene	--	<6.8		1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U
Hexane	--	10.2		0.54 U	12	0.54 U	59	0.54 U	0.54 U	250	1.72	67	0.54 U	7.9
Isopropyl Alcohol	--	--		481	44	499	250	504	190	170	20	87	1,250	800
m&p-Xylene	--	22.2		1.2 J	8.4	0.93 J	2.4	0.88 J	5.4	20	1.19 J	7.5	1.15 J	3.3
Methyl Butyl Ketone	--	--		1.3 U	1.2 U	1.3 U	1.2 U	1.3 U	1.2 U	1.2 U	1.3 U	1.2 U	1.3 U	1.2 U
Methyl Ethyl Ketone	--	12		137	0.9 U	270	100	261	46	110	6.9	41	147	25
Methyl Isobutyl Ketone	--	--		1.3 U	1.2 U	1.3 U	1.2 U	1.3 U	1.2 U	1.2 U	1.3 U	1.2 U	1.3 U	1.2 U
Methyl Tert-Butyl Ether	--	11.5		0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U	0.55 U
Methylene Chloride	60	N/A		263	37	242	210	198	93	170	7.5	42	4,950	4,600
n-Heptane	--	--		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
o-Xylene	--	7.9		0.49 J	2.8	0.66 U	0.84	0.66 U	1.9	6.2 J	0.49 J	2.3	0.44 J	1.1
Propylene	--	--		0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U	0.26 U
Styrene	--	1.9		1.9	2	0.91	0.65	0.65	0.65	0.65 U	9.3	0.65 U	1.3	0.52 J
Tetrachloroethene	100	N/A		1.0 U	9.5	1.0 U	1 U	1.0	40	0.97 J	1.0 U	8.4	1.0 U	5.4
Tetrahydrofuran	--	--		0.45 U	0.9	0.45 U	1.1	0.45 U	5.5	1.7	0.45 U	0.45 U	0.45 U	0.45 U
Toluene	--	43		5.2	15	6.3	6.6	4.0	7.2	58	8.4	49	6.2	5.9
trans-1,2-Dichloroethene	--	--		0.60 U	0.6 U	0.60 U	0.6 U	0.60 U	0.6 U	0.6 U	0.60 U	0.6 U	0.60 U	0.6 U
trans-1,3-Dichloropropene	--	<1.3		0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U	0.69 U
Trichloroethene	5	N/A		0.98	110	0.60	0.76 J	1.3	45	1.6	0.66	0.82 U	0.71	36
Vinyl Acetate	--	--		0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U	0.54 U
Vinyl Bromide	--	--		0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U	0.67 U
Vinyl Chloride	--	<1.9		0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U	0.39 U

Notes:

(a) 90% percentile background value (USEPA 2001. Building Assessment and Survey Evaluation (BASE))

(b) Subslab soil gas results for use in comparison to indoor air values only; subslab soil gas not compared to Air Guideline or background values

Indoor air cells exceeding the NYSDOH air guideline are shaded gray

Indoor air cells exceeding the NYSDOH background value are boldfaced

-- - Value not available

J - Analyte detected at or below quantitation limits

NA - Not analyzed

NYSDOH - New York State Department of Health

U - Not detected at the reporting limit

USEPA - U.S. Environmental Protection Agency

•g/m³ - Micrograms per cubic meter



Table 7. Evaluation of Potential Mitigation and Monitoring Actions Using NYSDOH Matrices, Vapor Intrusion Study Report, Solvent Dock Area, Former Lockheed Martin French Road Facility, Utica, New York.

Constituent	Sample ID: Lab ID: Date: Units:	S1 06B07706 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		17	No Further Action
Tetrachloroethene		21,000	Mitigate
Trichloroethene		680	Mitigate
1,1-Dichloroethene		12	No Further Action
cis-1,2-Dichloroethene		12	No Further Action
Vinyl chloride		8	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	S2 06B07698 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		260	Monitor
Tetrachloroethene		76	No Further Action
Trichloroethene		560	Mitigate
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.5	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	S3 06B07708 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		67	No Further Action
Tetrachloroethene		34	No Further Action
Trichloroethene		7	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	S4 06B07702 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		54	No Further Action
Tetrachloroethene		660	Monitor
Trichloroethene		2.5	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action



Table 7. Evaluation of Potential Mitigation and Monitoring Actions Using NYSDOH Matrices, Vapor Intrusion Study Report, Solvent Dock Area, Former Lockheed Martin French Road Facility, Utica, New York.

Constituent	Sample ID: Lab ID: Date: Units:	S5 06B07712 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		120	Monitor
Tetrachloroethene		26	No Further Action
Trichloroethene		4.7	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	S6 06B07715 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		6.3	No Further Action
Tetrachloroethene		280	Monitor
Trichloroethene		32	No Further Action
1,1-Dichloroethene		5.1	No Further Action
cis-1,2-Dichloroethene		2.8	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	S7 06B07710 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		30	No Further Action
Tetrachloroethene		95	No Further Action
Trichloroethene		30	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		4.8	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	S8 06B07705 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		77	No Further Action
Tetrachloroethene		35	No Further Action
Trichloroethene		3.4	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Table 7. Evaluation of Potential Mitigation and Monitoring Actions Using NYSDOH Matrices, Vapor Intrusion Study Report, Solvent Dock Area, Former Lockheed Martin French Road Facility, Utica, New York.

Constituent	Sample ID: Lab ID: Date: Units:	S9 06B07704 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		14	No Further Action
Tetrachloroethene		5	No Further Action
Trichloroethene		21	No Further Action
1,1-Dichloroethene		7	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action
Constituent	Sample ID: Lab ID: Date: Units:	S10 06B07709 2/26/2006 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		0.4	No Further Action
Tetrachloroethene		260	Monitor
Trichloroethene		70	Monitor
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action
Constituent	Sample ID: Lab ID: Date: Units:	VP-1SD C0704029-001A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		3.8	No Further Action
Tetrachloroethane		1.8	No Further Action
Trichloroethene		0.76 J	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action
Constituent	Sample ID: Lab ID: Date: Units:	VP-2SD C0704029-002A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		38	No Further Action
Tetrachloroethane		9.5	No Further Action
Trichloroethene		110	Monitor
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Table 7. Evaluation of Potential Mitigation and Monitoring Actions Using NYSDOH Matrices, Vapor Intrusion Study Report, Solvent Dock Area, Former Lockheed Martin French Road Facility, Utica, New York.

Constituent	Sample ID: Lab ID: Date: Units:	VP-3SD C0704029-003A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		0.72 J	No Further Action
Tetrachloroethane		0.5	No Further Action
Trichloroethene		0.76 J	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	VP-4SD C0704029-004A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		11	No Further Action
Tetrachloroethane		40	No Further Action
Trichloroethene		45	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	VP-5SD C0704029-005A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		0.78 J	No Further Action
Tetrachloroethane		0.97 J	No Further Action
Trichloroethene		1.6	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	VP-7SD C0704029-006A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		0.4	No Further Action
Tetrachloroethane		8.4	No Further Action
Trichloroethene		0.4	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action

Constituent	Sample ID: Lab ID: Date: Units:	VP-8SD C0704029-007A 4/12/2007 ($\mu\text{g}/\text{m}^3$)	Matrix Result Subslab Only
1,1,1-Trichloroethane		1.2	No Further Action
Tetrachloroethane		5.4	No Further Action
Trichloroethene		36	No Further Action
1,1-Dichloroethene		0.3	No Further Action
cis-1,2-Dichloroethene		0.3	No Further Action
Vinyl chloride		0.2	No Further Action


Notes:

Non-detected compounds are italicized and presented at 1/2 the detection limit

J - Analyte detected at or below quantitation limits

NYSDOH - New York State Department of Health

$\mu\text{g}/\text{m}^3$ - Micrograms per cubic meter



Source: USGS, 1955
Scale: 1:24000




482 CONGRESS ST. SUITE 501
PORTLAND, ME 04101
PHONE: 207.828.0046 FAX: 207.828.0062

FORMER LOCKHEED MARTIN FRENCH ROAD
FACILITY
SITE LOCATION

VAPOR INTRUSION STUDY REPORT
SOLVENT DOCK AREA
UTICA, NEW YORK

PROJECT MANAGER C. Motta	DRAWING NUMBER
CHECKED BY J. Bonsteel	PROJECT NUMBER AY000265.0015
DATE DRAWN July 27, 2005	FIGURE NUMBER 1



LEGEND	
	MW-1 MONITORING WELL
	PZ-7 PIEZOMETER
	I3 EARTH TECH INDOOR AIR SAMPLE LOCATION
	S3 EARTH TECH SUBSLAB AIR SAMPLE LOCATION
	ARCADIS MARCH 2007 SUBSLAB/INDOOR AIR SAMPLE LOCATION
	ARCADIS MARCH 2007 SUBSLAB/INDOOR AIR SAMPLE LOCATION - ONLY SUBSLAB SAMPLE ANALYZED
	AREAS UNDER POSITIVE PRESSURE

Project Director C. MOTTA	Area Manager R. GAN
Task Manager J. BONSTEEL	Technical Review J. BONSTEEL
Drawing Date 12-18-06	Drawn By FJF

482 CONGRESS ST. SUITE 501
 PORTLAND, ME 04101
 Tel: 207.828.0046 Fax: 207.828.0062
 www.arcadis-us.com



**FORMER LOCKHEED MARTIN
 FRENCH ROAD FACILITY**


**SUBSLAB / INDOOR AIR
 SAMPLE LOCATIONS**

**VAPOR INTRUSION STUDY
 REPORT - SOLVENT DOCK
 AREA**

Project Number AY0002650015	Figure 3
UTICA, NEW YORK	

LEGEND

- MW-1 EXISTING MONITORING WELL
- PZ-7 PIEZOMETER
- I3 EARTH TECH INDOOR AIR SAMPLE LOCATION
- S3 EARTH TECH SUBSLAB AIR SAMPLE LOCATION
- ARCADIS MARCH 2007 SUBSLAB/INDOOR AIR SAMPLE LOCATION
- AREAS UNDER POSITIVE PRESSURE



NYSDOH MATRIX DECISIONS
 BASED ON SUBSLAB ONLY

- NO FURTHER ACTION
- MONITOR
- MITIGATE

Project Director C. MOTTA	Area Manager R. GAN
Task Manager J. BONSTEEL	Technical Review N. WEINBERG
Drawing Date 6-26-2007	Drawn By M. WACKSMAN

482 CONGRESS ST. SUITE 501
 PORTLAND, ME 04101
 Tel: 207.828.0046 Fax: 207.828.0062
 www.arcadis-us.com



**FORMER
 LOCKHEED MARTIN FACILITY**

**SUBSLAB / INDOOR AIR
 SAMPLE LOCATIONS &
 NYSDOH MATRIX RESULTS**

**VAPOR INTRUSION STUDY
 REPORT - SOLVENT DOCK AREA**

UTICA, NEW YORK

Project Number AY0002650015	Figure 4
---------------------------------------	--------------------

ARCADIS

Appendix A

Product Inventory

**APPENDIX A
PRODUCT INVENTORY**

**ConMed Facility
525 French Road
Utica, NY**

Location	Product Description	Chemical Ingredients	Size	Condition
Mold Storage	waste hydraulic oil	petroleum	6 - 55 gal	good
Storage Room (near solvent dock)	lim603080 - pail kit	silicon	12-80 lb	New
	Synpro	polymer	2-25lb	New
Material Storage/Mix	Cyro-Acrylic Molding-Cyrolite - large boxes	proprietary	4 boxes	New
	<i>Slide Mold Cleaner with Rust Preventer</i>	<i>TCE (50-65%)</i>	<i>2-10 oz</i>	<i>Fair</i>
	<i>Stoner Non-Flammable Cleaner Degreaser</i>	<i>TCE (90-100%)</i>	<i>2-10 oz</i>	<i>Fair</i>
"Currently Vacant Room"	Lexan - 45lb bags GE Plastics	Polycarbonate resin	8 bags	New
Aisle *	ColorRite-Polymer-Unichem Vinyl Compound	proprietary		
(east of "currently vacant room)	94-532Blue-497 - in Boxes	proprietary	5-1500lb	New
	Liquid Silicon rubber (Rhodia) - in pails	Silicon	17-43lb	New
Mechanical Room	FTS-321- Chiller Liquid	Unknown	1-55gal	In Use
	FTS-933- Chiller Liquid	Unknown	2-55gal	In Use
	<i>Boiler Treatment Chemicals</i>	<i>Unknown</i>	<i>5-55 gal</i>	<i>Fair</i>
	<i>Paint</i>	<i>Petroleum distillates</i>	<i>1-gal</i>	<i>Fair</i>
	<i>Waste Refrigerant</i>	<i>Ethylene Glycol</i>	<i>1-55 gal</i>	<i>Fair</i>
Chemical Storage**	waste hydraulic oil	petroleum	8-55gal	good
	New hydraulic oil	petroleum	8-55gal	New
	Cyclohexanone	Cyclohexanone	1-55 gal	good
	Cyclohexanone	Cyclohexanone	1-55 gal	New
	Isopropyl alcohol	Isopropyl alcohol (99%)	9-55gal	New
	Methylene Chloride	Methylene Chloride	1-1gal	New
	Methylene Chloride	Methylene Chloride	12-1gal	good
	Propane gas cylinders	Propane	2-16oz	New
	<i>Zep Degreaser</i>	<i>Proprietary</i>	<i>2-30 gal</i>	<i>Empty</i>
Mold Maintenance	Latex paint	Latex paint	1-1gal	Used
	white lithium grease	petroleum	1-3oz	In Use
	Citrus Power - bulk mold cleaner		5-5 gal	New
	<i>Used Oil</i>	<i>Petroleum</i>	<i>1-55 gal</i>	<i>Fair</i>
	<i>Dynaclean</i>	<i>Proprietary</i>	<i>2-55 gal</i>	<i>New</i>
	<i>Xylene</i>	<i>Xylene</i>	<i>1-1 gal</i>	<i>Fair</i>
	<i>Xenit Citrus Degreaser</i>	<i>Petroleum Distillates</i>	<i>8-10 oz</i>	<i>Fair</i>
	<i>Simple Green</i>	<i>Proprietary</i>	<i>1-1 gal</i>	<i>Good</i>
Molding Facility	<i>Slide Mold Cleaner with Rust Preventer</i>	<i>TCE (50-65%)</i>	<i>2-10 oz</i>	<i>Fair</i>
	<i>Stoner Non-Flammable Cleaner Degreaser</i>	<i>TCE (90-100%)</i>	<i>3-10 oz</i>	<i>Fair</i>
	<i>Xenit Citrus Degreaser</i>	<i>Petroleum Distillates</i>	<i>4-10 oz</i>	<i>Fair</i>

Notes

1. Observations made on March 25, 2005, except those noted in italics, which were made during February and March 2006.
2. Aisle *- This area is full of large boxes and bins of proprietary resin and resin ingredients. All are odorless, and in a solid state. Examples of two types of materials stored in the aisle are tabulated above.
3. Chemical Storage**- In addition to the above list, a chemical storage cabinet blocked by 55-gallon drums could not be inventoried.

Appendix B

Indoor Air and Subslab Soil Gas
Sample Logs


ARCADIS

Soil Gas Sampling Log

Project Name UML solvent Project No. A900026515 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. AA-1SD Replicate No. —
Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
Tubing Diameter: —
Canister ID: 233
Regulator ID: 152
Vol. Purged: —
Vacuum at Start: 30
Vacuum at Finish: 14



Site Location

Apparent Moisture Content: None

Sample Depth: ~5' off ground

Sample Method: 8 hrs ambient air canister.

Sample Device: TO-15 canister

Remarks: 3

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per minute N/A Not Applicable
mg/L Milligrams per liter COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LMC solvent Project No. A100026515 Page 1 of 1
 Site Location Utica, NY Date 4/12/07
 Sample No. VP-15D Replicate No. —
 Weather (indoor) Sampling Time: Begin — End 1030

Field Parameters

Measuring Point: —
 Tubing Diameter: 1/4"
 Canister ID: 496
 Regulator ID: 143
 Vol. Purged: 300mL
 Vacuum at Start: 30
 Vacuum at Finish: 1
 Apparent Moisture Content: NONE



Site Location

Sample Depth: 4" ~~1/2~~ bgs
 Sample Method: tubing to canister // tested ~~through~~ helium through Centek dome.
 Sample Device: To-15 canister

Remarks: No leak detected sample directly from tubing.

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per minute N/A Not Applicable
 mg/L Milligrams per liter COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LMC Solvent Project No. A1000265.15 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. AA-2SD Replicate No. —
Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
Tubing Diameter: —
Canister ID: 356
Regulator ID: 456
Vol. Purged: —
Vacuum at Start: 30
Vacuum at Finish: 4



Site Location

Apparent Moisture Content: NONE

Sample Depth: ~ 3 1/2' off ground.

Sample Method: 8hr ambient air canister.

Sample Device: TO-15 canister

Remarks: _____

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per mint N/A Not Applicable
mg/L Milligrams per lite COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LMC-Solvent Project No. A7000265.15 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. VP-25D Replicate No. —
Weather (indoor) Sampling Time: Begin — End 1:00

Field Parameters

Measuring Point: —
Tubing Diameter: 1/4"
Canister ID: 243
Regulator ID: 345
Vol. Purged: 300mL
Vacuum at Start: 30
Vacuum at Finish: 1
Apparent Moisture Content: None



Site Location

Sample Depth: 6" bgs
Sample Method: tubing was clamped to canister after helium test.
Sample Device: TO-15 canister.

Remarks: Move location twice due to metal sheet just below concrete surface. Helium leak detected; re-connect tubing tested again, ok, sample directly from tubing.

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per minute N/A Not Applicable
mg/L Milligrams per liter COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name UML solvent Project No. A4000245.15 Page 1 of 1
 Site Location Utica, NY Date 4/12/07
 Sample No. AA-3SD Replicate No. —
 Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
 Tubing Diameter: —
 Canister ID: 326
 Regulator ID: 388
 Vol. Purged: —
 Vacuum at Start: 30
 Vacuum at Finish: 4
 Apparent Moisture Content: None



Site Location

Sample Depth: ~3 1/2' off ground
 Sample Method: 8hr ambient air air canister.
 Sample Device: TO-15 canister.

Remarks: _____

Constituents Sampled: TO-15 Sampling Personnel: (KW)


gpm Gallons per minute N/A Not Applicable
 mg/L Milligrams per liter COC Chain of Custody

ARCADIS
Soil Gas Sampling Log

Project Name UML-Solvent Project No. AY000205.05 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. VP-3SD Replicate No. —
Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
Tubing Diameter: 1/4"
Canister ID: 92
Regulator ID: 173
Vol. Purged: 300mL
Vacuum at Start: 29
Vacuum at Finish: 1



Apparent Moisture Content: None

Sample Depth: ~6" bgs

Sample Method: Tubing clamped to canister after helium test.

Sample Device: To15 canister (VPOBMAN)

Remarks: No helium leak detected sampled ~~directly~~ directly from tubing.

Constituents Sampled: TO-15 Sampling Personnel: (hw)

gpm Gallons per minute N/A Not Applicable
mg/L Milligrams per liter COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name Lml Solvent Project No. AP000265.15 Page 1 of 1
 Site Location Utica, NY Date 4/12/07
 Sample No. AA-4SD Replicate No. —
 Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
 Tubing Diameter: —
 Canister ID: 141
 Regulator ID: 279
 Vol. Purged: —
 Vacuum at Start: 30
 Vacuum at Finish: 2
 Apparent Moisture Content: None



Sample Depth: ~4 1/2' off ground
 Sample Method: 8hr ambient air canister.
 Sample Device: TO-15 canister

Remarks: _____

Constituents Sampled: TO-15 Sampling Personnel: (KLW)


gpm Gallons per minute N/A Not Applicable
 mg/L Milligrams per liter COC Chain of Custody

ARCADIS
Soil Gas Sampling Log

Project Name Lmc-Solvent Project No. A4000246.15 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. VP-4SD Replicate No. —
Weather (indoor) Sampling Time: Begin — End 1130

Field Parameters

Measuring Point: —
Tubing Diameter: 1/4"
Canister ID: 200
Regulator ID: 302
Vol. Purged: 300ml
Vacuum at Start: 30
Vacuum at Finish: 1
Apparent Moisture Content: None



Site Location

Sample Depth: 8" bgs
Sample Method: Tubing clamped to canister after helium test conducted.
Sample Device: TO-15 canister.

Remarks: No helium leak detected sampled directly from tubing.

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per mint N/A Not Applicable
mg/L Miligrams per lite COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LMC Sol Project No. A4000265.15 Page 1 of 1
 Site Location Utica, NY Date 4/12/07
 Sample No. AA-~~011~~55D Replicate No. —
 Weather Indoor Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
 Tubing Diameter: —
 Canister ID: ~~2010~~ 274
 Regulator ID: ~~440~~ 446
 Vol. Purged: —
 Vacuum at Start: 30
 Vacuum at Finish: 10
 Apparent Moisture Content: None



Site Location

Sample Depth: ~4 1/2 off ground
 Sample Method: 8 hr ambient air canister.
 Sample Device: TO-15 canister

Remarks: → Note: sample ~~stayed~~ stayed on (10) for 1 1/2 hrs → stopped sampled

Constituents Sampled: TO-15 Sampling Personnel: 


gpm Gallons per minute N/A Not Applicable
 mg/L Milligrams per liter COC Chain of Custody

ARCADIS
Soil Gas Sampling Log

Project Name LMC - solvent Project No. AY000265.15 Page 1 of 1
 Site Location Vtica, NY Date 4/12/07
 Sample No. VP-550 on VP-550 Replicate No. —
 Weather (indoor) Sampling Time: Begin — End 1200

Field Parameters

Measuring Point: —
 Tubing Diameter: 1/4"
 Canister ID: 196
 Regulator ID: 406
 Vol. Purged: 300 mL
 Vacuum at Start: 30
 Vacuum at Finish: 1



Site Location

Apparent Moisture Content: None

Sample Depth: 6" bgs.

Sample Method: ~~1/4" / 1/4" Tubing~~ Tubing clamped to canister after helium test conducted.

Sample Device: TO-15 canister.

Remarks: No helium leak detected sampled directly from tubing.

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per mint N/A Not Applicable
 mg/L Miligrams per lite COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LMC-Solvent Project No. AY000265.15 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. AA-~~050~~ 65D Replicate No. —
Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
Tubing Diameter: mm 1/4"
Canister ID: ~~050~~ 464
Regulator ID: ~~126~~
Vol. Purged: —
Vacuum at Start: 30
Vacuum at Finish: 1
Apparent Moisture Content: None



Site Location

Sample Depth: ~4' off ground
Sample Method: 8hr ambient air canister.
Sample Device: TO-15 canister

Remarks: _____

Constituents Sampled: TO-15 Sampling Personnel: KW


gpm Gallons per minute N/A Not Applicable
mg/L Milligrams per liter COC Chain of Custody

ARCADIS
Soil Gas Sampling Log

Project Name LMK Street Project No. AY000265.15 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. VP-6SD Replicate No. —
Weather (Indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: _____
Tubing Diameter: _____
Canister ID: _____
Regulator ID: _____
Vol. Purged: _____
Vacuum at Start: _____
Vacuum at Finish: _____
Apparent Moisture Content: _____
Sample Depth: _____
Sample Method: _____
Sample Device: _____


Site Location

Remarks: There. Move 3 different locations all concrete greater than 16" bgs.
Call JB don't sample just take ambient air Sample AA-6SD.

Constituents Sampled: TO-15 Sampling Personnel: (Kre)

gpm Gallons per minute N/A Not Applicable
mg/L Milligrams per liter COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LML Solvent Project No. AY000265.15 Page 1 of 1
 Site Location Utica, NY Date 4/12/07
 Sample No. AA-7SP Replicate No. —
 Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
 Tubing Diameter: —
 Canister ID: 86
 Regulator ID: 60
 Vol. Purged: —
 Vacuum at Start: 30
 Vacuum at Finish: 4
 Apparent Moisture Content: —



Site Location

Sample Depth: ~ 4 1/2' off ground
 Sample Method: 8hr Ambient Air canister.
 Sample Device: TO-15 canister.

Remarks: _____

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per minu N/A Not Applicable
 mg/L Miligrams per lite COC Chain of Custody

ARCADIS


Soil Gas Sampling Log

Project Name LMC-solvent Project No. A4000265.15 Page 1 of 1
 Site Location Utica, NY Date _____
 Sample No. VP-7SD Replicate No. DUP-1SD
 Weather (indoor) Sampling Time: Begin — End 12:30

Field Parameters

Measuring Point:
 Tubing Diameter:
 Canister ID:
 Regulator ID:
 Vol. Purged:
 Vacuum at Start:
 Vacuum at Finish:
 Apparent Moisture
 Content:

VP-7SD	DUP-1SD
1/4"	1/4"
138	148
270	376
300mL	—
30	28
1	1



Site Location

Sample Depth: 8" bgs
 Sample Method: Tubing clamped to canister after helium test conducted.
 Sample Device: TO-15 canister

Remarks: No helium leak detected sampled directly from tubing. Sample DUP-1SD at same time as VP-7SD.

Constituents Sampled: TO-15 Sampling Personnel: (KW)

gpm Gallons per minute N/A Not Applicable
 mg/L Milligrams per liter COC Chain of Custody


ARCADIS

Soil Gas Sampling Log

Project Name LMC Solvent Project No. AFD00265.15 Page 1 of 1
 Site Location Utica, NY Date 4/12/07
 Sample No. AA-85D Replicate No. —
 Weather (indoor) Sampling Time: Begin — End —

Field Parameters

Measuring Point: —
 Tubing Diameter: —
 Canister ID: 229
 Regulator ID: 308
 Vol. Purged: —
 Vacuum at Start: 28
 Vacuum at Finish: 1
 Apparent Moisture Content: None



Site Location

Sample Depth: ~5' off ground
 Sample Method: 8 hr Ambient air canister.
 Sample Device: TO-15 canister.

Remarks: _____

Constituents Sampled: TO-15 Sampling Personnel: (KW)


gpm Gallons per minute N/A Not Applicable
 mg/L Milligrams per liter COC Chain of Custody

ARCADIS
Soil Gas Sampling Log

Project Name LMC-Solvent Project No. A4000265.15 Page 1 of 1
Site Location Utica, NY Date 4/12/07
Sample No. VP-85D Replicate No. —
Weather (Indoor) Sampling Time: Begin — End 1300

Field Parameters

Measuring Point: —
Tubing Diameter: 1/4"
Canister ID: 35B
Regulator ID: 113
Vol. Purged: 300mL
Vacuum at Start: 28
Vacuum at Finish: 2



Site Location

Apparent Moisture Content: None

Sample Depth: 8" bgs.

Sample Method: Tubing clamped to canister after helium test conducted.

Sample Device: TO-15 canister.

Remarks: No leaks detected sampled directly from tubing.

Constituents Sampled: TO-15 Sampling Personnel: (kw)

gpm Gallons per minute N/A Not Applicable
mg/L Milligrams per liter COC Chain of Custody

ARCADIS

Appendix C

Analytical Laboratory Results

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-001A

Client Sample ID: VP-1SD
Tag Number: 496,143
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15		Analyst: LL		
1,1,1-Trichloroethane	3.8	0.83		ug/m3	1	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	7.0	0.75		ug/m3	1	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	2.2	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	2.4	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	1.0	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	2.5	0.75		ug/m3	1	4/16/2007
Acetone	57	29		ug/m3	40	4/18/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	7.8	4.9		ug/m3	10	4/16/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	18	4.7		ug/m3	10	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	7.7	0.74		ug/m3	1	4/16/2007
Chloromethane	0.42	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	29	5.2		ug/m3	10	4/16/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	ND	0.92		ug/m3	1	4/16/2007
Ethylbenzene	2.6	0.66		ug/m3	1	4/16/2007
Freon 11	1.3	0.86		ug/m3	1	4/16/2007
Freon 113	5.1	1.2		ug/m3	1	4/16/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-001A

Client Sample ID: VP-1SD
Tag Number: 496,143
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	27	6.2		ug/m3	10	4/16/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	62	5.4		ug/m3	10	4/16/2007
Isopropyl alcohol	150	30		ug/m3	80	4/18/2007
m&p-Xylene	8.5	1.3		ug/m3	1	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	ND	0.90		ug/m3	1	4/16/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	0.55	0.55		ug/m3	1	4/16/2007
Methylene chloride	90	21		ug/m3	40	4/18/2007
o-Xylene	2.7	0.66		ug/m3	1	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	0.69	0.65		ug/m3	1	4/16/2007
Tetrachloroethylene	1.8	1.0		ug/m3	1	4/16/2007
Tetrahydrofuran	2.0	0.45		ug/m3	1	4/16/2007
Toluene	11	5.7		ug/m3	10	4/16/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	0.76	0.82	J	ug/m3	1	4/16/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers:	B	Analyte detected in the associated Method Blank	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected at or below quantitation limits
	JN	Non-routine analyte. Quantitation estimated.	ND	Not Detected at the Reporting Limit
	S	Spike Recovery outside accepted recovery limits		

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-002A

Client Sample ID: VP-2SD
Tag Number: 243,345
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
1,1,1-Trichloroethane	38	8.3		ug/m3	10	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	8.0	0.75		ug/m3	1	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	2.3	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	2.3	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	ND	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	2.3	0.75		ug/m3	1	4/16/2007
Acetone	33	7.2		ug/m3	10	4/16/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	3.9	0.49		ug/m3	1	4/16/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	2.3	0.47		ug/m3	1	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	7.2	0.74		ug/m3	1	4/16/2007
Chloromethane	0.84	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	8.0	5.2		ug/m3	10	4/16/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	ND	0.92		ug/m3	1	4/16/2007
Ethylbenzene	2.4	0.66		ug/m3	1	4/16/2007
Freon 11	2.3	0.86		ug/m3	1	4/16/2007
Freon 113	85	12		ug/m3	10	4/16/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-002A

Client Sample ID: VP-2SD
Tag Number: 243,345
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	7.2	0.62		ug/m3	1	4/16/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	12	5.4		ug/m3	10	4/16/2007
Isopropyl alcohol	44	15		ug/m3	40	4/18/2007
m&p-Xylene	8.4	1.3		ug/m3	1	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	ND	0.90		ug/m3	1	4/16/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	ND	0.55		ug/m3	1	4/16/2007
Methylene chloride	37	5.3		ug/m3	10	4/16/2007
o-Xylene	2.8	0.66		ug/m3	1	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	2.0	0.65		ug/m3	1	4/16/2007
Tetrachloroethylene	9.5	1.0		ug/m3	1	4/16/2007
Tetrahydrofuran	0.90	0.45		ug/m3	1	4/16/2007
Toluene	15	5.7		ug/m3	10	4/16/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	110	8.2		ug/m3	10	4/16/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers:	B	Analyte detected in the associated Method Blank	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected at or below quantitation limits
	JN	Non-routine analyte. Quantitation estimated.	ND	Not Detected at the Reporting Limit
	S	Spike Recovery outside accepted recovery limits		

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-003A

Client Sample ID: VP-3SD
Tag Number: 92,173
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
1,1,1-Trichloroethane	0.72	0.83	J	ug/m3	1	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	3.1	0.75		ug/m3	1	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	1.0	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	2.3	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	ND	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	1.1	0.75		ug/m3	1	4/16/2007
Acetone	64	29		ug/m3	40	4/18/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	4.9	0.49		ug/m3	1	4/16/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	2.4	0.47		ug/m3	1	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	ND	0.74		ug/m3	1	4/16/2007
Chloromethane	ND	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	47	5.2		ug/m3	10	4/16/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	5.6	0.92		ug/m3	1	4/16/2007
Ethylbenzene	0.71	0.66		ug/m3	1	4/16/2007
Freon 11	0.97	0.86		ug/m3	1	4/16/2007
Freon 113	7.6	1.2		ug/m3	1	4/16/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-003A

Client Sample ID: VP-3SD
Tag Number: 92,173
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	11	6.2		ug/m3	10	4/16/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	59	5.4		ug/m3	10	4/16/2007
Isopropyl alcohol	250	30		ug/m3	80	4/18/2007
m&p-Xylene	2.4	1.3		ug/m3	1	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	100	36		ug/m3	40	4/18/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	ND	0.55		ug/m3	1	4/16/2007
Methylene chloride	210	21		ug/m3	40	4/18/2007
o-Xylene	0.84	0.66		ug/m3	1	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	0.65	0.65		ug/m3	1	4/16/2007
Tetrachloroethylene	ND	1.0		ug/m3	1	4/16/2007
Tetrahydrofuran	1.1	0.45		ug/m3	1	4/16/2007
Toluene	6.6	0.57		ug/m3	1	4/16/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	0.76	0.82	J	ug/m3	1	4/16/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-004A

Client Sample ID: VP-4SD
Tag Number: 200,302
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
1,1,1-Trichloroethane	11	0.83		ug/m3	1	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	6.6	0.75		ug/m3	1	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	2.0	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	2.5	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	ND	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	1.8	0.75		ug/m3	1	4/16/2007
Acetone	43	29		ug/m3	40	4/18/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	1.2	0.49		ug/m3	1	4/16/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	0.85	0.47		ug/m3	1	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	25	7.4		ug/m3	10	4/16/2007
Chloromethane	0.80	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	2.3	0.52		ug/m3	1	4/16/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	ND	0.92		ug/m3	1	4/16/2007
Ethylbenzene	1.5	0.66		ug/m3	1	4/16/2007
Freon 11	1.5	0.86		ug/m3	1	4/16/2007
Freon 113	450	47		ug/m3	40	4/18/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-004A

Client Sample ID: VP-4SD
Tag Number: 200,302
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15		Analyst: LL		
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	3.6	0.62		ug/m3	1	4/16/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	ND	0.54		ug/m3	1	4/16/2007
Isopropyl alcohol	190	15		ug/m3	40	4/18/2007
m&p-Xylene	5.4	1.3		ug/m3	1	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	46	9.0		ug/m3	10	4/16/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	ND	0.55		ug/m3	1	4/16/2007
Methylene chloride	93	21		ug/m3	40	4/18/2007
o-Xylene	1.9	0.66		ug/m3	1	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	0.65	0.65		ug/m3	1	4/16/2007
Tetrachloroethylene	40	10		ug/m3	10	4/16/2007
Tetrahydrofuran	5.5	0.45		ug/m3	1	4/16/2007
Toluene	7.2	0.57		ug/m3	1	4/16/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	45	8.2		ug/m3	10	4/16/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-005A

Client Sample ID: VP-5SD
Tag Number: 196,406
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15		Analyst: LL		
1,1,1-Trichloroethane	0.78	0.83	J	ug/m3	1	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	6.5	7.5	J	ug/m3	10	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	4.2	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	3.9	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	4.3	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	4.4	0.75		ug/m3	1	4/16/2007
Acetone	270	58		ug/m3	80	4/18/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	24	4.9		ug/m3	10	4/16/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	9.8	4.7		ug/m3	10	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	5.1	0.74		ug/m3	1	4/16/2007
Chloromethane	0.65	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	66	5.2		ug/m3	10	4/16/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	ND	0.92		ug/m3	1	4/16/2007
Ethylbenzene	6.2	6.6	J	ug/m3	10	4/16/2007
Freon 11	1.3	0.86		ug/m3	1	4/16/2007
Freon 113	9.5	1.2		ug/m3	1	4/16/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
JN Non-routine analyte. Quantitation estimated.
S Spike Recovery outside accepted recovery limits
E Value above quantitation range
J Analyte detected at or below quantitation limits
ND Not Detected at the Reporting Limit

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-005A

Client Sample ID: VP-5SD
Tag Number: 196,406
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	170	25		ug/m3	40	4/18/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	250	21		ug/m3	40	4/18/2007
Isopropyl alcohol	170	30		ug/m3	80	4/18/2007
m&p-Xylene	20	13		ug/m3	10	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	110	36		ug/m3	40	4/18/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	ND	0.55		ug/m3	1	4/16/2007
Methylene chloride	170	21		ug/m3	40	4/18/2007
o-Xylene	6.2	6.6	J	ug/m3	10	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	ND	0.65		ug/m3	1	4/16/2007
Tetrachloroethylene	0.97	1.0	J	ug/m3	1	4/16/2007
Tetrahydrofuran	1.7	0.45		ug/m3	1	4/16/2007
Toluene	58	5.7		ug/m3	10	4/16/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	1.6	0.82		ug/m3	1	4/16/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-006A

Client Sample ID: VP-7SD
Tag Number: 138,270
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
1,1,1-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	3.4	0.75		ug/m3	1	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	1.2	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	1.3	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	ND	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	1.4	0.75		ug/m3	1	4/16/2007
Acetone	390	58		ug/m3	80	4/18/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	28	4.9		ug/m3	10	4/18/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	5.6	0.47		ug/m3	1	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	0.65	0.74	J	ug/m3	1	4/16/2007
Chloromethane	0.31	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	64	21		ug/m3	40	4/18/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	ND	0.92		ug/m3	1	4/16/2007
Ethylbenzene	2.6	0.66		ug/m3	1	4/16/2007
Freon 11	ND	0.86		ug/m3	1	4/16/2007
Freon 113	2.2	1.2		ug/m3	1	4/16/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-006A

Client Sample ID: VP-7SD
Tag Number: 138,270
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	40	6.2		ug/m3	10	4/18/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	67	21		ug/m3	40	4/18/2007
Isopropyl alcohol	87	15		ug/m3	40	4/18/2007
m&p-Xylene	7.5	1.3		ug/m3	1	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	41	9.0		ug/m3	10	4/18/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	ND	0.55		ug/m3	1	4/16/2007
Methylene chloride	42	5.3		ug/m3	10	4/18/2007
o-Xylene	2.3	0.66		ug/m3	1	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	ND	0.65		ug/m3	1	4/16/2007
Tetrachloroethylene	8.4	1.0		ug/m3	1	4/16/2007
Tetrahydrofuran	ND	0.45		ug/m3	1	4/16/2007
Toluene	49	5.7		ug/m3	10	4/18/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	ND	0.82		ug/m3	1	4/16/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-007A

Client Sample ID: VP-8SD
Tag Number: 358,113
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
1,1,1-Trichloroethane	1.2	0.83		ug/m3	1	4/16/2007
1,1,2,2-Tetrachloroethane	ND	1.0		ug/m3	1	4/16/2007
1,1,2-Trichloroethane	ND	0.83		ug/m3	1	4/16/2007
1,1-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,1-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
1,2,4-Trichlorobenzene	ND	1.1		ug/m3	1	4/16/2007
1,2,4-Trimethylbenzene	3.0	0.75		ug/m3	1	4/16/2007
1,2-Dibromoethane	ND	1.2		ug/m3	1	4/16/2007
1,2-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,2-Dichloroethane	ND	0.62		ug/m3	1	4/16/2007
1,2-Dichloropropane	ND	0.70		ug/m3	1	4/16/2007
1,3,5-Trimethylbenzene	1.0	0.75		ug/m3	1	4/16/2007
1,3-butadiene	ND	0.34		ug/m3	1	4/16/2007
1,3-Dichlorobenzene	ND	0.92		ug/m3	1	4/16/2007
1,4-Dichlorobenzene	9.7	0.92		ug/m3	1	4/16/2007
1,4-Dioxane	ND	1.1		ug/m3	1	4/16/2007
2,2,4-trimethylpentane	ND	0.71		ug/m3	1	4/16/2007
4-ethyltoluene	1.1	0.75		ug/m3	1	4/16/2007
Acetone	24	7.2		ug/m3	10	4/18/2007
Allyl chloride	ND	0.48		ug/m3	1	4/16/2007
Benzene	2.0	0.49		ug/m3	1	4/16/2007
Benzyl chloride	ND	0.88		ug/m3	1	4/16/2007
Bromodichloromethane	ND	1.0		ug/m3	1	4/16/2007
Bromoform	ND	1.6		ug/m3	1	4/16/2007
Bromomethane	ND	0.59		ug/m3	1	4/16/2007
Carbon disulfide	1.8	0.47		ug/m3	1	4/16/2007
Carbon tetrachloride	ND	0.96		ug/m3	1	4/16/2007
Chlorobenzene	ND	0.70		ug/m3	1	4/16/2007
Chloroethane	ND	0.40		ug/m3	1	4/16/2007
Chloroform	3.2	0.74		ug/m3	1	4/16/2007
Chloromethane	0.55	0.31		ug/m3	1	4/16/2007
cis-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
cis-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Cyclohexane	5.0	0.52		ug/m3	1	4/16/2007
Dibromochloromethane	ND	1.3		ug/m3	1	4/16/2007
Ethyl acetate	ND	0.92		ug/m3	1	4/16/2007
Ethylbenzene	0.88	0.66		ug/m3	1	4/16/2007
Freon 11	0.97	0.86		ug/m3	1	4/16/2007
Freon 113	ND	1.2		ug/m3	1	4/16/2007
Freon 114	ND	1.1		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 19-Apr-07

CLIENT: Arcadis
Lab Order: C0704029
Project: Utica LML-Solvent dock
Lab ID: C0704029-007A

Client Sample ID: VP-8SD
Tag Number: 358,113
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 BY METHOD TO15		TO-15				Analyst: LL
Freon 12	ND	0.75		ug/m3	1	4/16/2007
Heptane	7.0	0.62		ug/m3	1	4/16/2007
Hexachloro-1,3-butadiene	ND	1.6		ug/m3	1	4/16/2007
Hexane	7.9	5.4		ug/m3	10	4/18/2007
Isopropyl alcohol	800	60		ug/m3	160	4/19/2007
m&p-Xylene	3.3	1.3		ug/m3	1	4/16/2007
Methyl Butyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl Ethyl Ketone	25	9.0		ug/m3	10	4/18/2007
Methyl Isobutyl Ketone	ND	1.2		ug/m3	1	4/16/2007
Methyl tert-butyl ether	ND	0.55		ug/m3	1	4/16/2007
Methylene chloride	4600	670		ug/m3	1280	4/19/2007
o-Xylene	1.1	0.66		ug/m3	1	4/16/2007
Propylene	ND	0.26		ug/m3	1	4/16/2007
Styrene	0.52	0.65	J	ug/m3	1	4/16/2007
Tetrachloroethylene	5.4	1.0		ug/m3	1	4/16/2007
Tetrahydrofuran	ND	0.45		ug/m3	1	4/16/2007
Toluene	5.9	0.57		ug/m3	1	4/16/2007
trans-1,2-Dichloroethene	ND	0.60		ug/m3	1	4/16/2007
trans-1,3-Dichloropropene	ND	0.69		ug/m3	1	4/16/2007
Trichloroethene	36	8.2		ug/m3	10	4/18/2007
Vinyl acetate	ND	0.54		ug/m3	1	4/16/2007
Vinyl Bromide	ND	0.67		ug/m3	1	4/16/2007
Vinyl chloride	ND	0.39		ug/m3	1	4/16/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-001A

Client Sample ID: AA-2SD
Tag Number: 356,456
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
1,1,1-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1,2,2-Tetrachloroethane	ND	1.05		ug/m3	1	4/25/2007
1,1,2-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,1-Dichloroethene	ND	0.605		ug/m3	1	4/25/2007
1,2,4-Trichlorobenzene	ND	1.13		ug/m3	1	4/25/2007
1,2,4-Trimethylbenzene	3.20	0.749		ug/m3	1	4/25/2007
1,2-Dibromoethane	ND	1.17		ug/m3	1	4/25/2007
1,2-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,2-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,2-Dichloropropane	ND	0.705		ug/m3	1	4/25/2007
1,3,5-Trimethylbenzene	1.50	0.750		ug/m3	1	4/25/2007
1,3-butadiene	ND	0.337		ug/m3	1	4/25/2007
1,3-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,4-Dichlorobenzene	1.35	0.917		ug/m3	1	4/25/2007
1,4-Dioxane	ND	1.10		ug/m3	1	4/25/2007
2,2,4-trimethylpentane	ND	0.712		ug/m3	1	4/25/2007
4-ethyltoluene	1.70	0.750		ug/m3	1	4/25/2007
Acetone	67.6	29.0		ug/m3	40	4/25/2007
Allyl chloride	ND	0.477		ug/m3	1	4/25/2007
Benzene	0.552	0.487		ug/m3	1	4/25/2007
Benzyl chloride	ND	0.877		ug/m3	1	4/25/2007
Bromodichloromethane	ND	1.02		ug/m3	1	4/25/2007
Bromoform	ND	1.58		ug/m3	1	4/25/2007
Bromomethane	ND	0.592		ug/m3	1	4/25/2007
Carbon disulfide	0.411	0.475	J	ug/m3	1	4/25/2007
Carbon tetrachloride	ND	0.256		ug/m3	1	4/25/2007
Chlorobenzene	ND	0.702		ug/m3	1	4/25/2007
Chloroethane	ND	0.402		ug/m3	1	4/25/2007
Chloroform	ND	0.744		ug/m3	1	4/25/2007
Chloromethane	ND	0.315		ug/m3	1	4/25/2007
cis-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
cis-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Cyclohexane	8.64	0.525		ug/m3	1	4/25/2007
Dibromochloromethane	ND	1.30		ug/m3	1	4/25/2007
Ethyl acetate	ND	0.916		ug/m3	1	4/25/2007
Ethylbenzene	0.485	0.662	J	ug/m3	1	4/25/2007
Freon 11	0.971	0.857		ug/m3	1	4/25/2007
Freon 113	ND	1.17		ug/m3	1	4/25/2007
Freon 114	ND	1.07		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank
 H Holding times for preparation or analysis exceeded
 JN Non-routine analyte. Quantitation estimated.
 S Spike Recovery outside accepted recovery limits
 E Value above quantitation range
 J Analyte detected at or below quantitation limits
 ND Not Detected at the Reporting Limit

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-001A

Client Sample ID: AA-2SD
Tag Number: 356,456
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1		TO-15				Analyst: RJP
Freon 12	2.06	0.754		ug/m3	1	4/25/2007
Heptane	4.96	0.625		ug/m3	1	4/25/2007
Hexachloro-1,3-butadiene	ND	1.63		ug/m3	1	4/25/2007
Hexane	ND	0.537		ug/m3	1	4/25/2007
Isopropyl alcohol	481	33.7		ug/m3	90	4/25/2007
m&p-Xylene	1.19	1.32	J	ug/m3	1	4/25/2007
Methyl Butyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl Ethyl Ketone	137	36.0		ug/m3	40	4/25/2007
Methyl Isobutyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl tert-butyl ether	ND	0.550		ug/m3	1	4/25/2007
Methylene chloride	263	21.2		ug/m3	40	4/25/2007
o-Xylene	0.485	0.662	J	ug/m3	1	4/25/2007
Propylene	ND	0.262		ug/m3	1	4/25/2007
Styrene	1.86	0.649		ug/m3	1	4/25/2007
Tetrachloroethylene	ND	1.03		ug/m3	1	4/25/2007
Tetrahydrofuran	ND	0.450		ug/m3	1	4/25/2007
Toluene	5.21	0.575		ug/m3	1	4/25/2007
trans-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
trans-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Trichloroethene	0.983	0.218		ug/m3	1	4/25/2007
Vinyl acetate	ND	0.537		ug/m3	1	4/25/2007
Vinyl Bromide	ND	0.667		ug/m3	1	4/25/2007
Vinyl chloride	ND	0.390		ug/m3	1	4/25/2007

Qualifiers:	B	Analyte detected in the associated Method Blank	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected at or below quantitation limits
	JN	Non-routine analyte. Quantitation estimated.	ND	Not Detected at the Reporting Limit
	S	Spike Recovery outside accepted recovery limits		

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-002A

Client Sample ID: AA-3SD
Tag Number: 326,388
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
1,1,1-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1,2,2-Tetrachloroethane	ND	1.05		ug/m3	1	4/25/2007
1,1,2-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,1-Dichloroethene	ND	0.605		ug/m3	1	4/25/2007
1,2,4-Trichlorobenzene	ND	1.13		ug/m3	1	4/25/2007
1,2,4-Trimethylbenzene	2.50	0.749		ug/m3	1	4/25/2007
1,2-Dibromoethane	ND	1.17		ug/m3	1	4/25/2007
1,2-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,2-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,2-Dichloropropane	ND	0.705		ug/m3	1	4/25/2007
1,3,5-Trimethylbenzene	1.40	0.750		ug/m3	1	4/25/2007
1,3-butadiene	ND	0.337		ug/m3	1	4/25/2007
1,3-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,4-Dichlorobenzene	0.856	0.917	J	ug/m3	1	4/25/2007
1,4-Dioxane	ND	1.10		ug/m3	1	4/25/2007
2,2,4-trimethylpentane	ND	0.712		ug/m3	1	4/25/2007
4-ethyltoluene	1.25	0.750		ug/m3	1	4/25/2007
Acetone	76.3	29.0		ug/m3	40	4/25/2007
Allyl chloride	ND	0.477		ug/m3	1	4/25/2007
Benzene	0.487	0.487		ug/m3	1	4/25/2007
Benzyl chloride	ND	0.877		ug/m3	1	4/25/2007
Bromodichloromethane	ND	1.02		ug/m3	1	4/25/2007
Bromoform	ND	1.58		ug/m3	1	4/25/2007
Bromomethane	ND	0.592		ug/m3	1	4/25/2007
Carbon disulfide	ND	0.475		ug/m3	1	4/25/2007
Carbon tetrachloride	ND	0.256		ug/m3	1	4/25/2007
Chlorobenzene	ND	0.702		ug/m3	1	4/25/2007
Chloroethane	ND	0.402		ug/m3	1	4/25/2007
Chloroform	ND	0.744		ug/m3	1	4/25/2007
Chloromethane	ND	0.315		ug/m3	1	4/25/2007
cis-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
cis-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Cyclohexane	3.50	0.525		ug/m3	1	4/25/2007
Dibromochloromethane	ND	1.30		ug/m3	1	4/25/2007
Ethyl acetate	ND	0.916		ug/m3	1	4/25/2007
Ethylbenzene	0.441	0.662	J	ug/m3	1	4/25/2007
Freon 11	0.800	0.857	J	ug/m3	1	4/25/2007
Freon 113	ND	1.17		ug/m3	1	4/25/2007
Freon 114	ND	1.07		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
JN Non-routine analyte. Quantitation estimated.
S Spike Recovery outside accepted recovery limits
E Value above quantitation range
J Analyte detected at or below quantitation limits
ND Not Detected at the Reporting Limit

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-002A

Client Sample ID: AA-3SD
Tag Number: 326,388
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
Freon 12	2.21	0.754		ug/m3	1	4/25/2007
Heptane	2.37	0.625		ug/m3	1	4/25/2007
Hexachloro-1,3-butadiene	ND	1.63		ug/m3	1	4/25/2007
Hexane	ND	0.537		ug/m3	1	4/25/2007
Isopropyl alcohol	499	33.7		ug/m3	90	4/25/2007
m&p-Xylene	0.927	1.32	J	ug/m3	1	4/25/2007
Methyl Butyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl Ethyl Ketone	270	36.0		ug/m3	40	4/25/2007
Methyl Isobutyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl tert-butyl ether	ND	0.550		ug/m3	1	4/25/2007
Methylene chloride	242	21.2		ug/m3	40	4/25/2007
o-Xylene	ND	0.662		ug/m3	1	4/25/2007
Propylene	ND	0.262		ug/m3	1	4/25/2007
Styrene	0.909	0.649		ug/m3	1	4/25/2007
Tetrachloroethylene	ND	1.03		ug/m3	1	4/25/2007
Tetrahydrofuran	ND	0.450		ug/m3	1	4/25/2007
Toluene	6.28	0.575		ug/m3	1	4/25/2007
trans-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
trans-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Trichloroethene	0.601	0.218		ug/m3	1	4/25/2007
Vinyl acetate	ND	0.537		ug/m3	1	4/25/2007
Vinyl Bromide	ND	0.667		ug/m3	1	4/25/2007
Vinyl chloride	ND	0.390		ug/m3	1	4/25/2007

Qualifiers:	B	Analyte detected in the associated Method Blank	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected at or below quantitation limits
	JN	Non-routine analyte. Quantitation estimated.	ND	Not Detected at the Reporting Limit
	S	Spike Recovery outside accepted recovery limits		

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-003A

Client Sample ID: AA-4SD
Tag Number: 141,279
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
1,1,1-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1,2,2-Tetrachloroethane	ND	1.05		ug/m3	1	4/25/2007
1,1,2-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,1-Dichloroethene	ND	0.605		ug/m3	1	4/25/2007
1,2,4-Trichlorobenzene	ND	1.13		ug/m3	1	4/25/2007
1,2,4-Trimethylbenzene	2.40	0.749		ug/m3	1	4/25/2007
1,2-Dibromoethane	ND	1.17		ug/m3	1	4/25/2007
1,2-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,2-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,2-Dichloropropane	ND	0.705		ug/m3	1	4/25/2007
1,3,5-Trimethylbenzene	0.999	0.750		ug/m3	1	4/25/2007
1,3-butadiene	ND	0.337		ug/m3	1	4/25/2007
1,3-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,4-Dichlorobenzene	1.47	0.917		ug/m3	1	4/25/2007
1,4-Dioxane	ND	1.10		ug/m3	1	4/25/2007
2,2,4-trimethylpentane	ND	0.712		ug/m3	1	4/25/2007
4-ethyltoluene	1.15	0.750		ug/m3	1	4/25/2007
Acetone	89.8	29.0		ug/m3	40	4/25/2007
Allyl chloride	ND	0.477		ug/m3	1	4/25/2007
Benzene	0.487	0.487		ug/m3	1	4/25/2007
Benzyl chloride	ND	0.877		ug/m3	1	4/25/2007
Bromodichloromethane	ND	1.02		ug/m3	1	4/25/2007
Bromoform	ND	1.58		ug/m3	1	4/25/2007
Bromomethane	ND	0.592		ug/m3	1	4/25/2007
Carbon disulfide	ND	0.475		ug/m3	1	4/25/2007
Carbon tetrachloride	ND	0.256		ug/m3	1	4/25/2007
Chlorobenzene	ND	0.702		ug/m3	1	4/25/2007
Chloroethane	ND	0.402		ug/m3	1	4/25/2007
Chloroform	ND	0.744		ug/m3	1	4/25/2007
Chloromethane	ND	0.315		ug/m3	1	4/25/2007
cis-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
cis-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Cyclohexane	2.48	0.525		ug/m3	1	4/25/2007
Dibromochloromethane	ND	1.30		ug/m3	1	4/25/2007
Ethyl acetate	ND	0.916		ug/m3	1	4/25/2007
Ethylbenzene	ND	0.662		ug/m3	1	4/25/2007
Freon 11	0.800	0.857	J	ug/m3	1	4/25/2007
Freon 113	ND	1.17		ug/m3	1	4/25/2007
Freon 114	ND	1.07		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-003A

Client Sample ID: AA-4SD
Tag Number: 141,279
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
Freon 12	2.16	0.754		ug/m3	1	4/25/2007
Heptane	3.62	0.625		ug/m3	1	4/25/2007
Hexachloro-1,3-butadiene	ND	1.63		ug/m3	1	4/25/2007
Hexane	ND	0.537		ug/m3	1	4/25/2007
Isopropyl alcohol	504	33.7		ug/m3	90	4/25/2007
m&p-Xylene	0.883	1.32	J	ug/m3	1	4/25/2007
Methyl Butyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl Ethyl Ketone	261	36.0		ug/m3	40	4/25/2007
Methyl Isobutyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl tert-butyl ether	ND	0.550		ug/m3	1	4/25/2007
Methylene chloride	198	21.2		ug/m3	40	4/25/2007
o-Xylene	ND	0.662		ug/m3	1	4/25/2007
Propylene	ND	0.262		ug/m3	1	4/25/2007
Styrene	0.649	0.649		ug/m3	1	4/25/2007
Tetrachloroethylene	1.03	1.03		ug/m3	1	4/25/2007
Tetrahydrofuran	ND	0.450		ug/m3	1	4/25/2007
Toluene	4.02	0.575		ug/m3	1	4/25/2007
trans-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
trans-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Trichloroethene	1.26	0.218		ug/m3	1	4/25/2007
Vinyl acetate	ND	0.537		ug/m3	1	4/25/2007
Vinyl Bromide	ND	0.667		ug/m3	1	4/25/2007
Vinyl chloride	ND	0.390		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-004A

Client Sample ID: AA-6SD
Tag Number: 274,446
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
1,1,1-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1,2,2-Tetrachloroethane	ND	1.05		ug/m3	1	4/25/2007
1,1,2-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,1-Dichloroethene	ND	0.605		ug/m3	1	4/25/2007
1,2,4-Trichlorobenzene	ND	1.13		ug/m3	1	4/25/2007
1,2,4-Trimethylbenzene	1.20	0.749		ug/m3	1	4/25/2007
1,2-Dibromoethane	ND	1.17		ug/m3	1	4/25/2007
1,2-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,2-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,2-Dichloropropane	ND	0.705		ug/m3	1	4/25/2007
1,3,5-Trimethylbenzene	ND	0.750		ug/m3	1	4/25/2007
1,3-butadiene	ND	0.337		ug/m3	1	4/25/2007
1,3-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,4-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,4-Dioxane	ND	1.10		ug/m3	1	4/25/2007
2,2,4-trimethylpentane	ND	0.712		ug/m3	1	4/25/2007
4-ethyltoluene	ND	0.750		ug/m3	1	4/25/2007
Acetone	20.5	7.24		ug/m3	10	4/25/2007
Allyl chloride	ND	0.477		ug/m3	1	4/25/2007
Benzene	0.779	0.487		ug/m3	1	4/25/2007
Benzyl chloride	ND	0.877		ug/m3	1	4/25/2007
Bromodichloromethane	ND	1.02		ug/m3	1	4/25/2007
Bromoform	ND	1.58		ug/m3	1	4/25/2007
Bromomethane	ND	0.592		ug/m3	1	4/25/2007
Carbon disulfide	0.443	0.475	J	ug/m3	1	4/25/2007
Carbon tetrachloride	ND	0.256		ug/m3	1	4/25/2007
Chlorobenzene	ND	0.702		ug/m3	1	4/25/2007
Chloroethane	ND	0.402		ug/m3	1	4/25/2007
Chloroform	ND	0.744		ug/m3	1	4/25/2007
Chloromethane	ND	0.315		ug/m3	1	4/25/2007
cis-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
cis-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Cyclohexane	45.5	5.25		ug/m3	10	4/25/2007
Dibromochloromethane	ND	1.30		ug/m3	1	4/25/2007
Ethyl acetate	ND	0.916		ug/m3	1	4/25/2007
Ethylbenzene	0.574	0.662	J	ug/m3	1	4/25/2007
Freon 11	0.800	0.857	J	ug/m3	1	4/25/2007
Freon 113	ND	1.17		ug/m3	1	4/25/2007
Freon 114	ND	1.07		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-004A

Client Sample ID: AA-6SD
Tag Number: 274,446
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
Freon 12	2.26	0.754		ug/m3	1	4/25/2007
Heptane	0.666	0.625		ug/m3	1	4/25/2007
Hexachloro-1,3-butadiene	ND	1.63		ug/m3	1	4/25/2007
Hexane	1.72	0.537		ug/m3	1	4/25/2007
Isopropyl alcohol	20.2	3.75		ug/m3	10	4/25/2007
m&p-Xylene	1.19	1.32	J	ug/m3	1	4/25/2007
Methyl Butyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl Ethyl Ketone	6.86	0.899		ug/m3	1	4/25/2007
Methyl Isobutyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl tert-butyl ether	ND	0.550		ug/m3	1	4/25/2007
Methylene chloride	7.52	0.530		ug/m3	1	4/25/2007
o-Xylene	0.485	0.662	J	ug/m3	1	4/25/2007
Propylene	ND	0.262		ug/m3	1	4/25/2007
Styrene	9.27	0.649		ug/m3	1	4/25/2007
Tetrachloroethylene	ND	1.03		ug/m3	1	4/25/2007
Tetrahydrofuran	ND	0.450		ug/m3	1	4/25/2007
Toluene	8.43	5.75		ug/m3	10	4/25/2007
trans-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
trans-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Trichloroethene	0.655	0.218		ug/m3	1	4/25/2007
Vinyl acetate	ND	0.537		ug/m3	1	4/25/2007
Vinyl Bromide	ND	0.667		ug/m3	1	4/25/2007
Vinyl chloride	ND	0.390		ug/m3	1	4/25/2007

Qualifiers:	B	Analyte detected in the associated Method Blank	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected at or below quantitation limits
	JN	Non-routine analyte. Quantitation estimated.	ND	Not Detected at the Reporting Limit
	S	Spike Recovery outside accepted recovery limits		

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-005A

Client Sample ID: AA-8SD
Tag Number: 229,308
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1						
		TO-15				Analyst: RJP
1,1,1-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1,2,2-Tetrachloroethane	ND	1.05		ug/m3	1	4/25/2007
1,1,2-Trichloroethane	ND	0.832		ug/m3	1	4/25/2007
1,1-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,1-Dichloroethene	ND	0.605		ug/m3	1	4/25/2007
1,2,4-Trichlorobenzene	ND	1.13		ug/m3	1	4/25/2007
1,2,4-Trimethylbenzene	4.65	0.749		ug/m3	1	4/25/2007
1,2-Dibromoethane	ND	1.17		ug/m3	1	4/25/2007
1,2-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,2-Dichloroethane	ND	0.617		ug/m3	1	4/25/2007
1,2-Dichloropropane	ND	0.705		ug/m3	1	4/25/2007
1,3,5-Trimethylbenzene	1.70	0.750		ug/m3	1	4/25/2007
1,3-butadiene	ND	0.337		ug/m3	1	4/25/2007
1,3-Dichlorobenzene	ND	0.917		ug/m3	1	4/25/2007
1,4-Dichlorobenzene	11.9	0.917		ug/m3	1	4/25/2007
1,4-Dioxane	ND	1.10		ug/m3	1	4/25/2007
2,2,4-trimethylpentane	ND	0.712		ug/m3	1	4/25/2007
4-ethyltoluene	2.65	0.750		ug/m3	1	4/25/2007
Acetone	91.7	14.5		ug/m3	20	4/25/2007
Allyl chloride	ND	0.477		ug/m3	1	4/25/2007
Benzene	0.455	0.487	J	ug/m3	1	4/25/2007
Benzyl chloride	ND	0.877		ug/m3	1	4/25/2007
Bromodichloromethane	ND	1.02		ug/m3	1	4/25/2007
Bromoform	ND	1.58		ug/m3	1	4/25/2007
Bromomethane	ND	0.592		ug/m3	1	4/25/2007
Carbon disulfide	ND	0.475		ug/m3	1	4/25/2007
Carbon tetrachloride	ND	0.256		ug/m3	1	4/25/2007
Chlorobenzene	ND	0.702		ug/m3	1	4/25/2007
Chloroethane	ND	0.402		ug/m3	1	4/25/2007
Chloroform	ND	0.744		ug/m3	1	4/25/2007
Chloromethane	ND	0.315		ug/m3	1	4/25/2007
cis-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
cis-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Cyclohexane	5.67	0.525		ug/m3	1	4/25/2007
Dibromochloromethane	ND	1.30		ug/m3	1	4/25/2007
Ethyl acetate	ND	0.916		ug/m3	1	4/25/2007
Ethylbenzene	0.485	0.662	J	ug/m3	1	4/25/2007
Freon 11	1.26	0.857		ug/m3	1	4/25/2007
Freon 113	0.857	1.17	J	ug/m3	1	4/25/2007
Freon 114	ND	1.07		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits

Centek Laboratories, LLC

Date: 26-Apr-07

CLIENT: Arcadis
Lab Order: C0704036
Project: LMC Utica Solvent Dock
Lab ID: C0704036-005A

Client Sample ID: AA-8SD
Tag Number: 229,308
Collection Date: 4/12/2007
Matrix: AIR

Analyses	Result	Limit	Qual	Units	DF	Date Analyzed
1UG/M3 W/ 0.25UG/M3 CT&TCE BY METHOD TO1		TO-15				Analyst: RJP
Freon 12	2.21	0.754		ug/m3	1	4/25/2007
Heptane	10.1	0.625		ug/m3	1	4/25/2007
Hexachloro-1,3-butadiene	ND	1.63		ug/m3	1	4/25/2007
Hexane	ND	0.537		ug/m3	1	4/25/2007
Isopropyl alcohol	1250	305		ug/m3	810	4/25/2007
m&p-Xylene	1.15	1.32	J	ug/m3	1	4/25/2007
Methyl Butyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl Ethyl Ketone	147	18.0		ug/m3	20	4/25/2007
Methyl Isobutyl Ketone	ND	1.25		ug/m3	1	4/25/2007
Methyl tert-butyl ether	ND	0.550		ug/m3	1	4/25/2007
Methylene chloride	4950	431		ug/m3	810	4/25/2007
o-Xylene	0.441	0.662	J	ug/m3	1	4/25/2007
Propylene	ND	0.262		ug/m3	1	4/25/2007
Styrene	1.30	0.649		ug/m3	1	4/25/2007
Tetrachloroethylene	ND	1.03		ug/m3	1	4/25/2007
Tetrahydrofuran	ND	0.450		ug/m3	1	4/25/2007
Toluene	6.24	0.575		ug/m3	1	4/25/2007
trans-1,2-Dichloroethene	ND	0.604		ug/m3	1	4/25/2007
trans-1,3-Dichloropropene	ND	0.692		ug/m3	1	4/25/2007
Trichloroethene	0.710	0.218		ug/m3	1	4/25/2007
Vinyl acetate	ND	0.537		ug/m3	1	4/25/2007
Vinyl Bromide	ND	0.667		ug/m3	1	4/25/2007
Vinyl chloride	ND	0.390		ug/m3	1	4/25/2007

Qualifiers: B Analyte detected in the associated Method Blank E Value above quantitation range
H Holding times for preparation or analysis exceeded J Analyte detected at or below quantitation limits
JN Non-routine analyte. Quantitation estimated. ND Not Detected at the Reporting Limit
S Spike Recovery outside accepted recovery limits